## **?**SaferMe

# **Demolition toolbox talk**

A simple, 5 minute outline of what to cover in a toolbox talk on Demolition.



#### Download a Demolition toolbox talk pdf

The potential risk of serious injury during demolition projects is high. People at risk include employees, contractors, and the public. Demolition workers have a duty under the Health and Safety at Work Act to work safely. Therefore, demolition work should be planned carefully so that all risks can be managed appropriately.

## Why run a Demolition Toolbox Talk?

- Prevent unnecessary injury from demolition hazards by improving awareness and training
- Assist with understanding of legislative aspects and standards
- Fewer injuries mean higher productivity

#### Hazard identification

Common hazards associated with demolition works include:

- Dust
- Noise
- Fire
- Falling/flying debris
- Fall from heights
- Collapse of structure
- Hazardous substances
- Heavy machinery movements

#### Before starting a job, a site should be inspected for:

- Asbestos-containing materials and other toxic substances, e.g. lead
- Polychlorinated chlorinated biphenyls (PCBs) in lighting or electrical fittings
- Persistent organic pollutants (POP) on site
- Flammable substances
- Power lines and other electric cables
- Tensioned concrete structures that might collapse when tensioned wires are cut
- Gas supply lines and other compressed gas sources
- Biological hazards, such as sewage, needles, and animal/ bird faeces
- Underground tanks, pits, and basements
- Unsafe/compromised structures
- Traffic conditions

#### Asbestos (New Zealand information)

If a structure was constructed pre-2000, or if asbestos has been identified or is likely to be identified, the Asbestos Regulations 2016 require any asbestos or asbestoscontaining materials be removed before demolition begins (unless some demolition is required for access).

Note: most countries will have relevant legislation managing the asbestos on demolition sites.

#### Hierarchy of controls:

To manage hazards, apply the following hierarchy of controls:

- Elimination
- Substitution
- Isolation e.g., fencing off demolition sites and maintaining clear collapse zones.
- Engineering e.g., use of long reach excavators
- Administration e.g., induction, training, safety and demolition plans
- PPE e.g., safety footwear, hard hats

#### **Record keeping and training**

Maintain good record keeping, such as pre-demolition checklists, hazard registers, and task analysis/job-safety analysis forms. Make sure staff have the correct licenses and training to use specific plant and tools.

#### PPE

- Safety glasses, safety helmets, gloves, appropriate footwear
- Respiratory protection
- Hearing protection
- Protective clothing

The PCBU has a duty to train staff in the correct: selection, use, fitting, inspection, maintenance, and storage of PPE.

Respirators should be fit-tested.

#### Key takeaways:

- Make sure that there is a demolition plan in place.
- Identify all hazards on site and make sure appropriate controls are in place.
- Asbestos must be removed.
- Make sure workers have the required training, including for PPE.

See all our toolbox talk topics here

#### **Contact us**

US 512 846-3011 AU 02 5104 6116 NZ 09 886 3309

#### About

About Us Careers Blog Help Centre API Docs Media Enquiries Toolbox Talk Topic Tool

### Legal

Terms and Conditions Privacy Policy Account Owner Terms

#### Social



Copyright SaferMe Limited 2015 - 2022