



## 230 and 240 The Donway West, Toronto, ON

M3B 2V8

Hydrogeological Investigation

**Client:**

*Donway Co-operative Development Corporation*

**Attention:**

Mr. Geoffrey McGrath, Director of Development

**Type of Document:**

Final Report

**Project Name:**

230 The Donway West, Toronto, Ontario

**Project Number:**

BRM-00607375-A0

EXP Services Inc.

1595 Clark Boulevard

Brampton, ON, L6T 4V1

t: 905.793.9800

f: 905.793.0641

**Date Submitted:**

2019-09-23

Revision 1: May 28, 2021

Revision 2: October 20, 2021

Revision 3: January 13, 2022

Revision 4: October 31, 2023

Project Number: BRM- 00607375-A0  
 Date: September 23, 2019  
 Revision 1: May 28, 2021  
 Revision 2: October 20, 2021  
 Revision 3: January 13, 2022  
 Revision 4: October 31, 2023

## Table of Contents

- 1. Introduction ..... 3
  - 1.1 Project Description..... 3
  - 1.2 Project Objectives ..... 3
  - 1.3 Scope of Work ..... 3
  - 1.4 Review of Previous Reports ..... 4
- 2. Hydrogeological Setting..... 5
  - 2.1 Regional Setting ..... 5
    - 2.1.1 Regional Physiography ..... 5
    - 2.1.2 Regional Geology and Hydrogeology ..... 5
    - 2.1.3 Existing Water Well Survey ..... 5
  - 2.2 Site Setting ..... 6
    - 2.2.1 Site Topography ..... 6
    - 2.2.2 Local Surface Water Features ..... 6
    - 2.2.3 Local Geology and Hydrogeology..... 6
- 3. Results..... 9
  - 3.1 Monitoring Well Details ..... 9
  - 3.2 Water Level Monitoring ..... 9
  - 3.3 Hydraulic Conductivity Testing..... 11
  - 3.4 Groundwater Quality ..... 12
- 4. Dewatering Assessment ..... 14
  - 4.1 Dewatering Flow Rate Estimate and Zone of Influence ..... 14
  - 4.2 Cooper-Jacob’s Radius of Influence..... 15
  - 4.3 Stormwater ..... 15
  - 4.4 Results of Dewatering Rate Estimate..... 16
    - 4.4.1 Construction Dewatering Rate Estimate ..... 16
    - 4.4.2 Post-Construction Dewatering Rate Estimate ..... 17
  - 4.5 MECP Water Taking Permit..... 18



Project Number: BRM- 00607375-A0  
 Date: September 23, 2019  
 Revision 1: May 28, 2021  
 Revision 2: October 20, 2021  
 Revision 3: January 13, 2022  
 Revision 4: October 31, 2023

4.5.1 Short-Term Discharge Rate (Construction Phase) ..... 18

4.5.2 Long-Term Discharge Rate (Post Construction Phase) ..... 18

6. Environmental Impact ..... 20

6.1 Surface Water Features ..... 20

6.2 Groundwater Sources ..... 20

6.3 Geotechnical Considerations ..... 20

6.4 Groundwater Quality ..... 20

6.5 Well Decommissioning..... 21

7. Conclusions and Recommendations..... 22

8. Limitations ..... 24

9. References ..... 25

**List of Figures**

- Figure 1: Site Location Plan
- Figure 2: Surficial Geology Map
- Figure 3: MECP Water Well Record Map
- Figure 4: Borehole/Monitoring Well Location Plan
- Figure 5A: Cross Section A – A’
- Figure 5B: Cross Section B – B’
- Figure 6: Groundwater Contour Plan for Intermediate Water-Bearing Zone

**List of Appendices**

- Appendix A – MECP WWR Summary Table
- Appendix B – Borehole Logs
- Appendix C – SWRT Procedures and Results
- Appendix D – Laboratory Certificates of Analysis
- Appendix E – Construction (Short-Term) and Post-Construction (Long-Term) Flow Rate Calculations
- Appendix F – Architectural Drawings



*Project Number: BRM- 00607375-A0  
Date: September 23, 2019  
Revision 1: May 28, 2021  
Revision 2: October 20, 2021  
Revision 3: January 13, 2022  
Revision 4: October 31, 2023*

## 1. Introduction

### 1.1 Project Description

EXP Services Inc. (EXP) was retained by Donway Co-operative Development Corporation to prepare a Hydrogeological Investigation Report associated with the proposed development located at 230 and 240 The Donway West, Toronto, Ontario (hereinafter referred to as the 'Site').

The Site is currently occupied by a church and the Brighton School that leases a portion of the property. The Site covers an area of approximately 2.55 acres. It is our understanding that the Site is to be re-developed. The proposed development plan comprises a six (6)-storey residential medium-rise structure with three (3) levels of underground parking, which will include an integrated church. The Site location plan is shown on Figure 1.

EXP conducted a Preliminary Geotechnical Investigation and Environmental Site Assessment for the Site in conjunction with this investigation. The pertinent information gathered from the noted investigations is utilized for this report.

### 1.2 Project Objectives

The main objectives of the Hydrogeological Investigation are as follows:

- Establish the local hydrogeological settings within the Site;
- Access short-term dewatering flow rates for the construction phase, as well as the potential impacts;
- Assess long-term foundation sub-drain flow discharge volumes for the post-construction phase;
- Assess groundwater quality;
- Prepare a Hydrogeological Investigation Report;

### 1.3 Scope of Work

To achieve the objectives of this Hydrogeological Investigation, EXP has completed the following scope of work:

- Reviewed available geological and hydrogeological information for the Site;
- Developed and conduct Single Well Response Tests (SWRTs) on monitoring wells to assess hydraulic conductivities of the saturated soils at the Site;
- Collected one (1) groundwater sample for analyses of the City of Toronto's Sanitary and Storm Sewer Use By-Law parameters;
- Evaluated the information collected during the field investigation program, including borehole geological information, SWRT results, groundwater level measurements and groundwater water quality;
- Prepared site plans, cross-sections, geological mapping, and groundwater contour mapping for the Site;
- Estimated construction dewatering flow rates (short-term);
- Provided preliminary estimates for sub-drain discharge volumes (long-term);
- Assessed potential impacts and recommend mitigation measures;
- Completed nine (9) rounds of groundwater measurements at all monitoring wells as part of a three (3) month-monitoring program required by the City of Toronto;

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

- Provided recommendations on the Ministry of Environment, Conservation and Parks (MECP) Water Taking Permits and the City of Toronto's Sewer Discharge Agreements (SDA) for the construction and post-construction phases; and
- Prepared a Hydrogeological Investigation Report.

The hydrogeological investigation was prepared in accordance with the Ontario Water Resources Act, Ontario Regulation 387/04, and Toronto Municipal Code 681-Sewers. The scope of work outlined above is prepared to assess dewatering and does not include a review of Environmental Site Assessments (ESA).

## 1.4 Review of Previous Reports

The following reports were reviewed as part of this Hydrogeological Investigation:

- EXP Services Inc. (October 15, 2021), Supplementary Geotechnical Investigation, Proposed Mid-Rise Residential Development, 230 The Donway West, Toronto, ON, prepared for Donway Co-operative Development Corporation.
- EXP Services Inc. (September 6, 2019), Geotechnical Investigation, Proposed Mid-Rise Residential Development, 230 The Donway West, Toronto, ON, prepared for Donway Co-operative Development Corporation.
- EXP Services Inc. (March 25, 2019), Phase Two Environmental Site Assessment, 230 The Donway West, Toronto, ON, prepared for Donway Co-operative Development Corporation.

Project Number: BRM- 00607375-A0  
 Date: September 23, 2019  
 Revision 1: May 28, 2021  
 Revision 2: October 20, 2021  
 Revision 3: January 13, 2022  
 Revision 4: October 31, 2023

## 2. Hydrogeological Setting

### 2.1 Regional Setting

#### 2.1.1 Regional Physiography

The Site is located within a physiographic region named the South Slope, and the physiographic landform is known as the Till Plains. The South Slope lies between the Peel Plain in the north and the Iroquois Plain to the south (Chapman & Putnam, 2007). The topography of the South Slope is relatively flat with a gradual slope to the south, toward Lake Ontario.

#### 2.1.2 Regional Geology and Hydrogeology

The surficial geology can be described as stone-poor, carbonated-derived silty to sandy till (Ministry of Northern Development and Mines, 2012). The surficial geology of the Site and surrounding areas is shown on Figure 2.

According to the Oak Ridges Moraine Groundwater Program (ORMGP, 2019) online mapping, the overburden within the Site boundary and surroundings is up to 122 meters thick. The subsurface stratigraphy of the Site from top to bottom can be described in the following sequence (TRCA, 2009 and ORMGP, 2019):

- **Halton Till:** This lithologic unit typically consists of sandy silt to clayey silt till interbedded with silt, clay, sand and gravel. Top elevation of this unit within the proposed development area is only shown on the southwest portion of the Site, but the top elevation has not been specified.
- **Oak Ridges Moraine:** This geology unit mainly consists of interbedded fine-grained sand and silt deposits where coarse-grained sand and gravel along with clay laminae are locally reported. Top elevation of this unit within the proposed development area approximately ranges from 140 masl to 141 masl.
- **Newmarket Till:** This lithologic unit mainly consist of a massive and dense silty sand unit. Top elevation of this unit within the Site boundary is approximately at 136 masl.
- **Thorncliffe Formation:** This formation generally consists of glaciofluvial (sand, silty sand) or glaciolacustrine deposits (silt, sand, pebbly silt and clay). Top elevation of this geology unit is approximately at 131 masl.
- **Sunnybrook Formation:** This lithologic unit predominately consists of silt and clay. Top elevation of this geology unit is mapped within the proposed development area is approximate at 121 masl.
- **Scarborough Formation:** This geological unit consists of peat sand overlaying silt and clay deposits. Top elevation of this unit is within the proposed development area is approximately at 116 masl. (Oak Ridge Moraine Groundwater Program, 2018).
- **Georgian Bay Formation:** Bedrock primarily consists of interbedded shale, limestone, dolostone, and siltstone of Upper Ordovician age (Ministry of Northern Development and Mines, 2012). Top of this unit within the proposed development is approximately at 20 masl.

Regional groundwater across the area is expected to flow southeast, towards Lake Ontario (ORMGP, 2019). Local deviation from the regional groundwater flow direction may occur in response to changes in topography and/or soils, as well as the presence of surface water features and/or existing subsurface infrastructure.

#### 2.1.3 Existing Water Well Survey

Water Well Records (WWRs) from the database maintained by the Ministry of the Environment, Conservation and Parks (MECP) were reviewed to determine the number of wells present within a 500-m radius of the Site boundaries.

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

The MECP WWR database indicates that a total of twenty-five (25) records exist within a 500-m radius from the Site centroid. No well records are found onsite. The locations of the MECP WWRs are shown on Figure 3. A summary of the WWR is included in Appendix A.

The database indicates that the offsite wells are at an approximate distance of two-hundred and ninety-eight (298) m or greater from the Site centroid. All offsite wells were reportedly identified as monitoring and observation wells, test holes, abandoned and/or listed with unknown use. The reported depth to water table ranged from 1.0 to 8.5 meters below ground surface (mbgs).

## 2.2 Site Setting

### 2.2.1 Site Topography

The Site is in an urbanized area. The topography is considered relatively flat, with a gradual northeasterly slope towards the Don River. As indicated on the borehole logs included in Appendix B, the surface elevation of the Site approximately ranges from 141.41 to 142.85 meters above mean sea level (masl).

### 2.2.2 Local Surface Water Features

The Site is located within the Don River Watershed. No surface water features exist onsite. The nearest surface water feature is a small tributary of the Don River East Branch, located approximately 400 meters northeast of the Site boundary. The Don River East Branch is approximately 770 meters northeast of the Site. Roughly 1,1 km southwest flows Wilket Creek, a tributary of the Don River West Branch. Lake Ontario is approximately 8.8 kilometers southeast of the Site boundary.

### 2.2.3 Local Geology and Hydrogeology

A summary of subsurface soil stratigraphy is provided in the following paragraphs. The soil descriptions are based on the Geotechnical Investigation report (EXP, 2019) and they are summarized for the hydrogeological interpretations. As such, the information provided in this section should not be used for the construction design purposes.

The detailed soil profiles encountered in each borehole and the results of moisture content determinations are presented on the attached borehole logs (Appendix B). The interpreted geological cross-sections are also presented on Figures 5A and 5B. It should be noted that the soil boundaries indicated on the borehole logs are inferred from non-continuous sampling and observations during drilling. These boundaries are intended to reflect approximate transition zones for the purpose of hydrogeological investigation and should not be interpreted as exact planes of geological change.

The "Notes on Sample Description" preceding the borehole logs form an integral part of the noted borehole logs and should be read in conjunction with this report. The following is a brief description of the soil conditions encountered during the investigation.

Based on the results of the Geotechnical Investigations, the general subsurface soil stratigraphy consists of the following units:

#### **Asphalt**

Asphalt, about 40 to 115 mm thick, was encountered at the ground surface of Boreholes 1, 2 and 3.

As per the 2021 supplementary geotechnical investigation (EXP, 2021), Asphalt of about 75 mm in thickness was encountered at the ground surface of Boreholes 101, 108 and 109

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

## **Top Soil**

Topsoil cover of about 140 and 150 mm in thickness was encountered at the ground surface of Boreholes 4 and 5, respectively.

As per the 2021 supplementary geotechnical investigation (EXP, 2021), Topsoil cover of about 100 and 175 mm in thickness was encountered at the ground surface of Boreholes 102 to 107.

## **Fill**

Fill, comprising sand and gravel to clayey silt was encountered below the asphalt and topsoil at all borehole locations. The fill material contains a trace of gravel, some sand and occasional topsoil inclusions. Hydrocarbon odor was noted in some of the fill samples recovered from Borehole 6 which is in the former underground storage tank area. The fill has a moisture content ranging from about 11 to 20 percent of dry mass and extending to depths ranging from about 1.4 to 3.7 m below existing ground surface (El. ~141.5 to 138.2 m).

As per the 2021 supplementary geotechnical investigation (EXP, 2021), Fill, comprising sand and gravel to clayey silt was encountered below the asphalt and topsoil at all borehole locations. The fill material generally contains a trace of gravel, some sand and occasional topsoil inclusions. The fill has a moisture content ranging from about 9 to 22 percent of dry mass and extending to depths ranging from about 0.7 to 2.1 m below existing ground surface (El. ~141.7 to 138.9 m).

## **Sandy to Clayey Silt**

As per the 2021 supplementary geotechnical investigation (EXP, 2021), the fill was underlain by a sandy to clayey silt deposit at all borehole locations. This deposit contains a trace of gravel with a trace of wet sand seams. A trace of oxidized zones and silt seams were also noted in some of the recovered samples. This deposit is generally brown in colour and becoming grey with depth, has moisture contents of about 10 to 22 percent of dry mass and has a soft to hard consistency (recorded 'N'-value of 2 to 32). The sandy to clayey silt extends to depths ranging from about 4.5 to 10.5 m below existing ground surface (El. ~138.1 to 129.6 m).

## **Silty Sand to Sandy Silt Till**

The fill was underlain by a silty sand to sandy silt till deposit at all borehole locations. The silty sand to sandy silt till contains a trace of gravel, some clay with occasional wet sand seams. Clayey zones were noted in Boreholes 4 and 5 between 6 to 8 m depth. It is generally brown in color and becoming grey with depth. This deposit has moisture contents of about 8 to 24 percent of dry mass and is in a loose to very dense state of compactness (recorded 'N'-value of 6 to over 100). Boreholes 1, 2, 4, 5 and 6 were terminated in the silty sand to sandy silt till deposit at depths of about 8.2 to 12.8 m below existing ground surface (El. ~133.6 to 128.6 m).

As per the 2021 supplementary geotechnical investigation (EXP, 2021), a silty sand to sandy silt till deposit was encountered below the sandy to clayey silt at all borehole locations, except for boreholes 103, 104 and 106,. The silty sand to sandy silt till is brown to grey in colour, contains a trace of gravel, some clay with occasional wet sand seams. This deposit has moisture contents of about 7 to 11 percent of dry mass and is in a compact to very dense state of compactness (recorded 'N'-value of 10 to over 100).

## **Clayey Silt Till**

In Borehole 3, a clayey silt till deposit was encountered below the silty sand to sandy silt till at about 11.5 m below existing ground surface. The clayey silt till is grey in color and contained a trace of gravel and sand pockets. With recorded 'N'-value of



*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

82 to over 100, the clayey silt till has a hard consistency. The clayey silt till deposit extended to the termination depth of about 15.7 m below existing grade in Borehole 3 (El. ~126.7 m).

As per the 2021 supplementary geotechnical investigation (EXP, 2021), a clayey silt till deposit was encountered below the sandy to clayey silt in Boreholes 103, 104 and 106; and below the silty sand to sandy silt till in Boreholes 102, 102, 105, 107, 108 and 109. The clayey silt till is grey in colour and contained a trace of gravel, a trace of sand and some silt seams. With recorded 'N'-value of 25 to over 100, the clayey silt till has a very stiff to hard consistency. The clayey silt till deposit extended to about 20 m below existing grade in Borehole 103 (El. ~122.8 m). The remaining boreholes were terminated in the clayey silt till between depths of about 15.7 and 20.4 m below existing grade (El. ~126.9 to 120.6 m).

### **Silty Sand**

As per the 2021 supplementary geotechnical investigation (EXP, 2021), the clayey silt till deposit encountered in Borehole 103 was underlain by a silty sand deposit. This deposit is grey in colour and is in a very dense state of compactness with recorded 'N'-value of over 100. Borehole 103 was terminated at a depth of about 20.2 m below existing grade (El. ~122.5 m).

Project Number: BRM- 00607375-A0  
Date: September 23, 2019  
Revision 1: May 28, 2021  
Revision 2: October 20, 2021  
Revision 3: January 13, 2022  
Revision 4: October 31, 2023

## 3. Results

### 3.1 Monitoring Well Details

The onsite network of monitoring wells, which was installed as part of the Geotechnical and Environmental Investigations at the Site, consists of the following:

- A total of two (2) shallow wells, including BH/MW 2 and BH/MW 6 were installed to an approximate depth range from 6.2 to 7.6 mbgs;
- A total of three (3) intermediate wells, including BH/MW 1, BH/MW 4, and BH/MW 6 were installed to an approximate depth range from 11.5 to 12.2 mbgs;
- Three (3) deep monitoring wells, including BH/MW 3, BH/MW 101, and BH/MW 106 were installed to an approximate depth ranged from 15.3 to 19.7 mbgs;
- Each monitoring well is equipped with a 50-mm diameter PVC casing with three (3)-meter long screen;
- Each monitoring wells is covered with a flush mount well protective casing.

Borehole logs and monitoring well installation details are provided in Appendix B. The monitoring well locations are outside of the existing building (s) and are shown on Figure 4.

### 3.2 Water Level Monitoring

As part of the Hydrogeological Investigation, static water levels in the monitoring wells were recorded in nine (9) monitoring events between August 8 and October 6, 2021. A summary of all static water level data as it relates to the elevation survey is provided in Table 3-1 below.

The groundwater elevations recorded for the shallow wells ranged from 139.60 (2.27 mbgs at BH/MW 6 on August 27, 2019) masl to 141.86 masl (0.99 mbgs at BH/MW 2 on August 9, 2019). The groundwater elevations recorded for the intermediate wells ranged from 131.75 masl (9.66 mbgs at BH/MW 5 on August 13, 2019) to 142.01 masl (0.56 mbgs at BH/MW 1 on November 1, 20219). The groundwater elevations recorded for deep wells ranged from 123.62 masl (19 mbgs at BH/MW 101 on September 28, 2021) to 135.13 masl (7.27 mbgs at BH/MW 3 on September 20, 2021).

One (1) map shows onsite groundwater contours for the intermediate water-bearing zone (Figure 6). Accordingly, the groundwater flow direction in the intermediate zone is interpreted to be northwest of the Site. The inferred local groundwater flow direction is consistent with the ORMGP online mapping. According to ORMGP (2019), groundwater flow diverts northeast from the Site boundary, and eventually discharges into the Don River East Branch.

A downward hydraulic gradient is inferred when comparing the measured groundwater elevations of the shallow, intermediate and deep water-bearing zones.

It should be noted that groundwater levels are expected to show seasonal fluctuations and vary in response to prevailing climate conditions; this may also affect the direction and rate of flow. It is recommended to conduct seasonal groundwater level measurements to provide more information on seasonal groundwater level fluctuations.

Project Number: BRM- 00607375-A0

Date: September 23, 2019

Revision 1: May 28, 2021

Revision 2: October 20, 2021

Revision 3: January 13, 2022

Revision 4: October 26, 2023

**Table 3-1: Summary of Measured Groundwater Elevations**

Monitoring Well ID	Ground Surface Elevation (masl)	Approximate Full Well Depth (mbgs)	Depth	8-Aug-19	13-Aug-19	27-Aug-19	23-Sep-19	15-Oct-19	1-Nov-19	20-Sep-21	28-Sep-21	6-Oct-21
BH/MW1	142.56	12.2	mbgs	1.02	1.16	1.18	1.13	1.31	0.56	1.54	1.03	1.00
			masl	141.55	141.40	141.38	141.44	141.25	142.01	141.02	141.53	141.56
BH/MW2	142.85	6.2	mbgs	0.99	1.21	1.31	1.39	1.51	Inaccessible	1.63	1.40	1.35
			masl	141.86	141.64	141.54	141.46	141.34		141.22	141.45	141.50
BH/MW3	142.39	15.2	mbgs	9.75	<u>12.91</u>	9.18	9.15	8.82	8.31	7.27	7.41	7.36
			masl	132.64	<u>129.48</u>	133.21	133.24	133.57	134.08	135.13	134.98	135.03
BH/MW4	142.53	11.5	mbgs	2.09	2.28	1.58	1.84	1.82	1.68	2.25	2.32	2.26
			masl	140.44	140.25	140.96	140.70	140.71	140.85	140.29	140.21	140.27
BH/MW5	141.41	12.2	mbgs	1.57	<u>9.66</u>	1.60	1.62	1.62	1.24	1.86	1.74	1.76
			masl	139.84	<u>131.75</u>	139.82	139.79	139.79	140.17	139.56	139.67	139.65
BH/MW6	141.86	7.6	mbgs	2.12	2.26	2.27	2.34	2.39	2.61	2.81	2.56	2.47
			masl	139.74	139.61	139.60	139.52	139.47	139.25	139.06	139.30	139.39
BH/MW 101	142.62	19.7	mbgs	-	-	-	-	-	-	18.51	19.00	18.20
			masl	-	-	-	-	-	-	124.11	123.62	124.42
BH/MW 106	142.43	19.2	mbgs	-	-	-	-	-	-	16.24	16.73	14.44
			masl	-	-	-	-	-	-	126.20	125.70	127.99

**Notes:**

mbgs: meters below ground surface

masl: meters above mean sea level

\* Based on field measurements

Underlined: indicates that groundwater level did not reach static level after well development. The hydraulic conductivity tests in the corresponding wells were completed during the consecutive event when the groundwater level was at the static level (refer to section 3.3 of this report).

Project Number: BRM- 00607375-A0

Date: September 23, 2019

Revision 1: May 28, 2021

Revision 2: October 20, 2021

Revision 3: January 13, 2022

Revision 4: October 26, 2023

### 3.3 Hydraulic Conductivity Testing

A total of eight (8) Single Well Response Tests (SWRT's) were completed in all monitoring wells onsite (BH/MW1 through BH/MW 6 on August 13 and 27 of 2019, as well as BH/MW 101 and BH/MW 106 on September 28 and October 6, 2021, respectively). The tests were completed to estimate the saturated hydraulic conductivity (K) of the soils at the well screen depths.

The static water level within each monitoring well was measured prior to the start of testing. In advance of performing SWRTs, each monitoring well underwent development to remove fines introduced into the screens following construction. The development process involved purging of the monitoring wells to induce the flow of fresh formation water through the screen. Each monitoring well was permitted to fully recover prior to performing SWRTs.

Hydraulic conductivity values were calculated from the SWRT data as per Hvorslev's solution included in the AQTESOLV Pro. V.4.5 software package. The semi-log plots for normalized drawdown versus time are included in Appendix C.

A summary of the hydraulic conductivity (K) values estimated from the SWRTs are provided in Table 3-2 below.

**Table 3-2: Summary of Hydraulic Conductivity Testing**

Monitoring Well	Well Depth (mbgs)*	Screen Interval (mbgs)		Soil Formation Screened **	Estimated Hydraulic Conductivity (m/s)
		From	To		
BH/MW 1	12.2	9.2	12.2	Silty Sand to Sandy Silt Till	$4.2 \times 10^{-8}$
BH/MW 2	6.2	3.2	6.2	Silty Sand to Sandy Silt Till	$1.6 \times 10^{-7}$
BH/MW 3	15.2	12.3	15.2	Clayey Silt Till	$9.0 \times 10^{-9}$
BH/MW 4	11.5	7.8	11.5	Silty Sand to Sandy Silt Till	$4.8 \times 10^{-8}$
BH/MW 5	12.2	8.7	12.2	Silty Sand to Sandy Silt Till	$2.5 \times 10^{-7}$
BH/MW 6	7.6	4.6	7.6	Silty Sand to Sandy Silt Till	$2.1 \times 10^{-8}$
BH/MW 101	19.7	16.7	19.7	Clayey Silt Till	$2.1 \times 10^{-7}$
BH/MW 106	19.2	16.2	19.2	Clayey Silt Till	$4.9 \times 10^{-7}$
<b>Highest Estimated K Value for shallow and deep wells</b>					$4.9 \times 10^{-7}$
<b>Highest Estimated K Value for shallow wells</b>					$2.5 \times 10^{-7}$
<b>Arithmetic Mean of Estimated K Values</b>					$1.5 \times 10^{-7}$
<b>Geometric Mean of Estimated K Values</b>					$7.9 \times 10^{-8}$

**Notes:**

mbgs: meters below ground surface

\* Based on field measurements

\*\* Based on geotechnical borehole logs

Project Number: BRM- 00607375-A0

Date: September 23, 2019

Revision 1: May 28, 2021

Revision 2: October 20, 2021

Revision 3: January 13, 2022

Revision 4: October 31, 2023

SWRTs provide estimates of K for the geological formation in the immediate media zone surrounding the well screens and may not be representative of bulk formation hydraulic conductivity. As shown in Table 3-2, the highest K for the tested water-bearing zones is estimated to be  $4.9 \times 10^{-7}$  m/s, and the arithmetic and geometric means of the K values are  $1.2 \times 10^{-7}$  and  $7.9 \times 10^{-8}$  m/s, respectively.

### 3.4 Groundwater Quality

To assess the suitability for discharge of pumped groundwater to the sewer system owned by the City of Toronto during dewatering activities, two (2) groundwater samples were collected from monitoring wells BH/MW 2 on August 13, 2019 and BH/MW 106 on October 7, 2021, using a peristaltic pump and a bailer, respectively. Prior to the collection of noted water sample, approximately three (3) standing well volumes of groundwater were purged from the noted well.

The samples were collected unfiltered and placed into pre-cleaned laboratory-supplied vials and/or bottles provided with analytical test group specific preservatives, as required. Dedicated nitrile gloves were used during sample handling. The groundwater samples were submitted for analysis to Bureau Veritas, a CALA certified independent laboratory in Mississauga, Ontario.

In addition to the results from the water samples collected for this hydrogeological study, the water quality results of the groundwater samples collected for ESA were also compared to the Sanitary and Storm Sewer Use By-Law guidelines. It should be mentioned that the ESA water samples were collected according to the MOECP's protocols.

The laboratory Certificate of Analysis (CofA) showed that all parameters conform the Sanitary and Combined Sewer Use By-Law limits (Table 1).

When compared to the Storm Sewer Use By-Law Limits (Table-2), the concentration of Total Manganese (Mn) exceeded the Storm Sewer Use By-Law criteria.

Based on the water quality results for one (1) water sample collected for the ESA, the concentrations of all tested parameters were reported below both, Sanitary and Storm Sewer Use By-Law limits.

Table 3-3 shown below summarizes the concentrations of the parameters exceeded the Sanitary Sewer Use By-Law (Table-1) and Storm Sewer By-Law (Table-2) criteria. The laboratory CofA is provided in Appendix D.

**Table 3-3: Summary of Analytical Results**

Parameter	City of Toronto Sanitary and Combined Sewer Discharge Limit (Table 1)	City of Toronto Storm Sewer Discharge Limit (Table 2)	Concentration	
			BH/MW 2 August 13, 2019	BH/MW 106 October 7, 2021
Total Manganese (Mn) (µg/L)	5,000	50	<b>140</b>	<b>65</b>

**Note:**

**Bold:** indicates the concentration exceeded the Storm Sewer By-Law Limit.

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

For the short-term dewatering system (construction phase), it is anticipated that TSS levels and some other parameters (for example, Total Manganese) in the pumped groundwater may become elevated and exceed both, Sanitary and Storm Sewer Use By-Law limits. To control the concentration of TSS and associated metals, it is recommended that a suitable treatment method be implemented (filtration or decantation facilities and/ or any other applicable treatment system) during construction dewatering activities to discharge to the applicable sewer system. The specifications of the treatment system will need to be adjusted to the reported water quality results by the treatment contractor/process engineer.

For long-term dewatering (post-construction), the water is suitable to be released into the Sanitary Sewer system without treatment, However, the pumped water is unsuitable to be discharged into the Storm Sewer system without implementing a suitable pre-treatment system, as required.

It is noted that the water quality results presented in this report may not be representative of the long-term groundwater quality conditions. As such, regular water quality monitoring is recommended for the post-construction phase as required by the City.

An agreement to discharge to the sewers owned by the City of Toronto will be required prior to releasing dewatering effluent.

The Environmental Site Assessment Report(s) should be reviewed for more information on the groundwater quality conditions at the Site.

Project Number: BRM- 00607375-A0

Date: September 23, 2019

Revision 1: May 28, 2021

Revision 2: October 20, 2021

Revision 3: January 13, 2022

Revision 4: October 31, 2023

## 4. Dewatering Assessment

It is our understanding that the proposed development plan comprises a six (6)-storey residential medium-rise structure with three (3) levels of underground parking. For this assessment, it was assumed that the proposed construction plans include an excavation with a temporary shoring system (i.e. soldier pile and lagging), extending to the Site boundaries. EXP should be retained to review the assumptions outlined in this section, should the proposed shoring design change. Table 4-1 presents the assumptions used to calculate the dewatering rate for the Site.

Based on the geotechnical investigation report (EXP, 2019), the foundations of the proposed structure are anticipated to rest on the native compact silty sand to sandy silt till. Further, the proposed structure is projected to be supported on either conventional strip and spread footings or raft foundation (EXP, 2019).

**Table 4-1 Dewatering Estimate Assumptions**

Input Parameter		Assumption for P2	Notes
Ground Surface Elevation		142.85 masl	Highest ground surface elevation shown on the geotechnical borehole logs (EXP, 2021)
Groundwater Elevation		142.01 masl	The highest representative groundwater elevation measured across the Site at BH/MW 1 on November 1, 2021.
Lowest Top Slab Elevation		133.3 masl	It is anticipated to be 9.55 mbgs
Lowest Foundation Elevation		131.8 masl	Assumed to be 1.5 m below top of slab elevation.
Dewatering Elevation Target	Short-Term	130.8 masl	Assumed to be approx. 1 m below the lowest foundation elevation.
	Long-Term	132.8 masl	
Hydraulic Conductivity (K)		$1.5 \times 10^{-7}$ m/s	Arithmetic mean of estimated K-value.

Pits (elevator, sump pits) are assumed to have depth of excavation with the same dewatering target as main excavation; deeper pits may require localized dewatering and revised dewatering estimates.

### 4.1 Dewatering Flow Rate Estimate and Zone of Influence

The Dupuit-Forcheimer equation for radial flow to both sides of an excavation through an unconfined aquifer resting on a horizontal impervious surface was used to obtain a flow rate estimate. Dewatering flow rate is expressed as follows:

$$Q_w = \frac{\pi K(H^2 - h^2)}{\ln \left[ \frac{R_o}{r_e} \right]}$$

$$r_e = \frac{a+b}{\pi} \quad R_o = R_{cj} + r_e$$

Project Number: BRM- 00607375-A0

Date: September 23, 2019

Revision 1: May 28, 2021

Revision 2: October 20, 2021

Revision 3: January 13, 2022

Revision 4: October 31, 2023

Where:

$Q_w$	= Rate of pumping ( $m^3/sec$ )
$X$	= Length of excavation (m)
$K$	= Hydraulic conductivity (m/sec)
$H$	= Hydraulic head beyond the influence of pumping (static groundwater elevation) (m)
$h$	= Hydraulic head above the base of aquifer in an excavation (m)
$R_o$	= Radius of Influence (m)
$R_{cj}$	= Cooper Jacob Radius of Influence (m)
$r_e$	= Equivalent perimeter (m)
$a$	= Length of the excavation area (m)
$b$	= Width of the excavation area (m)

It is expected that the initial dewatering rate will be higher to remove groundwater from within the overburden formation. The dewatering rates are expected to decrease once the target water level is achieved in the excavation footprint as groundwater will have been removed, primarily from storage, resulting in lower seepage rates into the excavation.

It is expected that the initial dewatering rate will be higher to remove groundwater from within the overburden formation. The dewatering rates are expected to decrease once the target water level is achieved in the excavation footprint as groundwater will have been removed, primarily from storage, resulting in lower seepage rates into the excavation.

## 4.2 Cooper-Jacob's Radius of Influence

The radius of influence ( $R_{cj}$ ) for the construction dewatering was calculated based on Cooper-Jacob equation. This equation is used to predict the distance at which the drawdown resulting from pumping is negligible. The estimated radius of influence due to pumping is based on Cooper-Jacob formula as shown below. The calculations are provided in Appendix E.

$$R_{cj} = \sqrt{2.25KDt/S}$$

Where:

$R_{cj}$	= Estimated radius of influence (m)
$D$	= Aquifer thickness (original saturated thickness) (m)
$K$	= Hydraulic conductivity (m/sec)
$S$	= Storage coefficient
$t$	= Duration of pumping (s)

## 4.3 Stormwater

Additional pumping capacity may be required to maintain dry conditions within the excavation during and following significant precipitation events. Therefore, the dewatering rates at the Site should also include removing stormwater from the excavation.

A 15 mm precipitation event was utilized for the estimate. Given that the total area of the excavation is approximately 10,140  $m^2$  the estimated stormwater volume to be collected in the excavation is approximately 152  $m^3$  for a 15 mm precipitation event. The calculations for the stormwater estimate are included in Appendix E.



Project Number: BRM- 00607375-A0

Date: September 23, 2019

Revision 1: May 28, 2021

Revision 2: October 20, 2021

Revision 3: January 13, 2022

Revision 4: October 31, 2023

It is noted that a two (2) year storm event over a 24-hour period is approximately 57 mm. During large precipitation events, the water should be retained onsite to not exceed the allowable water taking and discharge limits as necessary.

## 4.4 Results of Dewatering Rate Estimate

### 4.4.1 Construction Dewatering Rate Estimate

For this assessment, it was assumed that the proposed construction plans include an excavation with shoring extending to the Site boundaries. EXP should be retained to review the assumptions outlined in this section, should the assumed shoring design change. Short-term (construction) dewatering calculations are presented in Appendix E. Based on the assumptions provided in this report, the results of the dewatering rate estimate are summarized in Table 4-2

**Table 4-2 Summary of Dewatering Flow Rate Estimate**

Peak Dewatering Flow Rate Including Rain Collection Volume and Zone of Influence		
Description	Units	Value
Estimated Short Term Dewatering Rate (without safety factor or precipitation)	L/day	73,000
From Precipitation Event of 15 mm in one day	L/day	152,000
With Factor of Safety of 2 (excluding Precipitation) for designs and budgeting	L/day	145,000
Without Factor of Safety (including Precipitation)	L/day	225,000
With Factor of Safety of 2 (including Precipitation)	L/day	298,000
Radius of Influence from sides of excavation	m	8

This peak dewatering flow rates accounts for accumulation of some precipitation, seasonal fluctuations in the groundwater table, flow from beddings of existing sewers, and variation in hydrogeological properties beyond those encountered during this study. This peak dewatering flow rate also provides additional capacity for the dewatering contractor.

Localized dewatering may be required for pits (elevator pits, sump pits) if they extend deeper than the dewatering target. Dewatering estimates should be reviewed once the pit dimensions are available.

It is noted that the maximum flow estimate equation calculated with a high K-value, provides a conservative estimate to account for higher-than-expected flow rates during the construction dewatering.

Please note that it is the responsibility of the contractor to ensure dry conditions are always maintained within the excavation at all costs.

Project Number: BRM- 00607375-A0

Date: September 23, 2019

Revision 1: May 28, 2021

Revision 2: October 20, 2021

Revision 3: January 13, 2022

Revision 4: October 31, 2023

#### 4.4.2 Post-Construction Dewatering Rate Estimate

It is our understanding that the development plan includes a permanent foundation sub-drain system that will ultimately discharge to the municipal sewer system if conventional footings are installed.

As of January 1, 2022, the foundation drainage policy from the City of Toronto prohibits post construction discharge of groundwater into the municipal sewer system.

The long-term dewatering was based on the same equations as construction dewatering shown in Section 4.1.

The calculation for the estimated flow to the future sub-drain system (with no cutoff walls) is provided in Appendix E. The dewatering target for the foundation drainage system is taken at 0.5 m below the lowest slab elevation.

The foundation drain analysis provides a flow rate estimate. Once the foundation drain is built, actual flow rate measurements of the sump discharge will be required to confirm the estimated flow rate.

Seasonal and daily fluctuations are expected. These estimates may be affected by hydrogeological conditions beyond those encountered at this time, fluctuations in groundwater regimes, surrounding Site alterations, and existing and future infrastructures.

For the design of shallow foundations without perimeter and/or foundation drainage system, shallower wells need to be considered to evaluate the shallow groundwater table. The hydrogeologist needs to be consulted during the design process.

**Table 4-3: Summary of Long-Term Dewatering Rate**

Long-Term Dewatering Flow Rate	Building with P3 (L/day)
Long-Term Dewatering Rate without Safety Factor	8,000
Long-Term Dewatering Rate with Safety Factor of 1.5 for design, budgeting and permitting	11,000

The long term dewatering rate of 11,000 L/day is same as before stated in the hydrogeological report dated January 13, 2022.

Intermittent cycling of sump pumps and seasonal fluctuation in groundwater regimes should be considered for pump specifications. A safety factor was applied to the flow rate to account for water level fluctuations due to seasonal changes.

These estimates assume that pits (elevator and/or sump pits) are made as watertight structures (without drainage), if their depths extend below the dewatering target, as previously stated. The dewatering assumptions are based on using shoring system without open cuts. Open cuts can act as preferential groundwater pathways in the long-term and cause foundation drainage volumes to increase.

The sub-drain rate estimate is based on the assumptions outlined in this report. Any variations in hydrogeological conditions beyond those encountered as part of this investigation may significantly influence the sub-drain discharge volumes.

Project Number: BRM- 00607375-A0

Date: September 23, 2019

Revision 1: May 28, 2021

Revision 2: October 20, 2021

Revision 3: January 13, 2022

Revision 4: October 31, 2023

## 4.5 MECP Water Taking Permit

### 4.5.1 Short-Term Discharge Rate (Construction Phase)

In accordance with the Ontario Water Resources Act, if the water taking for the construction dewatering will be more than 50 m<sup>3</sup>/day but less than 400 m<sup>3</sup>/day, then an online registration in the Environmental Activity and Sector Registry (EASR) with MECP is required. If groundwater dewatering rates exceed 400 m<sup>3</sup>/day, then an application for a Category 3 Permit to Take Water (PTTW) will be required from the MECP.

As of July 1, 2021, an amendment of O. Reg. 63/16 has come into effect and replaced the former subsection 7 (5) such that the water taking limit of 400,000 L/day would apply to groundwater takings of each dewatered work area only, excluding stormwater.

The maximum flow estimate, which was calculated with a representative K-value, provides a conservative estimate to account for higher-than-expected flow rates during construction dewatering. The dewatering estimate including a safety factor and excluding precipitation is stated below. The MECP construction dewatering rate excludes the precipitation amount and is the rate used for the permit application. Based on the MECP construction dewatering an EASR will be required to facilitate the construction dewatering program of the Site.

**Table 4-4: MECP Construction Dewatering Flow Rate**

Scenario	Building with P1 (L/day)
MECP Construction Dewatering Flow Rate <b>With Safety Factor of 2</b> (excluding rainwater collection)	145,000

A Discharge Plan (dewatering sketch, sewer discharge agreement) must be developed and applied for any discharges from the Site. Monitoring of both water quantity and water quality must be carried out for the entire duration of the construction dewatering phase. During this phase, the Discharge Plan and the daily water taking records must be available onsite.

The EASR, Discharge Plan, hydrogeological investigation report, and geotechnical assessment of settlements must also be available at the construction Site during the entire construction dewatering. EXP should be notified immediately about any changes to the construction dewatering schedule or design, since the EASR will need to be updated to reflect these modifications. Altogether, the hydrogeological report, EASR, Discharge Plan and geotechnical assessment constitute the Water Taking Plan which needs to be available onsite during the construction dewatering.

### 4.5.2 Long-Term Discharge Rate (Post Construction Phase)

In accordance with the Ontario Water Resources Act, if the water taking for the construction dewatering is more than 50,000 L/day, then an application for a Category 3 Permit to Take Water (PTTW) will be required from the MECP.

The maximum flow rate, which was calculated with a representative K-value, provides a conservative estimate to account for higher-than-expected flow rates during post-development dewatering. Based on the dewatering estimate of approximately 11,000 L/day (applying a safety factor of 1.5) for this project, no permit to take-water will be required for the post-development phase.

The safety factor for construction (short-term) dewatering is selected larger than for long-term to account for anticipated greater groundwater volumes during initial dewatering. The applied analytical formula is adequate for long-term (steady state) conditions as it omits specific yield and time dependency. When the formula is used for short-term conditions a larger safety

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

factor is recommended to cover a larger initial dewatering rate, which is required to remove stored groundwater. Moreover, a large initial construction dewatering rate is favorable, as it supports reducing the time to reach the dewatering target elevation.

*Project Number: BRM- 00607375-A0  
Date: September 23, 2019  
Revision 1: May 28, 2021  
Revision 2: October 20, 2021  
Revision 3: January 13, 2022  
Revision 4: October 31, 2023*

## 6. Environmental Impact

### 6.1 Surface Water Features

The Site is located within the Don River Watershed. No surface water features exist onsite. The nearest surface water feature is a small tributary of the Don River East Branch, located approximately 400 meters northeast of the Site boundary. The Don River East Branch is approximately 770 meters northeast of the Site. Roughly 1.1 km southwest flows Wilket Creek, a tributary of the Don River West Branch. Lake Ontario is approximately 8.8 kilometers southeast of the Site boundary.

Due to the limited extent of zone of influence and the large distance of the nearest surface water feature, no impacts to surface water features are expected during construction activities.

### 6.2 Groundwater Sources

Well Records from the MECP Water Well Record (WWR) Database were reviewed to determine the number of water supply wells present within a 500 m radius of the Site centroid. Given that the dewatering zone of influence, no dewatering related impact is expected on the water wells in the area.

### 6.3 Geotechnical Considerations

Under certain conditions, dewatering activities can cause settlements due to an increase of the effective stress in the dewatered soil. A letter related to geotechnical issues (i.e. settlement) as it pertains to the Site is recommended to be completed under a separate cover.

### 6.4 Groundwater Quality

It is our understanding that the potential discharge from the dewatering system during the construction will be directed to the municipal sewer system. As such, the quality of groundwater discharge is required to conform the City of Toronto Sewer Use By-Law.

Based on the water quality results for the water sample collected for ESA, the concentrations of all tested parameters were reported below both Sanitary and Storm Sewer Use By-Law limits. For the short-term dewatering system (construction phase), it is anticipated that TSS levels and some other parameters (for example, Total Manganese) in the pumped groundwater may become elevated and exceed both, Sanitary and Storm Sewer Use By-Law limits. To control the concentration of TSS and associated metals, it is recommended that a suitable treatment method be implemented (filtration or decantation facilities and/ or any other applicable treatment system) during construction dewatering activities to discharge to the applicable sewer system. The specifications of the treatment system will need to be adjusted to the reported water quality results by the treatment contractor/process engineer.

Dewatering (short and long-term) may induce migration of contaminants within the zone of influence and beyond due to changing hydraulic gradients, hydrogeological conditions beyond Site boundaries and preferential pathways in utility beddings etc. The water quality sampling conducted as part of this assessment was performed under static conditions. As a result, monitoring may be required during dewatering activities (short and long-term) to monitor potential migration, and this should be performed more frequently during early dewatering stages.

For the long-term dewatering (post-construction), the water is suitable to be released into the Sanitary Sewer system without a treatment system. However, the pumped water is unsuitable to be discharged into the Storm Sewer system without implementing an appropriate pre-treatment system as required.

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

It is noted that the water quality results presented in this report may not be representative of the long-term condition of groundwater quality onsite. As such, regular water quality monitoring is recommended for the post-construction phase as required by the City.

An agreement to discharge into the sewers owned by the City of Toronto will be required prior to discharging dewatering effluent.

The Environmental Site Assessment Report(s) should be reviewed for more information on the groundwater quality conditions at the Site.

## 6.5 Well Decommissioning

In conformance with Regulation 903 of the Ontario Water Resources Act, the installation and eventual decommissioning of any dewatering system wells or monitoring wells must be completed by a licensed well contractor. This will be required for all wells that are no longer in use.

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

## 7. Conclusions and Recommendations

Based on the findings of the Hydrogeological Investigation, the following conclusions and recommendations are provided:

- The laboratory Certificate of Analysis (CofA) showed that all parameters conform the Sanitary and Combined Sewer Use By-Law limits (Table 1).
- When compared to the Storm Sewer By-Law Limits (Table-2), the concentration of Total Manganese (Mn) exceeded the Storm Sewer Use By-Law criteria.
- Based on the assumptions outlined in this report, the estimated peak dewatering rate for proposed construction activities is approximately 298,000 L/day. This is the rate which will be required to be discharged to the municipal sewer system.
- Based on the assumptions outlined in this report, the estimated peak MECP dewatering rate for proposed construction activities is approximately 145,000 L/day. As the dewatering flow rate estimate is between 50,000 L/day and 400,000 L/day, an EASR will be required to facilitate the construction dewatering program for the Site.
- The long-term flow rate of the foundation sub-drain is estimated to be approximately 11,000 L/day. It is recommended that once the sub-drain system is in place, a flow meter be installed at the sump(s) to record daily discharge volumes during the commissioning stage of the system. Regular maintenance/cleaning of the sub-drain system is recommended to ensure its proper operation. Permit to take water will not be required for long-term discharge.
- The construction dewatering and long-term estimate of sub-drain discharge volumes are based on the assumptions outlined in this report, and any variations in hydrogeological conditions beyond those encountered as part of this investigation may significantly influence the discharge volumes.
- As per the MECP technical requirement for EASR, the geotechnical assessment of the stability of the soils due to water taking (ex: settlement, soil loss, subsidence etc.) is required. The water taking should not have unacceptable interference on soils and underground structures (foundations, utilities etc.). A letter related to geotechnical issues as it pertains to the Site is required to be completed under a separate cover.
- The EASR registration allows construction dewatering discharge of up to 400,000 L/day. A Discharge Plan (dewatering sketch, sewer discharge agreement) must be developed and applied for any discharges from the Site. The Discharge Plan and monitoring for both water quantity and water quality must be carried at the Site during the entire construction dewatering phase. The daily water taking records must be maintained onsite for the entire construction dewatering phase. The EASR, Discharge Plan, hydrogeological investigation report, and geotechnical assessment of settlements must always also be available at the construction Site for the entire construction dewatering. EXP should be notified immediately about any changes to the construction dewatering schedule or design, since EASR will need to be updated to reflect these modifications. The hydrogeological report, EASR, Discharge Plan and geotechnical assessment constitutes the Water Taking Plan which needs to be available onsite for the duration of construction dewatering.
- For the short-term dewatering system (construction phase), it is anticipated that TSS levels and some other parameters (for example, Total Manganese) in the pumped groundwater may become elevated and exceed both, Sanitary and Storm Sewer Use By-Law limits. To control the concentration of TSS and associated metals, it is recommended that a suitable treatment method be implemented (filtration or decantation facilities and/ or any other applicable treatment system) during construction dewatering activities to discharge to the applicable sewer system. The specifications of the treatment system will need to be adjusted to the reported water quality results by the treatment contractor/process engineer.

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

- For the long-term dewatering (post-construction), the water is suitable to be released into the Sanitary Sewer system without a treatment system. However, the pumped water is unsuitable to be discharged into the Storm Sewer system without implementing an appropriate pre-treatment system, as required.
- It is noted that an agreement to discharge into the sewers owned by the City of Toronto will be required prior to releasing dewatering effluent.
- In conformance with Regulation 903 of the Ontario Water Resources Act, the installation and eventual decommissioning of any dewatering system wells or monitoring wells must be completed by a licensed well contractor. This will be required for all wells that are no longer in use.

The conclusions and recommendations provided above should be reviewed in conjunction with the entirety of the report where they are based on the assumptions that the present design concept described throughout the report will proceed to construction. This report is solely intended for the construction and long-term dewatering assessments. Any changes to the design concept may result in a modification to the recommendations provided in this report.



Project Number: BRM- 00607375-A0

Date: September 23, 2019

Revision 1: May 28, 2021

Revision 2: October 20, 2021

Revision 3: January 13, 2022

Revision 4: October 31, 2023

## 8. Limitations

This report is based on a limited investigation designed to provide information to support an assessment of the current hydrogeological conditions within the study area. The conclusions and recommendations presented within this report reflect Site conditions existing at the time of the assessment. EXP must be contacted immediately if any unforeseen Site conditions are experienced during construction activities. This will allow EXP to review the new findings and provide appropriate recommendations to allow the construction to proceed in a timely and cost-effective manner.

Our undertaking at EXP, therefore, is to perform our work within limits prescribed by our clients, with the usual thoroughness and competence of the geoscience/engineering profession. No other warranty or representation, either expressed or implied, is included or intended in this report.

This report was prepared for the exclusive use of Donway Co-operative Development Corporation. This report may not be reproduced in whole or in part, without the prior written consent of EXP, or used or relied upon in whole or in part by other parties for any purposes whatsoever. Any use which a third party makes of this report, or any part thereof, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. EXP Services Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.

We trust that this information is satisfactory for your purposes. Should you have any questions or comments, please do not hesitate to contact this office.

Sincerely,

EXP Services Inc.

*Amar Neku*



Amar Neku, Ph.D., P.Eng., P.Geo.  
Senior Hydrogeologist  
Environmental Services

*Francois Chartier*

Francois Chartier, M.Sc., P.Geo.  
Discipline Manager, Hydrogeology  
Environmental Services

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

## 9. References

- Cashman and Preene (2013) Groundwater Lowering in Construction, 2nd Edition.
- Chapman, L.J. and Putnam, D.F. (2007). Physiography of Southern Ontario, 3rd Edition, Ontario Geological Survey.
- EXP Services Inc. (March 25, 2019), Phase Two Environmental Site Assessment, 230 The Donway West, Toronto, ON, prepared for Donway Co-operative Development Corporation.
- EXP Services Inc. (October 15, 2021), Supplementary Geotechnical Investigation, Proposed Mid-Rise Residential Development, 230 The Donway West, Toronto, ON, prepared for Donway Co-operative Development Corporation.
- EXP Services Inc. (September 6, 2019), Proposed Mid-Rise Residential Development, 230 The Donway West, Toronto, ON, prepared for Donway Co-operative Development Corporation.
- J.P. Powers, A.B. Corwin, P.C. Schmall, and W.E. Kaeck (2007). Construction Dewatering and Groundwater Control, Third Edition.
- Ministry of Northern Development and Mines (May, 2012). OGS Earth. Retrieved from <http://www.mndm.gov.on.ca/en/mines-and-minerals/applications/ogsearth>.
- Oak Ridges Moraine Groundwater Program. Accessed to the website (<https://oakridgeswater.ca/>) dated September 2019.
- Toronto and Region Conservation (2009), Humber/Don River State of the Watershed Report – Geology and Groundwater Resources.

EXP Services Inc.

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*


*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*


*Revision 4: October 31, 2023*

## Figures



X:\DRAWINGS\607000\607300\607375\607375A\HG INVESTIGATION\AUG 16 2018\BRM-00607375-A0.dwg

**EXP Services Inc.**  
 t: +1.905.793.9800 | f: +1.905.793.0641  
 1595 Clark Boulevard  
 Brampton, ON L6T 4V1  
 Canada




[www.exp.com](http://www.exp.com)

- BUILDINGS • EARTH & ENVIRONMENT • ENERGY •
- INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

LEGEND:  
 APPROXIMATE SITE BOUNDARY

TITLE AND LOCATION:  
**SITE LOCATION PLAN**  
 HYDROGEOLOGICAL INVESTIGATION  
 230 & 240 THE DONWAY WEST  
 TORONTO, ONTARIO

PROJECT NO.:	DWN.:
BRM-00607375-A0	AS
SCALE:	CK:
AS NOTED	PS
DATE:	FIG. NO.:
SEPTEMBER 2019	1



SCALE:  
 0 80 160 240 320 400 m

SOURCE:  
 BASED ON ONTARIO GEOLOGICAL SURVEY DATA PUBLISHED IN 2010

exp.  
 DRAWN BY: AC  
 CHECKED BY: CS

LEGEND:


- APPROXIMATE SITE BOUNDARY
- 19: MODERN ALLUVIAL DEPOSITS
- 9C: COARSE-TEXTURED (FORESHORE-BASINAL) GLACIOLACUSTRINE DEPOSITS
- 8A: FINE-TEXTURED GLACIOLACUSTRINE DEPOSITS
- 5B: STONE-POOR, CARBONATE-DERIVED SILTY TO SANDY TILL
- 5E: UNDIFFERENTIATED OLDER TILL AND STRATIFIED SEDIMENT

SURFICIAL GEOLOGY FIGURE: 2

HYDROGEOLOGICAL INVESTIGATION  
 230 & 240 THE DONWAY WEST  
 TORONTO, ONTARIO

PROJECT NUMBER: BRM-00607375-A0 DATE: AUGUST 2019











X:\607300\607375\607375\SAHG INVESTIGATION\2021-10\BRM-00607375-A0.dwg

**EXP Services Inc.**  
 t: +1.905.793.9800 | f: +1.905.793.0641  
 1595 Clark Boulevard  
 Brampton, ON L6T 4V1  
 Canada



[www.exp.com](http://www.exp.com)

• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •  
 • INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

 APPROXIMATE SITE BOUNDARY	 A-A' CROSS SECTION A-A' (SEE FIGURE 5A)
 BOREHOLE / MONITORING WELL LOCATION (EXP, 2019)	 B-B' CROSS SECTION B-B' (SEE FIGURE 5B)
 BOREHOLE LOCATION (EXP, 2021)	
 BOREHOLE / MONITORING WELL LOCATION (EXP, 2021)	

TITLE AND LOCATION:  
**BOREHOLE / MONITORING  
 LOCATION PLAN**  
 HYDROGEOLOGICAL INVESTIGATION  
 230 THE DONWAY WEST  
 TORONTO, ONTARIO

PROJECT NO.:	DWN.:
BRM-00607375-A0	JA
SCALE:	CK:
AS NOTED	PS
DATE:	FIG. NO.:
OCTOBER 2021	4

A  
NORTH

A'  
SOUTH

BH105  
EL:141.04

BH/MW6  
EL:141.86


BH/MW106  
EL:141.81

BH/MW5  
EL:141.41

BH/MW4  
EL:142.53

BH/MW3  
EL:142.39

BH102  
EL:142.43



VERTICAL SCALE: AS SHOWN

HORIZONTAL SCALE: 0 6 12 18 24 30 m

**EXP Services Inc.**  
 t: +1.905.793.9800 | f: +1.905.793.0641  
 1595 Clark Boulevard  
 Brampton, ON L6T 4V1  
 Canada  
 www.exp.com

• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •  
 • INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

**LEGEND:**

- ASPHALT / CONCRETE
- TOPSOIL
- FILL
- SILTY SAND TO SANDY SILT TILL
- CLAYEY SILT TILL
- GROUNDWATER ELEVATION AS MEASURED ON OCTOBER 6, 2021
- SANDY TO CLAYEY SILT

TITLE AND LOCATION:  
**CROSS SECTION A-A'**  
 HYDROGEOLOGICAL INVESTIGATION  
 230 THE DONWAY WEST  
 TORONTO, ONTARIO


PROJECT NO.:	DWN.:
BRM-00607375-A0	JA
SCALE:	CK:
AS NOTED	PS
DATE:	FIG. NO.:
OCTOBER 2021	5A

X:\607000\607300\607375\607375\AIHG INVESTIGATION\2021-10\BRM-00607375-A0.dwg



B  
NORTHEAST

B'  
SOUTHWEST



BH104  
EL:140.09

BH/MW106  
EL:141.81

BH/MW5  
EL:141.41

BH/MW4  
EL:142.53

BH108  
EL:142.50

BH/MW2  
EL:142.85

BH/MW1  
EL:142.56

X:\607000\607300\607375\607375\AIHG INVESTIGATION\2021-10\BRM-00607375-A0.dwg

**EXP Services Inc.**  
 t: +1.905.793.9800 | f: +1.905.793.0641  
 1595 Clark Boulevard  
 Brampton, ON L6T 4V1  
 Canada  
 www.exp.com

**exp**

• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •  
 • INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

**LEGEND:**


- ASPHALT / CONCRETE
- TOPSOIL
- FILL
- SILTY SAND TO SANDY SILT TILL
- CLAYEY SILT TILL
- GROUNDWATER ELEVATION AS MEASURED ON OCTOBER 6, 2021
- SANDY TO CLAYEY SILT

TITLE AND LOCATION:  
**CROSS SECTION B-B'**  
 HYDROGEOLOGICAL INVESTIGATION  
 230 THE DONWAY WEST  
 TORONTO, ONTARIO

PROJECT NO.:	DWN.:
BRM-00607375-A0	JA
SCALE:	CK:
AS NOTED	PS
DATE:	FIG. NO.:
OCTOBER 2021	5B




**EXP Services Inc.**  
 t: +1.905.793.9800 | f: +1.905.793.0641  
 1595 Clark Boulevard  
 Brampton, ON L6T 4V1  
 Canada



[www.exp.com](http://www.exp.com)

• BUILDINGS • EARTH & ENVIRONMENT • ENERGY •  
 • INDUSTRIAL • INFRASTRUCTURE • SUSTAINABILITY •

- LEGEND:**
- APPROXIMATE SITE BOUNDARY
  -  BOREHOLE / MONITORING WELL LOCATION (EXP, 2019)
  - ~ GROUNDWATER CONTOURS
  - [XX.XX] GROUNDWATER ELEVATION AS MEASURED ON AUGUST 27, 2019
  - GROUNDWATER FLOW DIRECTION

TITLE AND LOCATION:  
**GROUNDWATER CONTOURS**  
 HYDROGEOLOGICAL INVESTIGATION  
 230 & 240 THE DONWAY WEST  
 TORONTO, ONTARIO

PROJECT NO.:	DWN.:
BRM-00607375-A0	AS
SCALE:	CK:
AS NOTED	PS
DATE:	FIG. NO.:
SEPTEMBER 2019	6

X:\DRAWING\GS607000\607300\607375\607375A\HG INVESTIGATION\AUG 16 2018\BRM-00607375-A0.dwg

EXP Services Inc.

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

## Appendix A – MECP WWR Summary Table

Off-Site													
BORE_HOLE_ID	WELL_ID	DATE	EAST83	NORTH83	ELEVATION (m ASL)	STREET	CITY	DISTANCE TO SITE CENTROID (m)	WATER FOUND (m BGS)	1st USE	2nd USE	FINAL STATUS	
23050315	7050315	9/11/2007	633224	4843753	143.2			469		Dewatering			
1003963380	7183655	6/15/2012	633147	4843882	143.5	895 LAWRENCE AVE E	TORONTO	323		Monitoring and Test Hole		Monitoring and Test Hole	
1003963383	7183656	6/15/2012	633103	4843838	144.2	895 LAWRENCE AVE E	TORONTO	358		Monitoring and Test Hole		Monitoring and Test Hole	
1003963386	7183657	6/15/2012	633129	4843903	143.7	895 LAWRENCE AVE E	TORONTO	298		Monitoring and Test Hole		Monitoring and Test Hole	
1004262112	7198354	2/28/2013	633109	4843677	147.0	99 THE DONWAY WEST	TORONTO	518	8.5	Monitoring and Test Hole		Test Hole	
1004717749	7217263	1/20/2014	633509	4844470	134.9	15 MALLOW ROAD	Toronto	525		Test Hole		Test Hole	
1004717752	7217264	1/20/2014	633511	4844457	134.9	15 MALLOW ROAD	Toronto	529		Test Hole		Test Hole	
1004717758	7217266	1/20/2014	633551	4844468	134.6	15 MALLOW RD.	Toronto	560		Test Hole		Test Hole	
1005117481	7226881	7/6/2014	633524	4844321	135.7	15 MALLOW RD	TORONTO	479		Monitoring and Test Hole		Test Hole	
1005117487	7226883	7/6/2014	633482	4844449	135.1	15 MALLOW RD.	TORONTO	491		Monitoring and Test Hole		Test Hole	
1005117490	7226884	7/6/2014	633487	4844375	135.7	15 MALLOW RD.	TORONTO	462		Monitoring and Test Hole		Test Hole	
1005117493	7226885	7/6/2014	633552	4844420	134.9	15 MALLOW RD.	TORONTO	539		Monitoring and Test Hole		Test Hole	
1005117496	7226886	7/6/2014	633533	4844452	134.8	15 MALLOW RD.	TORONTO	537		Monitoring and Test Hole		Test Hole	
1006252423	7272073	8/29/2016	633396	4843903	142.2	7 MAGINN MEWS	TORONTO	442		Monitoring and Test Hole		Monitoring and Test Hole	
1006252426	7272074	8/29/2016	633377	4843961	141.7	7 MAGINN MEWS	TORONTO	391		Monitoring and Test Hole		Monitoring and Test Hole	
1006252429	7272075	8/29/2016	633294	4843868	142.4	7 MAGINN MEWS	TORONTO	399		Monitoring and Test Hole		Monitoring and Test Hole	
1006270603	7272931	7/8/2016	633115	4843765	145.9			432	4.2	Monitoring		Observation Wells	
1006352863	7280762	8/30/2016	633291	4843741	141.9	7 MAGINN MEWS	Toronto	507		Monitoring and Test Hole		Monitoring and Test Hole	
1006356018	7281531	6/3/2016	633111	4843749	146.2	169 THE DONWAY WEST	Toronto	447		Monitoring		Observation Wells	
23051270	7051270	9/27/2007	633224	4843753	143.2	DONMILLS RD & LAWRENCE AVE. EAST		469					
1005341694	7240996	2/13/2015	633440	4844025	139.8	DON MILLS RD. LAWRENCE AVE	TORONTO	413	1.4			Abandoned-Other	
1006270606	7272932	7/15/2016	633108	4843753	146.1			443	7.5				
1005318851	7239233	10/14/2014	633103	4843770	145.9			425					
1005320078	7239407	4/17/2014	633056	4843801	146.2			392					
1005913647	7259873	11/23/2015	633104	4843770	145.9			425					

EXP Services Inc.

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

## Appendix B – Borehole Logs

# Log of Borehole 1

Project No. BRM-00607375-A0

Drawing No. 2

Project: Preliminary Environmental, Geotechnical & Hydrogeological Investigations Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: August 1, 2019

Auger Sample

Combustible Vapour Reading

SPT (N) Value

Natural Moisture

Drill Type: Hollow Stem Augers

Dynamic Cone Test

Plastic and Liquid Limit

Datum: Geodetic


Shelby Tube

Undrained Triaxial at

Field Vane Test

% Strain at Failure

Penetrometer



LAGWGL02EXP 607375A\_BH\_LOGS\_2.GPJ NEW.GDT 9/6/19

**Notes:**

- Borehole advanced to completion at ~12.8 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.
- This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-A0); borehole data requires interpretation assistance by exp professional staff before use by others.



Brampton

Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	~11.5	Well
August 8, 2019	~1.0	Well
August 27, 2019	~1.2	Well

# Log of Borehole 2

Project No. BRM-00607375-A0

Drawing No. 3

Project: Preliminary Environmental, Geotechnical & Hydrogeological Investigations Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: July 30, 2019

Drill Type: Hollow Stem Augers

Datum: Geodetic

Auger Sample

SPT (N) Value

Dynamic Cone Test

Shelby Tube

Field Vane Test

Combustible Vapour Reading


Natural Moisture

Plastic and Liquid Limit

Undrained Triaxial at

% Strain at Failure

Penetrometer



LAGWGL02EXP 607375A\_BH\_LOGS\_2.GPJ NEW.GDT 9/6/19

Notes:  
 1. Borehole advanced to completion at ~12.8 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.  
 2. This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-A0); borehole data requires interpretation assistance by exp professional staff before use by others.



Brampton

Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	~9.6	Well
August 8, 2019	~1.0	Well
August 27, 2019	~1.3	Well

# Log of Borehole 3

Project No. BRM-00607375-A0

Drawing No. 4

Project: Preliminary Environmental, Geotechnical & Hydrogeological Investigations Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: July 30, 2019

Drill Type: Hollow Stem Augers

Datum: Geodetic

Auger Sample

SPT (N) Value

Dynamic Cone Test

Shelby Tube

Field Vane Test


Combustible Vapour Reading

Natural Moisture

Plastic and Liquid Limit

Undrained Triaxial at  
% Strain at Failure

Penetrometer



LAGWGL02EXP 607375A\_BH\_LOGS\_2.GPJ NEW.GDT 9/6/19

**Notes:**

- Borehole advanced to completion at ~15.7 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.
- This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-A0); borehole data requires interpretation assistance by exp professional staff before use by others.



Brampton

Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	~13.8	Well
August 8, 2019	~9.8	Well
August 27, 2019	~9.2	Well



# Log of Borehole 4

Project No. BRM-00607375-A0

Drawing No. 5

Project: Preliminary Environmental, Geotechnical & Hydrogeological Investigations Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: July 31, 2019

Drill Type: Hollow Stem Augers

Datum: Geodetic

Auger Sample

SPT (N) Value

Dynamic Cone Test

Shelby Tube

Field Vane Test

Combustible Vapour Reading


Natural Moisture

Plastic and Liquid Limit

Undrained Triaxial at

% Strain at Failure

Penetrometer



LAGWGL02EXP 607375A\_BH\_LOGS\_2.GPJ NEW.GDT 9/6/19

**Notes:**

- Borehole advanced to completion at ~13.6 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.
- This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-A0); borehole data requires interpretation assistance by exp professional staff before use by others.



Brampton

Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	~8.3	Well
August 8, 2019	~2.1	Well
August 27, 2019	~1.6	Well

# Log of Borehole 5

Project No. BRM-00607375-A0

Drawing No. 6

Project: Preliminary Environmental, Geotechnical & Hydrogeological Investigations Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: July 31, 2019

Drill Type: Hollow Stem Augers

Datum: Geodetic

Auger Sample

SPT (N) Value

Dynamic Cone Test

Shelby Tube

Field Vane Test

Combustible Vapour Reading


Natural Moisture

Plastic and Liquid Limit

Undrained Triaxial at

% Strain at Failure

Penetrometer



LAGWGL02EXP 607375A\_BH\_LOGS\_2.GPJ NEW.GDT 9/6/19

Notes:  
 1. Borehole advanced to completion at ~12.8 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.  
 2. This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-A0); borehole data requires interpretation assistance by exp professional staff before use by others.



Brampton

Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	~11.3	Well
August 8, 2019	~1.6	Well
August 27, 2019	~1.6	Well

# Log of Borehole 6

Project No. BRM-00607375-A0

Drawing No. 7

Project: Preliminary Environmental, Geotechnical & Hydrogeological Investigations Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: August 1, 2019

Drill Type: Hollow Stem Augers

Datum: Geodetic

Auger Sample

SPT (N) Value

Dynamic Cone Test

Shelby Tube

Field Vane Test


Combustible Vapour Reading

Natural Moisture

Plastic and Liquid Limit

Undrained Triaxial at % Strain at Failure

Penetrometer



LAGWGL02EXP 607375A\_BH\_LOGS\_2.GPJ NEW.GDT 9/6/19

**Notes:**

- Borehole advanced to completion at ~8.2 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.
- This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-A0); borehole data requires interpretation assistance by exp professional staff before use by others.



Brampton

Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	No Free Water	Well
August 8, 2019	~2.1	Well
August 27, 2019	~2.3	Well

# Log of Borehole 101

Project No. BRM-00607375-D0

Drawing No. 2

Project: Supplementary Geotechnical Investigation

Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: September 7, 2021

Auger Sample



SPT (N) Value



Dynamic Cone Test



Shelby Tube



Field Vane Test



Combustible Vapour Reading



Natural Moisture



Plastic and Liquid Limit



Undrained Triaxial at




% Strain at Failure



Penetrometer



Datum: Geodetic



LAGWGL02EXP 607375D\_BH\_LOGS BERND.GPJ NEW.GDT 10/7/21

Notes:  
 1. Borehole advanced to completion at ~20.4 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.  
 2. This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-D0); borehole data requires interpretation assistance by exp professional staff before use by others.



Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	No Free Water	~19.8
September 13, 2021	~18.9	Well
September 20, 2021	~18.5	Well

# Log of Borehole 102

Project No. BRM-00607375-D0

Drawing No. 3

Project: Supplementary Geotechnical Investigation

Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: September 9, 2021

Auger Sample



SPT (N) Value



Dynamic Cone Test



Shelby Tube



Field Vane Test



Combustible Vapour Reading



Natural Moisture



Plastic and Liquid Limit




Undrained Triaxial at % Strain at Failure



Penetrometer



Datum: Geodetic



LAGWGL02EXP 607375D\_BH\_LOGS BERND.GPJ NEW.GDT 10/7/21

**Notes:**

- Borehole advanced to completion at ~15.9 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.
- This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-D0); borehole data requires interpretation assistance by exp professional staff before use by others.



Brampton

Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	No Free Water	~7.9

# Log of Borehole 103

Project No. BRM-00607375-D0

Drawing No. 4

Project: Supplementary Geotechnical Investigation

Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: September 13, 2021

Auger Sample



SPT (N) Value



Dynamic Cone Test



Shelby Tube



Field Vane Test



Combustible Vapour Reading



Natural Moisture



Plastic and Liquid Limit




Undrained Triaxial at % Strain at Failure



Penetrometer



Datum: Geodetic



LAGWGL02EXP 607375D\_BH\_LOGS BERND.GPJ NEW.GDT 10/7/21

Notes:  
 1. Borehole advanced to completion at ~20.2 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.  
 2. This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-D0); borehole data requires interpretation assistance by exp professional staff before use by others.



Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	No Free Water	13.72

# Log of Borehole 104

Project No. BRM-00607375-D0

Drawing No. 5

Project: Supplementary Geotechnical Investigation

Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: September 10, 2021

Auger Sample



SPT (N) Value



Dynamic Cone Test



Shelby Tube



Field Vane Test



Combustible Vapour Reading



Natural Moisture



Plastic and Liquid Limit




Undrained Triaxial at % Strain at Failure



Penetrometer



Datum: Geodetic



LAGWGL02EXP 607375D\_BH\_LOGS BERND.GPJ NEW.GDT 10/7/21

Notes:  
 1. Borehole advanced to completion at ~15.8 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.  
 2. This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-D0); borehole data requires interpretation assistance by exp professional staff before use by others.



Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	No Free Water	~19.8

# Log of Borehole 105

Project No. BRM-00607375-D0

Drawing No. 6

Project: Supplementary Geotechnical Investigation

Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: September 9, 2021

Auger Sample

Combustible Vapour Reading

SPT (N) Value

Natural Moisture

Drill Type: Hollow Stem Augers

Dynamic Cone Test

Plastic and Liquid Limit


Datum: Geodetic

Shelby Tube

Undrained Triaxial at % Strain at Failure

Field Vane Test

Penetrometer



LAGWGL02EXP 607375D\_BH\_LOGS BERND.GPJ NEW.GDT 10/7/21

**Notes:**

- Borehole advanced to completion at ~20.4 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.
- This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-D0); borehole data requires interpretation assistance by exp professional staff before use by others.



Brampton

Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	~17.1	~19.5



# Log of Borehole 106

Project No. BRM-00607375-D0

Drawing No. 7

Project: Supplementary Geotechnical Investigation

Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: September 13, 2021

Auger Sample



SPT (N) Value



Dynamic Cone Test



Shelby Tube



Field Vane Test



Combustible Vapour Reading



Natural Moisture



Plastic and Liquid Limit




Undrained Triaxial at % Strain at Failure



Penetrometer



Datum: Geodetic



Notes:

- Borehole advanced to completion at ~20.4 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.
- This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-D0); borehole data requires interpretation assistance by exp professional staff before use by others.



Brampton

Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	~16.6	~19.8
September 20, 2021	~16.2	Well

# Log of Borehole 107

Project No. BRM-00607375-D0

Drawing No. 8

Project: Supplementary Geotechnical Investigation

Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: September 8, 2021

Auger Sample



SPT (N) Value



Dynamic Cone Test



Shelby Tube



Field Vane Test



Combustible Vapour Reading



Natural Moisture



Plastic and Liquid Limit




Undrained Triaxial at % Strain at Failure



Penetrometer



Datum: Geodetic



LAGWGL02EXP 607375D\_BH\_LOGS BERND.GPJ NEW.GDT 10/7/21

**Notes:**

- Borehole advanced to completion at ~15.7 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.
- This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-D0); borehole data requires interpretation assistance by exp professional staff before use by others.



Brampton

Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	~10.7	~15.2

# Log of Borehole 108

Project No. BRM-00607375-D0

Drawing No. 9

Project: Supplementary Geotechnical Investigation

Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: September 8, 2021

Auger Sample



SPT (N) Value



Dynamic Cone Test



Shelby Tube



Field Vane Test



Combustible Vapour Reading



Natural Moisture



Plastic and Liquid Limit




Undrained Triaxial at % Strain at Failure



Penetrometer



Datum: Geodetic



LAGWGL02EXP 607375D\_BH\_LOGS BERND.GPJ NEW.GDT 10/7/21

**Notes:**

- Borehole advanced to completion at ~20.4 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.
- This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-D0); borehole data requires interpretation assistance by exp professional staff before use by others.



Brampton

Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	~7.3	~13.7

# Log of Borehole 109

Project No. BRM-00607375-D0

Drawing No. 10

Project: Supplementary Geotechnical Investigation

Sheet No. 1 of 1

Location: 230 The Donway West, Toronto, Ontario

Date Drilled: September 7, 2021

Auger Sample



SPT (N) Value



Dynamic Cone Test



Shelby Tube



Field Vane Test



Combustible Vapour Reading



Natural Moisture



Plastic and Liquid Limit




Undrained Triaxial at % Strain at Failure



Penetrometer



Datum: Geodetic



LAGWGL02EXP 607375D\_BH\_LOGS BERND.GPJ NEW.GDT 10/7/21

Notes:  
 1. Borehole advanced to completion at ~15.7 m depth by conventional soil sampling methods using a specialist drilling subcontractor. For borehole definitions, see notes prior to logs.  
 2. This drawing forms part of and must be read in conjunction with the subject report (Ref. No.: BRM-00607375-D0); borehole data requires interpretation assistance by exp professional staff before use by others.



Elapsed Time	Water Level (m)	Hole Open to (m)
On Completion	~14.6	~14.9



exp Services Inc.  
1595 Clark Boulevard, Brampton  
Ontario, Canada, L6T 4V1  
Telephone: (905) 793-9800  
Fax: (905) 793-0641

# Grain Size Analysis & Hydrometer Test Report

ST08

Sample Test No.: 378451-3

Report No.: 1

Date Reported: 17-Sep-21

Project No.: brm-00607375-d0 100

Project Name: Combined Drilling Program

**Grain Size Proportion (%)**

Gravel (> 4.75mm): **0.5**  
Sand (> 75µm, < 4.75mm): **40.3**  
Silt (> 2µm, < 75µm): **46.8**  
Clay (< 2µm): **12.4**  
Total: **100.0**


**Sample Information**

Location: BH 101  
Sample Method: SS  
Sample No.: 7  
Depth: 6.1 - 6.7 m  
Sample Description: Silt and Sand, some Clay; trace Gravel; Grey  
Sampled By: Bernd  
Sampling Date: 9/7/2021  
Date Received: 9/7/2021  
Client Sample ID:  
Comments:

Grain Size (mm)	% Passing	Grain Size (mm)	% Passing
26.5	100.0	0.0454	43.8
22.4	100.0	0.0331	34.5
19	100.0	0.0214	28.6
16	100.0	0.0125	24.5
13.2	100.0	0.0089	22.4
12.5	100.0	0.0063	19.3
9.5	100.0	0.0031	16.2
6.7	99.7	0.0013	9.9
4.75	99.5		
2	97.8		
0.85	95.9		
0.425	92.2		
0.25	81.3		
0.18	75.9		
0.15	71.9		
0.075	59.2		
0.053	48.9		

UNIFIED SOIL CLASSIFICATION SYSTEM

CLAY AND SILT	SAND			GRAVEL	
	Fine	Medium	Coarse	Fine	Coarse



Project Manager: Kevin Leung

Approved By: Original Signed By  
Willie Rodych, Lab Supervisor

Date Approved: 17-Sep-21



exp Services Inc.  
1595 Clark Boulevard, Brampton  
Ontario, Canada, L6T 4V1  
Telephone: (905) 793-9800  
Fax: (905) 793-0641

# Grain Size Analysis & Hydrometer Test Report

ST08

Sample Test No.: 378662-3

Report No.: 2

Date Reported: 17-Sep-21

Project No.: brm-00607375-d0 100

Project Name: Combined Drilling Progrm

**Grain Size Proportion (%)**

Gravel (> 4.75mm): **2.0**  
Sand (> 75µm, < 4.75mm): **19.9**  
Silt (> 2µm, < 75µm): **51.1**  
Clay (< 2µm): **27.0**  
Total: **100.0**


**Sample Information**

Location: BH 102  
Sample Method: SS  
Sample No.: 11  
Depth: 12.2 - 12.8 m  
Sample Description: Clayey Silt, some Sand; trace Gravel; Grey  
Sampled By: Bernd  
Sampling Date: 9/9/2021  
Date Received: 9/9/2021  
Client Sample ID:  
Comments:

Grain Size (mm)	% Passing	Grain Size (mm)	% Passing
26.5	100.0	0.0414	67.5
22.4	100.0	0.0297	64.5
19	100.0	0.0193	57.7
16	100.0	0.0113	53.1
13.2	100.0	0.0081	48.4
12.5	100.0	0.0059	42.3
9.5	98.8	0.0030	33.0
6.7	98.3	0.0013	22.8
4.75	98.0		
2	97.1		
0.85	96.0		
0.425	94.5		
0.25	91.8		
0.18	89.4		
0.15	86.8		
0.075	78.1		
0.053	72.4		

UNIFIED SOIL CLASSIFICATION SYSTEM

CLAY AND SILT	SAND			GRAVEL	
	Fine	Medium	Coarse	Fine	Coarse



Project Manager: Kevin Leung

Approved By: Original Signed By  
Willie Rodych, Lab Supervisor

Date Approved: 17-Sep-21



exp Services Inc.  
1595 Clark Boulevard, Brampton  
Ontario, Canada, L6T 4V1  
Telephone: (905) 793-9800  
Fax: (905) 793-0641

# Grain Size Analysis & Hydrometer Test Report

ST08

Sample Test No.: 378641-3

Report No.: 3

Date Reported: 17-Sep-21

Project No.: brm-00607375-d0 100

Project Name: Combined Drilling Progrm

**Grain Size Proportion (%)**

Gravel (> 4.75mm): **2.0**  
Sand (> 75µm, < 4.75mm): **24.1**  
Silt (> 2µm), < 75µm): **40.8**  
Clay (< 2µm): **33.1**  
Total: **100.0**


**Sample Information**

Location: BH 105  
Sample Method: SS  
Sample No.: 7  
Depth: 6.1 - 6.7 m  
Sample Description: Sandy, Clayey Silt; trace Gravel; Grey  
Sampled By: Bernd  
Sampling Date: 9/9/2021  
Date Received: 9/9/2021  
Client Sample ID:  
Comments:

Grain Size (mm)	% Passing	Grain Size (mm)	% Passing
26.5	100.0	0.0415	66.5
22.4	100.0	0.0297	63.4
19	100.0	0.0192	58.8
16	100.0	0.0113	52.7
13.2	100.0	0.0081	49.6
12.5	100.0	0.0058	45.0
9.5	98.4	0.0029	37.4
6.7	98.2	0.0013	29.7
4.75	98.0		
2	96.4		
0.85	94.1		
0.425	91.3		
0.25	87.8		
0.18	85.4		
0.15	82.7		
0.075	73.9		
0.053	69.7		

UNIFIED SOIL CLASSIFICATION SYSTEM

CLAY AND SILT	SAND			GRAVEL	
	Fine	Medium	Coarse	Fine	Coarse



Project Manager: Kevin Leung

Approved By: Original Signed By  
Willie Rodych, Lab Supervisor

Date Approved: 17-Sep-21



exp Services Inc.  
1595 Clark Boulevard, Brampton  
Ontario, Canada, L6T 4V1  
Telephone: (905) 793-9800  
Fax: (905) 793-0641

# Grain Size Analysis & Hydrometer Test Report

ST08

Sample Test No.: 378888-2

Report No.: 4

Date Reported: 17-Sep-21

Project No.: brm-00607375-d0 100

Project Name: Combined Drilling Progrm

**Grain Size Proportion (%)**

Gravel (> 4.75mm): **1.2**  
Sand (> 75µm, < 4.75mm): **37.2**  
Silt (> 2µm), < 75µm): **43.1**  
Clay (< 2µm): **18.5**  
Total: **100.0**


**Sample Information**

Location: BH 106  
Sample Method: SS  
Sample No.: 8  
Depth: 7.6 - 8.2 m  
Sample Description: Silt and Sand, some Clay; trace Gravel; Grey  
Sampled By: Bernd  
Sampling Date: 9/13/2021  
Date Received: 9/13/2021  
Client Sample ID:  
Comments:

Grain Size (mm)	% Passing	Grain Size (mm)	% Passing
26.5	100.0	0.0445	49.1
22.4	100.0	0.0322	42.9
19	100.0	0.0207	37.7
16	100.0	0.0121	33.0
13.2	100.0	0.0087	30.6
12.5	100.0	0.0062	28.4
9.5	99.6	0.0031	22.2
6.7	99.3	0.0013	16.1
4.75	98.8		
2	97.2		
0.85	95.1		
0.425	91.3		
0.25	80.1		
0.18	75.2		
0.15	71.8		
0.075	61.6		
0.053	53.4		

UNIFIED SOIL CLASSIFICATION SYSTEM

CLAY AND SILT	SAND			GRAVEL	
	Fine	Medium	Coarse	Fine	Coarse



Project Manager: Kevin Leung

Approved By: Original Signed By  
Willie Rodych, Lab Supervisor

Date Approved: 17-Sep-21





exp Services Inc.  
1595 Clark Boulevard, Brampton  
Ontario, Canada, L6T 4V1  
Telephone: (905) 793-9800  
Fax: (905) 793-0641

# Grain Size Analysis & Hydrometer Test Report

ST08

Sample Test No.: 378585-3

Report No.: 5

Date Reported: 17-Sep-21

Project No.: brm-00607375-d0 100

Project Name: Combined Drilling Progrm

**Grain Size Proportion (%)**

Gravel (> 4.75mm): **0.1**  
Sand (> 75µm, < 4.75mm): **39.2**  
Silt (> 2µm, < 75µm): **42.4**  
Clay (< 2µm): **18.3**  
Total: **100.0**


**Sample Information**

Location: BH 108  
Sample Method: SS  
Sample No.: 8  
Depth: 7.6 - 8.2 m  
Sample Description: Silt and Sand, some Clay; trace Gravel; Grey  
Sampled By: Bernd  
Sampling Date: 9/8/2021  
Date Received: 9/8/2021  
Client Sample ID:  
Comments:

Grain Size (mm)	% Passing	Grain Size (mm)	% Passing
26.5	100.0	0.0452	46.2
22.4	100.0	0.0325	40.9
19	100.0	0.0209	35.5
16	100.0	0.0122	32.3
13.2	100.0	0.0087	30.1
12.5	100.0	0.0062	28.2
9.5	100.0	0.0031	22.2
6.7	99.9	0.0013	15.8
4.75	99.9		
2	99.7		
0.85	97.2		
0.425	93.1		
0.25	80.9		
0.18	75.7		
0.15	72.0		
0.075	60.7		
0.053	51.6		

UNIFIED SOIL CLASSIFICATION SYSTEM

CLAY AND SILT	SAND			GRAVEL	
	Fine	Medium	Coarse	Fine	Coarse



Project Manager: Kevin Leung

Approved By: Original Signed By  
Willie Rodych, Lab Supervisor

Date Approved: 17-Sep-21



exp Services Inc.  
1595 Clark Boulevard, Brampton  
Ontario, Canada, L6T 4V1  
Telephone: (905) 793-9800  
Fax: (905) 793-0641

# Grain Size Analysis & Hydrometer Test Report

ST08

Sample Test No.: 378440-2

Report No.: 6

Date Reported: 17-Sep-21

Project No.: brm-00607375-d0 100

Project Name: Combined Drilling Progrm

**Grain Size Proportion (%)**

Gravel (> 4.75mm): **4.6**  
Sand (> 75µm, < 4.75mm): **48.2**  
Silt (> 2µm, < 75µm): **35.5**  
Clay (< 2µm): **11.7**  
Total: **100.0**


**Sample Information**

Location: BH 109  
Sample Method: SS  
Sample No.: 9  
Depth: 9.1 - 9.8 m  
Sample Description: Sand and Silt, some Clay; trace Gravel; Grey  
Sampled By: Bernd  
Sampling Date: 9/7/2021  
Date Received: 9/7/2021  
Client Sample ID:  
Comments:

Grain Size (mm)	% Passing	Grain Size (mm)	% Passing
26.5	100.0	0.0463	37.0
22.4	100.0	0.0331	33.6
19	100.0	0.0212	29.4
16	100.0	0.0124	27.0
13.2	99.0	0.0088	23.9
12.5	98.2	0.0063	20.3
9.5	97.6	0.0031	14.9
6.7	96.7	0.0013	9.7
4.75	95.4		
2	95.4		
0.85	92.3		
0.425	86.2		
0.25	72.1		
0.18	64.7		
0.15	59.6		
0.075	47.2		
0.053	40.5		

UNIFIED SOIL CLASSIFICATION SYSTEM

CLAY AND SILT	SAND			GRAVEL	
	Fine	Medium	Coarse	Fine	Coarse



Project Manager: Kevin Leung

Approved By: Original Signed By  
Willie Rodych, Lab Supervisor

Date Approved: 17-Sep-21

EXP Services Inc.

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*


*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

## Appendix C – SWRT Procedures and Results



SWRT - FALLING HEAD - BH/MW 1

Data Set: C:\Users\simonc\Documents\BHMW1.aqt

Date: 08/20/19

Time: 10:59:30

PROJECT INFORMATION

Company: EXP Service Inc.

Client: Donway Co-operative

Project: BRM-00607375

Location: 230 The Donway W, Toronto, ON

Test Well: BH/MW 1

Test Date: August 13, 2019

AQUIFER DATA

Saturated Thickness: 11.05 m

Anisotropy Ratio (Kz/Kr): 1.

WELL DATA (BH/MW 1)

Initial Displacement: 0.972 m

Static Water Column Height: 11.05 m

Total Well Penetration Depth: 11.05 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.1016 m


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

K = 4.23E-8 m/sec

y0 = 0.84 m



SWRT - RISING HEAD - BH/MW 2

Data Set: C:\Users\simonc\Documents\BHMW2.aqt

Date: 08/20/19

Time: 10:51:25

PROJECT INFORMATION

Company: EXP Service Inc.

Client: Donway Co-operative

Project: BRM-00607375

Location: 230 The Donway W, Toronto, ON

Test Well: BH/MW 2

Test Date: August 13, 2019

AQUIFER DATA

Saturated Thickness: 4.991 m

Anisotropy Ratio (Kz/Kr): 1.

WELL DATA (BH/MW 2)

Initial Displacement: 1.966 m

Static Water Column Height: 4.991 m

Total Well Penetration Depth: 4.991 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.1016 m


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

K = 1.6E-7 m/sec

y0 = 1.997 m



SWRT - FALLING HEAD - BH 3

Data Set: C:\Users\simonc\Documents\BH3.aqt

Date: 08/27/19

Time: 20:25:54

PROJECT INFORMATION

Company: EXP Service Inc.

Client: Donway Co-operative

Project: BRM-00607375

Location: 230 The Donway W, Toronto, ON

Test Well: BH 3

Test Date: August 27, 2019

AQUIFER DATA

Saturated Thickness: 5.98 m

Anisotropy Ratio (Kz/Kr): 1.

WELL DATA (BH 3)

Initial Displacement: 1.848 m

Static Water Column Height: 5.98 m

Total Well Penetration Depth: 5.98 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.1016 m


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

K = 9.01E-9 m/sec

y0 = 1.817 m



SWRT - FALLING HEAD - BH/MW 4

Data Set: C:\Users\simonc\Documents\BHMW4.aqt

Date: 08/20/19

Time: 10:54:16

PROJECT INFORMATION

Company: EXP Service Inc.

Client: Donway Co-operative

Project: BRM-00607375

Location: 230 The Donway W, Toronto, ON

Test Well: BH/MW 4

Test Date: August 13, 2019

AQUIFER DATA

Saturated Thickness: 9.302 m

Anisotropy Ratio (Kz/Kr): 1.

WELL DATA (BH/MW 4)

Initial Displacement: 1.947 m

Static Water Column Height: 9.302 m

Total Well Penetration Depth: 9.302 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.1016 m


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

K = 4.77E-8 m/sec

y0 = 1.864 m



SWRT - FALLING HEAD - BH 5

Data Set: C:\Users\simonc\Documents\BH5\_.aqt

Date: 08/27/19

Time: 20:25:24

PROJECT INFORMATION

Company: EXP Service Inc.

Client: Donway Co-operative

Project: BRM-00607375

Location: 230 The Donway W, Toronto, ON

Test Well: BH 5

Test Date: August 27, 2019

AQUIFER DATA

Saturated Thickness: 10.58 m

Anisotropy Ratio (Kz/Kr): 1.

WELL DATA (BH 5)

Initial Displacement: 1.566 m

Static Water Column Height: 10.58 m

Total Well Penetration Depth: 10.58 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.1016 m

SOLUTION


Aquifer Model: Unconfined

Solution Method: Hvorslev

K = 2.54E-7 m/sec

y0 = 1.378 m





SWRT - FALLING HEAD - BH/MW 6

Data Set: C:\Users\simonc\Documents\BHMW6.aqt

Date: 08/20/19

Time: 11:01:55

PROJECT INFORMATION

Company: EXP Service Inc.

Client: Donway Co-operative

Project: BRM-00607375

Location: 230 The Donway W, Toronto, ON

Test Well: BH/MW 6

Test Date: August 13, 2019

AQUIFER DATA

Saturated Thickness: 5.325 m

Anisotropy Ratio (Kz/Kr): 1.

WELL DATA (BH/MW 6)

Initial Displacement: 1.641 m

Static Water Column Height: 5.325 m

Total Well Penetration Depth: 5.325 m

Screen Length: 3. m

Casing Radius: 0.0254 m

Well Radius: 0.1016 m


SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

K = 2.1E-8 m/sec

y0 = 1.576 m



BH/MW 101\_RISING HEAD SWRT

Data Set: ...\BH 101.aqt  
 Date: 10/13/21

Time: 15:30:23

PROJECT INFORMATION

Company: EXP  
 Client: Donway Co-Op Develepment Corp  
 Project: BRM-21003722-A0  
 Location: 230 The Donway West  
 Test Well: BH/MW101  
 Test Date: 6 Oct 2021

AQUIFER DATA

Saturated Thickness: 1.5 m

Anisotropy Ratio (Kz/Kr): 1.

WELL DATA (BH/MW 101)

Initial Displacement: 0.879 m  
 Total Well Penetration Depth: 3. m  
 Casing Radius: 0.0254 m

Static Water Column Height: 1.5 m  
 Screen Length: 3. m  
 Well Radius: 0.0762 m

SOLUTION

Aquifer Model: Unconfined

Solution Method: Hvorslev

K = 2.083E-7 m/sec

y0 = 0.8697 m




# Single Well Response Test Procedure

A Single Well Response Test (SWRT), also known as a bail test or a slug test, is conducted in order to determine the saturated hydraulic conductivity ( $K$ ) of an aquifer. The method of the SWRT is to characterize the change of groundwater level in a well or borehole over time.

In order to ensure consistency and repeatability, all **exp** employees are to follow the procedure outlined in this document when conducting SWRTs.

The figure below depicts a schematic of a slug and bail test and the respective water level changes.





## Slug Test Procedure

### Equipment Required

- Copy of a signed health and safety plan
- Copy of the work program
- PPE as required by Site-Specific HASP
- Copy of the monitoring well location plan/site plan
- Waterproof pen and bound field note book
- SWRT field data Entry form
- Disposable gloves
- Duct tape
- Deionized water
- Alconox (phosphate free detergent)
- Spray bottles
- Electronic water level meter and spare batteries
- Solid PVC or stainless steel slug of known volume or clean water
- String (nylon)
- Water pressure transducer (data logger) and baro-logger
- Watch or stop watch with second hand
- Plastic sheeting

### Testing Procedure

1. Remove cap from well and collect static water level
2. Remove waterra tubing/bailer and place in garbage bag. Record static water level measurement again.
3. Lower the slug into the well and record the dynamic water level.
4. Record the drawdown (for the slug test) at set five (5) second intervals for the first five (5) minutes, then reduce to every one (1) minute.
5. Continue recording the drawdown until 95% recovery is reached. To calculate this value: Find the difference between the dynamic water level and the static water level, then multiply by 95% (.95). Add the resulting value to the dynamic water level.  
(Static Water Level – Dynamic Water Level).95 + Static Water Level = 95% Recovery Value
6. Once complete, replace the waterra tubing/bailer and re-secure the well cap.

**Note:** If the well is deep, more than one slug may be inserted by attaching the slugs to a series.

Slugs must be washed with methanol, then lab grade soap, and then rinsed with de-ionized water after each use.



Based on the recorded observations, the hydraulic conductivity (in m/s) of the aquifer will be determined. In order to determine the hydraulic conductivity; the well diameter, radius of the borehole and length of the screen will also be required.

## Bail Test Procedure

### Equipment Required

- 20 L (5 gal) Graduated pail
- Stop watch or watch with seconds
- Garbage bags
- Water level meter
- Field sheets/log book
- Latex Gloves
- Bailer and Rope

### Procedure

1. Remove cap from well and collect static water level.
2. If using a **bailer**:
  - a. Affix the rope to the bailer.
  - b. Remove the watterra tubing and place in garbage bag
  - c. Record static water level measurement again.
  - d. Record how much water was removed by either counting the number of full bailers or emptying removed water into a container.
  - e. Quickly lower the bailer into the well and remove.
  - f. Continue this process until the water level will reduce no further.
  - g. Record the dynamic water level.
3. If using **watterra** to bail the water:
  - a. Pump the water into graduated bucket until the water level will reduce no further.
  - b. Record how much water has been removed.
  - c. Record the dynamic water level.
4. Record the recovery at set five (5) second intervals for the first (5) minutes, then reduce to every one (1) minute.
5. Continue recording the drawdown/recovery until 95% recovery is reached.
6. Once complete, replace any watterra tubing that may have been removed from the well and re-secure the well cap.

EXP Services Inc.

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

## Appendix D – Laboratory Certificates of Analysis



Your P.O. #: ENV-BRM  
 Your Project #: BRM-00607375  
 Site Location: 230 THE DONWAY W  
 Your C.O.C. #: 686832-11-01

**Attention: Francois Chartier**

exp Services Inc  
 1595 Clark Blvd  
 Brampton, ON  
 CANADA L6T 4V1

**Report Date: 2019/08/19**  
 Report #: R5845545  
 Version: 1 - Final

**CERTIFICATE OF ANALYSIS**

**BV LABS JOB #: B9M3673**  
**Received: 2019/08/13, 16:22**

Sample Matrix: Water  
 # Samples Received: 1

Analyses	Quantity	Date	Date	Laboratory Method	Reference
		Extracted	Analyzed		
Sewer Use By-Law Semivolatile Organics	1	2019/08/15	2019/08/15	CAM SOP 00301	EPA 8270 m
Biochemical Oxygen Demand (BOD)	1	2019/08/14	2019/08/19	CAM SOP-00427	SM 23 5210B m
Chromium (VI) in Water	1	N/A	2019/08/15	CAM SOP-00436	EPA 7199 m
Total Cyanide	1	2019/08/15	2019/08/15	CAM SOP-00457	OMOE E3015 5 m
Fluoride	1	2019/08/13	2019/08/14	CAM SOP-00449	SM 23 4500-F C m
Mercury in Water by CVAA	1	2019/08/14	2019/08/14	CAM SOP-00453	EPA 7470A m
Total Metals Analysis by ICPMS	1	N/A	2019/08/16	CAM SOP-00447	EPA 6020B m
E.coli, (CFU/100mL)	1	N/A	2019/08/13	CAM SOP-00552	MOE LSB E3371
Total Nonylphenol in Liquids by HPLC	1	2019/08/14	2019/08/16	CAM SOP-00313	In-house Method
Nonylphenol Ethoxylates in Liquids: HPLC	1	2019/08/14	2019/08/16	CAM SOP-00313	In-house Method
Animal and Vegetable Oil and Grease	1	N/A	2019/08/17	CAM SOP-00326	EPA1664B m,SM5520B m
Total Oil and Grease	1	2019/08/17	2019/08/17	CAM SOP-00326	EPA1664B m,SM5520A m
Polychlorinated Biphenyl in Water	1	2019/08/14	2019/08/14	CAM SOP-00309	EPA 8082A m
pH	1	2019/08/14	2019/08/14	CAM SOP-00413	SM 4500H+ B m
Phenols (4AAP)	1	N/A	2019/08/14	CAM SOP-00444	OMOE E3179 m
Total Kjeldahl Nitrogen in Water	1	2019/08/14	2019/08/15	CAM SOP-00938	OMOE E3516 m
Total PAHs (1)	1	N/A	2019/08/16	CAM SOP - 00301	EPA 8270 m
Mineral/Synthetic O & G (TPH Heavy Oil) (2)	1	2019/08/17	2019/08/17	CAM SOP-00326	EPA1664B m,SM5520F m
Total Suspended Solids	1	2019/08/14	2019/08/15	CAM SOP-00428	SM 23 2540D m
Volatile Organic Compounds in Water	1	N/A	2019/08/16	CAM SOP-00228	EPA 8260C m

**Remarks:**

Bureau Veritas Laboratories are accredited to ISO/IEC 17025 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by BV Labs are based upon recognized Provincial, Federal or US method compendia such as CCME, MELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in BV Labs profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and BV Labs in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement Uncertainty has not been accounted for when stating conformity to the referenced standard.

BV Labs liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied.





Your P.O. #: ENV-BRM  
Your Project #: BRM-00607375  
Site Location: 230 THE DONWAY W  
Your C.O.C. #: 686832-11-01

**Attention: Francois Chartier**

exp Services Inc  
1595 Clark Blvd  
Brampton, ON  
CANADA L6T 4V1

**Report Date: 2019/08/19**  
Report #: R5845545  
Version: 1 - Final

**CERTIFICATE OF ANALYSIS**

**BV LABS JOB #: B9M3673**

**Received: 2019/08/13, 16:22**

BV Labs has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by BV Labs, unless otherwise agreed in writing. BV Labs is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by BV Labs, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

\* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) Total PAHs include only those PAHs specified in the sewer use by-by-law.

(2) Note: TPH (Heavy Oil) is equivalent to Mineral / Synthetic Oil & Grease

Encryption Key



**AUTHORIZED REPORT  
RAPPORT AUTORISÉ**

Bureau Veritas Laboratories

19 Aug 2019 16:56:01

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Christine Gripton, Senior Project Manager

Email: Christine.Gripton@bvlabs.com

Phone# (519)652-9444

=====  
This report has been generated and distributed using a secure automated process.

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



**TORONTO SANITARY & STORM SEWER PACKAGE (WATER)**

BV Labs ID				KMU811		
Sampling Date				2019/08/13 12:00		
COC Number				686832-11-01		
	UNITS	Criteria	Criteria-2	BH/MW2	RDL	QC Batch
<b>Calculated Parameters</b>						
Total Animal/Vegetable Oil and Grease	mg/L	150	-	ND	0.50	6276479
<b>Inorganics</b>						
Total BOD	mg/L	300	15	ND	2	6279060
Fluoride (F-)	mg/L	10	-	0.16	0.10	6277431
Total Kjeldahl Nitrogen (TKN)	mg/L	100	-	1.1	0.10	6279230
pH	pH	6.0:11.5	6.0:9.5	7.41		6277433
Phenols-4AAP	mg/L	1.0	0.008	ND	0.0010	6278746
Total Suspended Solids	mg/L	350	15	14	10	6279331
Total Cyanide (CN)	mg/L	2	0.02	ND	0.0050	6282143
<b>Petroleum Hydrocarbons</b>						
Total Oil & Grease	mg/L	-	-	ND	0.50	6285783
Total Oil & Grease Mineral/Synthetic	mg/L	15	-	ND	0.50	6285784
<b>Miscellaneous Parameters</b>						
Nonylphenol Ethoxylate (Total)	mg/L	0.2	0.01	ND	0.005	6279600
Nonylphenol (Total)	mg/L	0.02	0.001	ND	0.001	6279599
<b>Metals</b>						
Chromium (VI)	ug/L	2000	40	ND	0.50	6280118
Mercury (Hg)	mg/L	0.01	0.0004	ND	0.0001	6279288
Total Aluminum (Al)	ug/L	50000	-	140	5.0	6278919
Total Antimony (Sb)	ug/L	5000	-	0.60	0.50	6278919
Total Arsenic (As)	ug/L	1000	20	ND	1.0	6278919
Total Cadmium (Cd)	ug/L	700	8	ND	0.10	6278919
Total Chromium (Cr)	ug/L	4000	80	ND	5.0	6278919
Total Cobalt (Co)	ug/L	5000	-	1.4	0.50	6278919
Total Copper (Cu)	ug/L	2000	40	1.5	1.0	6278919
Total Iron (Fe)	ug/L	-	-	200	100	6278919
No Fill	No Exceedance					
Grey	Exceeds 1 criteria policy/level					
Black	Exceeds both criteria/levels					
RDL = Reportable Detection Limit						
QC Batch = Quality Control Batch						
Criteria: Toronto Sanitary and Combined Sewers Discharge Guidelines. Referenced to the Chapter 681.						
Criteria-2: Toronto Storm Sewer Discharge Use By-Law						
ND = Not detected						



**TORONTO SANITARY & STORM SEWER PACKAGE (WATER)**

BV Labs ID				KMU811		
Sampling Date				2019/08/13 12:00		
COC Number				686832-11-01		
	UNITS	Criteria	Criteria-2	BH/MW2	RDL	QC Batch
Total Lead (Pb)	ug/L	1000	120	ND	0.50	6278919
Total Manganese (Mn)	ug/L	5000	50	<b>140</b>	2.0	6278919
Total Molybdenum (Mo)	ug/L	5000	-	6.0	0.50	6278919
Total Nickel (Ni)	ug/L	2000	80	3.9	1.0	6278919
Total Phosphorus (P)	ug/L	10000	400	ND	100	6278919
Total Selenium (Se)	ug/L	1000	20	ND	2.0	6278919
Total Silver (Ag)	ug/L	5000	120	ND	0.10	6278919
Total Tin (Sn)	ug/L	5000	-	2.0	1.0	6278919
Total Titanium (Ti)	ug/L	5000	-	6.6	5.0	6278919
Total Zinc (Zn)	ug/L	2000	40	9.8	5.0	6278919
<b>Semivolatile Organics</b>						
Di-N-butyl phthalate	ug/L	80	15	ND	2	6281306
Bis(2-ethylhexyl)phthalate	ug/L	12	8.8	3	2	6281306
3,3'-Dichlorobenzidine	ug/L	2	0.8	ND	0.8	6281306
Pentachlorophenol	ug/L	5	2	ND	1	6281306
Phenanthrene	ug/L	-	-	ND	0.2	6281306
Anthracene	ug/L	-	-	ND	0.2	6281306
Fluoranthene	ug/L	-	-	ND	0.2	6281306
Pyrene	ug/L	-	-	ND	0.2	6281306
Benzo(a)anthracene	ug/L	-	-	ND	0.2	6281306
Chrysene	ug/L	-	-	ND	0.2	6281306
Benzo(b/j)fluoranthene	ug/L	-	-	ND	0.2	6281306
Benzo(k)fluoranthene	ug/L	-	-	ND	0.2	6281306
Benzo(a)pyrene	ug/L	-	-	ND	0.2	6281306
Indeno(1,2,3-cd)pyrene	ug/L	-	-	ND	0.2	6281306
Dibenz(a,h)anthracene	ug/L	-	-	ND	0.2	6281306
Benzo(g,h,i)perylene	ug/L	-	-	ND	0.2	6281306
No Fill	No Exceedance					
Grey	Exceeds 1 criteria policy/level					
Black	Exceeds both criteria/levels					
RDL = Reportable Detection Limit						
QC Batch = Quality Control Batch						
Criteria: Toronto Sanitary and Combined Sewers Discharge Guidelines. Referenced to the Chapter 681.						
Criteria-2: Toronto Storm Sewer Discharge Use By-Law						
ND = Not detected						



**TORONTO SANITARY & STORM SEWER PACKAGE (WATER)**

BV Labs ID				KMU811		
Sampling Date				2019/08/13 12:00		
COC Number				686832-11-01		
	UNITS	Criteria	Criteria-2	BH/MW2	RDL	QC Batch
Dibenzo(a,i)pyrene	ug/L	-	-	ND	0.2	6281306
Benzo(e)pyrene	ug/L	-	-	ND	0.2	6281306
Perylene	ug/L	-	-	ND	0.2	6281306
Dibenzo(a,j) acridine	ug/L	-	-	ND	0.4	6281306
7H-Dibenzo(c,g) Carbazole	ug/L	-	-	ND	0.4	6281306
1,6-Dinitropyrene	ug/L	-	-	ND	0.4	6281306
1,3-Dinitropyrene	ug/L	-	-	ND	0.4	6281306
1,8-Dinitropyrene	ug/L	-	-	ND	0.4	6281306
<b>Calculated Parameters</b>						
Total PAHs (18 PAHs)	ug/L	5	2	ND	1	6276901
<b>Volatile Organics</b>						
Benzene	ug/L	10	2	ND	0.40	6278824
Chloroform	ug/L	40	2	ND	0.40	6278824
1,2-Dichlorobenzene	ug/L	50	5.6	ND	1.0	6278824
1,4-Dichlorobenzene	ug/L	80	6.8	ND	1.0	6278824
cis-1,2-Dichloroethylene	ug/L	4000	5.6	ND	1.0	6278824
trans-1,3-Dichloropropene	ug/L	140	5.6	ND	0.80	6278824
Ethylbenzene	ug/L	160	2	ND	0.40	6278824
Methylene Chloride(Dichloromethane)	ug/L	2000	5.2	ND	4.0	6278824
1,1,2,2-Tetrachloroethane	ug/L	1400	17	ND	1.0	6278824
Tetrachloroethylene	ug/L	1000	4.4	ND	0.40	6278824
Toluene	ug/L	16	2	ND	0.40	6278824
Trichloroethylene	ug/L	400	7.6	ND	0.40	6278824
p+m-Xylene	ug/L	-	-	ND	0.40	6278824
o-Xylene	ug/L	-	-	ND	0.40	6278824
Total Xylenes	ug/L	1400	4.4	ND	0.40	6278824
No Fill	No Exceedance					
Grey	Exceeds 1 criteria policy/level					
Black	Exceeds both criteria/levels					
RDL = Reportable Detection Limit						
QC Batch = Quality Control Batch						
Criteria: Toronto Sanitary and Combined Sewers Discharge Guidelines. Referenced to the Chapter 681.						
Criteria-2: Toronto Storm Sewer Discharge Use By-Law						
ND = Not detected						



BUREAU  
VERITAS

BV Labs Job #: B9M3673  
Report Date: 2019/08/19

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY W  
Your P.O. #: ENV-BRM  
Sampler Initials: CS

**TORONTO SANITARY & STORM SEWER PACKAGE (WATER)**

BV Labs ID				KMU811		
Sampling Date				2019/08/13 12:00		
COC Number				686832-11-01		
	UNITS	Criteria	Criteria-2	BH/MW2	RDL	QC Batch
<b>PCBs</b>						
Total PCB	ug/L	1	0.4	ND	0.05	6278968
<b>Microbiological</b>						
Escherichia coli	CFU/100mL	-	200	30	10	6278059
<b>Surrogate Recovery (%)</b>						
2,4,6-Tribromophenol	%	-	-	92		6281306
2-Fluorobiphenyl	%	-	-	76		6281306
D14-Terphenyl (FS)	%	-	-	98		6281306
D5-Nitrobenzene	%	-	-	75		6281306
D8-Acenaphthylene	%	-	-	78		6281306
Decachlorobiphenyl	%	-	-	79		6278968
4-Bromofluorobenzene	%	-	-	93		6278824
D4-1,2-Dichloroethane	%	-	-	115		6278824
D8-Toluene	%	-	-	93		6278824
No Fill	No Exceedance					
Grey	Exceeds 1 criteria policy/level					
Black	Exceeds both criteria/levels					
RDL = Reportable Detection Limit						
QC Batch = Quality Control Batch						
Criteria: Toronto Sanitary and Combined Sewers Discharge Guidelines. Referenced to the Chapter 681.						
Criteria-2: Toronto Storm Sewer Discharge Use By-Law						
ND = Not detected						



BV Labs Job #: B9M3673  
 Report Date: 2019/08/19

exp Services Inc  
 Client Project #: BRM-00607375  
 Site Location: 230 THE DONWAY W  
 Your P.O. #: ENV-BRM  
 Sampler Initials: CS

### TEST SUMMARY

**BV Labs ID:** KMU811  
**Sample ID:** BH/MW2  
**Matrix:** Water

**Collected:** 2019/08/13  
**Shipped:**  
**Received:** 2019/08/13

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sewer Use By-Law Semivolatile Organics	GC/MS	6281306	2019/08/15	2019/08/15	Kathy Horvat
Biochemical Oxygen Demand (BOD)	DO	6279060	2019/08/14	2019/08/19	Nusrat Naz
Chromium (VI) in Water	IC	6280118	N/A	2019/08/15	Rupinder Sihota
Total Cyanide	SKAL/CN	6282143	2019/08/15	2019/08/15	Barbara Kalbasi Esfahani
Fluoride	ISE	6277431	2019/08/13	2019/08/14	Surinder Rai
Mercury in Water by CVAA	CV/AA	6279288	2019/08/14	2019/08/14	Ron Morrison
Total Metals Analysis by ICPMS	ICP/MS	6278919	N/A	2019/08/16	Arefa Dabhad
E.coli, (CFU/100mL)	PL	6278059	N/A	2019/08/13	Tharmini Sivalingam
Total Nonylphenol in Liquids by HPLC	LC/FLU	6279599	2019/08/14	2019/08/16	Dennis Boodram
Nonylphenol Ethoxylates in Liquids: HPLC	LC/FLU	6279600	2019/08/14	2019/08/16	Dennis Boodram
Animal and Vegetable Oil and Grease	BAL	6276479	N/A	2019/08/17	Automated Statchk
Total Oil and Grease	BAL	6285783	2019/08/17	2019/08/17	Gurseerat singh gill
Polychlorinated Biphenyl in Water	GC/ECD	6278968	2019/08/14	2019/08/14	Svitlana Shaula
pH	AT	6277433	2019/08/14	2019/08/14	Surinder Rai
Phenols (4AAP)	TECH/PHEN	6278746	N/A	2019/08/14	Bramdeo Motiram
Total Kjeldahl Nitrogen in Water	SKAL	6279230	2019/08/14	2019/08/15	Rajni Tyagi
Total PAHs	CALC	6276901	N/A	2019/08/16	Automated Statchk
Mineral/Synthetic O & G (TPH Heavy Oil)	BAL	6285784	2019/08/17	2019/08/17	Gurseerat singh gill
Total Suspended Solids	BAL	6279331	2019/08/14	2019/08/15	Xinyue (Sarah) Hou
Volatile Organic Compounds in Water	GC/MS	6278824	N/A	2019/08/16	Manpreet Sarao



BUREAU  
VERITAS

BV Labs Job #: B9M3673  
Report Date: 2019/08/19

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY W  
Your P.O. #: ENV-BRM  
Sampler Initials: CS

### GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	16.3°C
-----------	--------

Sample KMU811 [BH/MW2] : VOC Analysis: Due to the sample matrix, sample required dilution. Detection limits were adjusted accordingly.

**Results relate only to the items tested.**



BUREAU VERITAS

BV Labs Job #: B9M3673  
Report Date: 2019/08/19

### QUALITY ASSURANCE REPORT

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY W  
Your P.O. #: ENV-BRM  
Sampler Initials: CS

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
6278824	4-Bromofluorobenzene	2019/08/15	102	70 - 130	101	70 - 130	97	%				
6278824	D4-1,2-Dichloroethane	2019/08/15	109	70 - 130	103	70 - 130	105	%				
6278824	D8-Toluene	2019/08/15	102	70 - 130	102	70 - 130	94	%				
6278968	Decachlorobiphenyl	2019/08/14	89	60 - 130	81	60 - 130	73	%				
6281306	2,4,6-Tribromophenol	2019/08/15	95	10 - 130	90	10 - 130	78	%				
6281306	2-Fluorobiphenyl	2019/08/15	85	30 - 130	82	30 - 130	71	%				
6281306	D14-Terphenyl (TS)	2019/08/15	95	30 - 130	96	30 - 130	92	%				
6281306	D5-Nitrobenzene	2019/08/15	89	30 - 130	77	30 - 130	69	%				
6281306	D8-Acenaphthylene	2019/08/15	82	30 - 130	82	30 - 130	74	%				
6277431	Fluoride (F-)	2019/08/14	98	80 - 120	102	80 - 120	ND, RDL=0.10	mg/L	4.7		20	
6277433	pH	2019/08/14			102	98 - 103	ND, RDL=0.0010	mg/L	0.58		N/A	
6278746	Phenols-4AAP	2019/08/14	103	80 - 120	102	80 - 120	ND, RDL=0.0010	mg/L	0		20	
6278824	1,1,2,2-Tetrachloroethane	2019/08/15	113	70 - 130	101	70 - 130	ND, RDL=0.50	ug/L	NC		30	
6278824	1,2-Dichlorobenzene	2019/08/15	96	70 - 130	91	70 - 130	ND, RDL=0.50	ug/L	NC		30	
6278824	1,4-Dichlorobenzene	2019/08/15	100	70 - 130	97	70 - 130	ND, RDL=0.50	ug/L	NC		30	
6278824	Benzene	2019/08/15	97	70 - 130	94	70 - 130	ND, RDL=0.20	ug/L	NC		30	
6278824	Chloroform	2019/08/15	96	70 - 130	90	70 - 130	ND, RDL=0.20	ug/L	NC		30	
6278824	cis-1,2-Dichloroethylene	2019/08/15	93	70 - 130	90	70 - 130	ND, RDL=0.50	ug/L	1.7		30	
6278824	Ethylbenzene	2019/08/15	92	70 - 130	91	70 - 130	ND, RDL=0.20	ug/L	NC		30	
6278824	Methylene Chloride(Dichloromethane)	2019/08/15	102	70 - 130	97	70 - 130	ND, RDL=2.0	ug/L	NC		30	
6278824	o-Xylene	2019/08/15	94	70 - 130	96	70 - 130	ND, RDL=0.20	ug/L	NC		30	
6278824	p-m-Xylene	2019/08/15	101	70 - 130	101	70 - 130	ND, RDL=0.20	ug/L	NC		30	
6278824	Tetrachloroethylene	2019/08/15	90	70 - 130	87	70 - 130	ND, RDL=0.20	ug/L	NC		30	
6278824	Toluene	2019/08/15	94	70 - 130	92	70 - 130	ND, RDL=0.20	ug/L	NC		30	
6278824	Total Xylenes	2019/08/15					ND, RDL=0.20	ug/L	NC		30	
6278824	trans-1,3-Dichloropropene	2019/08/15	108	70 - 130	100	70 - 130	ND, RDL=0.40	ug/L	NC		30	
6278824	Trichloroethylene	2019/08/15	98	70 - 130	95	70 - 130	ND, RDL=0.20	ug/L	NC		30	
6278919	Total Aluminum (Al)	2019/08/16	NC (1)	80 - 120	100	80 - 120	ND, RDL=5.0	ug/L	8.1		20	
6278919	Total Antimony (Sb)	2019/08/16	NC (1)	80 - 120	102	80 - 120	ND, RDL=0.50	ug/L	1.7		20	





BUREAU  
VERITAS

BV Labs Job #: B9M3673  
Report Date: 2019/08/19

**QUALITY ASSURANCE REPORT(CONT'D)**

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY W  
Your P.O. #: ENV-BRM  
Sampler Initials: CS

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
6278919	Total Arsenic (As)	2019/08/16	NC (1)	80 - 120	102	80 - 120	ND, RDL=1.0	ug/L	6.6	NC	20	
6278919	Total Cadmium (Cd)	2019/08/16	NC (1)	80 - 120	100	80 - 120	ND, RDL=0.10	ug/L	NC	NC	20	
6278919	Total Chromium (Cr)	2019/08/16	NC (1)	80 - 120	96	80 - 120	ND, RDL=5.0	ug/L	NC	NC	20	
6278919	Total Cobalt (Co)	2019/08/16	NC (1)	80 - 120	97	80 - 120	ND, RDL=0.50	ug/L	NC	NC	20	
6278919	Total Copper (Cu)	2019/08/16	NC (1)	80 - 120	104	80 - 120	ND, RDL=1.0	ug/L	NC	NC	20	
6278919	Total Iron (Fe)	2019/08/16	NC (1)	80 - 120	99	80 - 120	ND, RDL=100	ug/L	3.6	NC	20	
6278919	Total Lead (Pb)	2019/08/16	NC (1)	80 - 120	99	80 - 120	ND, RDL=0.50	ug/L	NC	NC	20	
6278919	Total Manganese (Mn)	2019/08/16	NC (1)	80 - 120	97	80 - 120	ND, RDL=2.0	ug/L	4.3	NC	20	
6278919	Total Molybdenum (Mo)	2019/08/16	NC (1)	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	9.0	NC	20	
6278919	Total Nickel (Ni)	2019/08/16	NC (1)	80 - 120	96	80 - 120	ND, RDL=1.0	ug/L	NC	NC	20	
6278919	Total Phosphorus (P)	2019/08/16	NC (1)	80 - 120	105	80 - 120	ND, RDL=100	ug/L	0.26	NC	20	
6278919	Total Selenium (Se)	2019/08/16	NC (1)	80 - 120	103	80 - 120	ND, RDL=2.0	ug/L	NC	NC	20	
6278919	Total Silver (Ag)	2019/08/16	NC (1)	80 - 120	99	80 - 120	ND, RDL=0.10	ug/L	NC	NC	20	
6278919	Total Tin (Sn)	2019/08/16	NC (1)	80 - 120	100	80 - 120	ND, RDL=1.0	ug/L	NC	NC	20	
6278919	Total Titanium (Ti)	2019/08/16	NC (1)	80 - 120	95	80 - 120	ND, RDL=5.0	ug/L	NC	NC	20	
6278919	Total Zinc (Zn)	2019/08/16	NC (1)	80 - 120	102	80 - 120	ND, RDL=5.0	ug/L	11	NC	20	
6278968	Total PCB	2019/08/14	101	60 - 130	78	60 - 130	ND, RDL=0.05	ug/L	NC	NC	40	
6279060	Total BOD	2019/08/19					ND, RDL=2	mg/L	NC	NC	30	104
6279230	Total Kjeldahl Nitrogen (TKN)	2019/08/15	99	80 - 120	101	80 - 120	ND, RDL=0.10	mg/L	4.6	NC	20	93
6279288	Mercury (Hg)	2019/08/14	98	75 - 125	101	80 - 120	ND, RDL=0.0001	mg/L	NC	NC	20	
6279331	Total Suspended Solids	2019/08/15					ND, RDL=10	mg/L	NC	NC	25	95
6279599	Nonylphenol (Total)	2019/08/16	116	50 - 130	105	50 - 130	ND, RDL=0.001	mg/L	NC	NC	40	
6279600	Nonylphenol Ethoxylate (Total)	2019/08/16	113	50 - 130	99	50 - 130	ND, RDL=0.005	mg/L	NC	NC	40	
6280118	Chromium (VI)	2019/08/15	99	80 - 120	100	80 - 120	ND, RDL=0.50	ug/L	NC	NC	20	
6281306	1,3-Dinitropyrene	2019/08/16	31	30 - 130	81	30 - 130	ND, RDL=0.4	ug/L	NC	NC	40	
6281306	1,6-Dinitropyrene	2019/08/16	40	30 - 130	88	30 - 130	ND, RDL=0.4	ug/L	NC	NC	40	
6281306	1,8-Dinitropyrene	2019/08/16	57	30 - 130	59	30 - 130	ND, RDL=0.4	ug/L	NC	NC	40	



BV Labs Job #: B9M3673  
Report Date: 2019/08/19

**QUALITY ASSURANCE REPORT(CONT'D)**

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY W  
Your P.O. #: ENV-BRM  
Sampler Initials: CS

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
6281306	3,3'-Dichlorobenzidine	2019/08/16	58	30 - 130	67	30 - 130	ND, RDL=0.8	ug/L	NC	40		
6281306	7H-Dibenzol(c,g) Carbazole	2019/08/16	98	30 - 130	101	30 - 130	ND, RDL=0.4	ug/L	NC	40		
6281306	Anthracene	2019/08/16	86	30 - 130	89	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Benzo(a)anthracene	2019/08/16	102	30 - 130	105	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Benzo(a)pyrene	2019/08/16	89	30 - 130	98	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Benzo(b,j)fluoranthene	2019/08/16	85	30 - 130	96	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Benzo(e)pyrene	2019/08/16	86	30 - 130	95	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Benzo(g,h,i)perylene	2019/08/16	106	30 - 130	111	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Benzo(k)fluoranthene	2019/08/16	96	30 - 130	98	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Bis(2-ethylhexyl)phthalate	2019/08/16	99	30 - 130	103	30 - 130	ND, RDL=2	ug/L	NC	40		
6281306	Chrysene	2019/08/16	89	30 - 130	95	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Dibenz(a,h)anthracene	2019/08/16	110	30 - 130	113	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Dibenz(a,i)pyrene	2019/08/16	115	30 - 130	125	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Dibenz(a,j)acridine	2019/08/16	94	30 - 130	102	30 - 130	ND, RDL=0.4	ug/L	NC	40		
6281306	Di-N-butyl phthalate	2019/08/16	91	30 - 130	98	30 - 130	ND, RDL=2	ug/L	NC	40		
6281306	Fluoranthene	2019/08/16	101	30 - 130	100	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Indeno(1,2,3-cd)pyrene	2019/08/16	106	30 - 130	111	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Pentachlorophenol	2019/08/16	89	30 - 130	78	30 - 130	ND, RDL=1	ug/L	NC	40		
6281306	Perylene	2019/08/16	96	30 - 130	96	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Phenanthrene	2019/08/16	90	30 - 130	91	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6281306	Pyrene	2019/08/16	102	30 - 130	102	30 - 130	ND, RDL=0.2	ug/L	NC	40		
6282143	Total Cyanide (CN)	2019/08/15	103	80 - 120	96	80 - 120	ND, RDL=0.0050	mg/L	NC	20		
6285783	Total Oil & Grease	2019/08/17			95	85 - 115	ND, RDL=0.50	mg/L	3.9	25		



BUREAU  
VERITAS

BV Labs Job #: B9M3673  
Report Date: 2019/08/19

### QUALITY ASSURANCE REPORT(CONT'D)

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY W  
Your P.O. #: ENV-BRM  
Sampler Initials: CS

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
6285784	Total Oil & Grease Mineral/Synthetic	2019/08/17			99	85 - 115	ND, RDL=0.50	mg/L	4.1		25	

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

Surrogate: A pure or isotopically labeled compound whose behavior mirrors the analytes of interest. Used to evaluate extraction efficiency.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spike amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than the native sample concentration)

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).

(1) Matrix Spike not calculated. Original sample and matrix spike sample were analyzed at a dilution, due to high target analytes, or sample matrix interference.



BUREAU  
VERITAS

BV Labs Job #: B9M3673  
Report Date: 2019/08/19

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY W  
Your P.O. #: ENV-BRM  
Sampler Initials: CS

### VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

\_\_\_\_\_  
Anastassia Hamanov, Scientific Specialist

\_\_\_\_\_  
Tharmini Sivalingam, Supervisor, Food Microbiology Laboratory

---

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Maxxam Analytical International Corporation via Maxxam Analytics  
 6740 Camphorwood Road, Mississauga, Ontario Canada L5N 2L8 Tel: (905) 817-5790 Toll-Free: 800-563-0266 Fax: (905) 817-5777 www.maxxam.ca

CHAIN OF CUSTODY RECORD

INVOICE TO: **EXP SERVICES INC**  
 Company Name: #9590 exp Services Inc  
 Attention: Central Services  
 Address: 1595 Clark Blvd  
 Brampton ON L6T 4V1  
 Tel: (905) 793-9800 Fax: (905) 793-0941  
 Email: Karen.Burke@exp.com, AP@exp.com

REPORT TO: **EXP SERVICES INC**  
 Company Name: F Charlier, ~~EXP SERVICES INC~~  
 Attention: CHARLIER, SIMON @EXP.COM  
 Address: (905) 793-9800 Ext. 2523 Fax: (905) 793-9800  
 Email: Francois.Charlier@exp.com, ~~EXP SERVICES INC~~

PROJECT INFORMATION:  
 Duration #: **PHASE 3 STE 61172**  
 P.O.#: **SHAWNEE ENV-BEM**  
 Project: **BRIMWOOD/STEVENS BEM-CO607375**  
 Project Name: **230 THE DONWAY W**  
 Site #: **20V376 VEG DONWAY/STEVENS**  
 Sampled By: **CS**

Laboratory Use Only:  
 Maxxam Job #: **PHASE 3 STE 61172** Bottle Order #: **658932**  
 Project Manager: **Tanya Fidin**

MOE REGULATED DRINKING WATER OR WATER INTENDED FOR HUMAN CONSUMPTION MUST BE SUBMITTED ON THE MAXXAM DRINKING WATER CHAIN OF CUSTODY

ANALYSIS REQUESTED (PLEASE BE SPECIFIC):  
**13-Aug-19 16:22**  
**Tanya Fidin**  
**B9M3673**  
**MAF ENV-592**

Regular (Standard) TAT:  (will be applied if Rush TAT is not specified)  
 Standard TAT = 5-7 Working Days for most tests.  
 Please note: Standard TAT for certain tests such as BOD and Dissolved Solids are > 5 days - contact your Project Manager for details.  
 Job Specific Rush TAT (if applies to entire submission):  
 Rush Confirmation Number: \_\_\_\_\_ Time Required: \_\_\_\_\_  
 (call lab for #) \_\_\_\_\_

Sample Barcode Label	Sample Location/Identification	Date Sampled	Time Sampled	Matrix	Field Filtered (please circle): Metals / Hg / Cr VI	ANALYSIS REQUESTED (PLEASE BE SPECIFIC)	# of Batches	Comments
BH1MW 2		13/08/19	12:00 PM	GW	N	TORONTO SANITARY and STORM Bylaw Comprehensive Plus Iron	19	5 DAY FIRM TURN AROUND TIME PLEASE

RELINQUISHED BY: (Signature/Print) **Chanelle Simon** Date: (YY/MM/DD) **19/08/19** Time: **16:20 PM**

RECEIVED BY: (Signature/Print) **Donna Ainsworth** Date: (YY/MM/DD) **20/08/19** Time: **16:22**

Laboratory Use Only:  
 Temperature (°C) on Receipt: **18/14/17/10C**  
 Custody Seal Present: **Yes**  
 White: Maxxam Yellow: Client

UNLESS OTHERWISE AGREED TO IN WRITING, WORK SUBMITTED ON THIS CHAIN OF CUSTODY IS SUBJECT TO MAXXAM'S STANDARD TERMS AND CONDITIONS. SIGNING OF THIS CHAIN OF CUSTODY DOCUMENT IS ACKNOWLEDGMENT AND ACCEPTANCE OF OUR TERMS WHICH ARE AVAILABLE FOR VIEWING AT WWW.MAXXAM.CA/TERMS.  
 IT IS THE RESPONSIBILITY OF THE RELINQUISHER TO ENSURE THE ACCURACY OF THE CHAIN OF CUSTODY RECORD. AN INCOMPLETE CHAIN OF CUSTODY MAY RESULT IN ANALYTICAL TAT DELAYS.  
 \*\* SAMPLE CONTAINER, PRESERVATION, HOLD TIME AND PACKAGE INFORMATION CAN BE VIEWED AT HTTP://MAXXAM.CAMP-CONTENT/UPLOAD/ONTARIO-COC.PDF.



BUREAU  
VERITAS

BV Labs Job #: B9M3673  
Report Date: 2019/08/19

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY W  
Your P.O. #: ENV-BRM  
Sampler Initials: CS

**Exceedence Summary Table – Toronto Sanitary Sewer**  
**Result Exceedences**

Sample ID	BV Labs ID	Parameter	Criteria	Result	DL	Units
No Exceedences						
The exceedence summary table is for information purposes only and should not be considered a comprehensive listing or statement of conformance to applicable regulatory guidelines.						

**Exceedence Summary Table – Toronto Storm Sewer**  
**Result Exceedences**

Sample ID	BV Labs ID	Parameter	Criteria	Result	DL	Units
BH/MW2	KMU811-12	Total Manganese (Mn)	50	140	2.0	ug/L
The exceedence summary table is for information purposes only and should not be considered a comprehensive listing or statement of conformance to applicable regulatory guidelines.						



Your P.O. #: ENV-BRM  
 Your Project #: BRM-00607375  
 Site Location: 230 THE DONWAY  
 Your C.O.C. #: 828273-05-01

**Attention: Francois Chartier**

exp Services Inc  
 1595 Clark Blvd  
 Brampton, ON  
 CANADA L6T 4V1

**Report Date: 2021/10/19**  
 Report #: R6858754  
 Version: 3 - Final

**CERTIFICATE OF ANALYSIS**

**BV LABS JOB #: C1T2443**

**Received: 2021/10/07, 19:16**

Sample Matrix: Water  
 # Samples Received: 1

Analyses	Quantity	Date	Date	Laboratory Method	Analytical Method
		Extracted	Analyzed		
Sewer Use By-Law Semivolatile Organics	1	2021/10/12	2021/10/13	CAM SOP 00301	EPA 8270 m
Biochemical Oxygen Demand (BOD)	1	2021/10/09	2021/10/14	CAM SOP-00427	SM 23 5210B m
Chromium (VI) in Water	1	N/A	2021/10/13	CAM SOP-00436	EPA 7199 m
Total Cyanide	1	2021/10/13	2021/10/13	CAM SOP-00457	OMOE E3015 5 m
Fluoride	1	2021/10/13	2021/10/14	CAM SOP-00449	SM 23 4500-F C m
Mercury in Water by CVAA	1	2021/10/13	2021/10/13	CAM SOP-00453	EPA 7470A m
Total Metals Analysis by ICPMS	1	N/A	2021/10/18	CAM SOP-00447	EPA 6020B m
E.coli, (CFU/100mL)	1	N/A	2021/10/07	CAM SOP-00552	MOE LSB E3371
Total Nonylphenol in Liquids by HPLC	1	2021/10/08	2021/10/09	CAM SOP-00313	In-house Method
Nonylphenol Ethoxylates in Liquids: HPLC	1	2021/10/08	2021/10/09	CAM SOP-00313	In-house Method
Animal and Vegetable Oil and Grease	1	N/A	2021/10/17	CAM SOP-00326	EPA1664B m,SM5520B m
Total Oil and Grease	1	2021/10/17	2021/10/17	CAM SOP-00326	EPA1664B m,SM5520B m
Polychlorinated Biphenyl in Water	1	2021/10/08	2021/10/09	CAM SOP-00309	EPA 8082A m
pH	1	2021/10/13	2021/10/14	CAM SOP-00413	SM 4500H+ B m
Phenols (4AAP)	1	N/A	2021/10/08	CAM SOP-00444	OMOE E3179 m
Total Kjeldahl Nitrogen in Water	1	2021/10/13	2021/10/14	CAM SOP-00938	OMOE E3516 m
Total PAHs (1)	1	N/A	2021/10/14	CAM SOP - 00301	
Mineral/Synthetic O & G (TPH Heavy Oil) (2)	1	2021/10/17	2021/10/17	CAM SOP-00326	EPA1664B m,SM5520F m
Total Suspended Solids	1	2021/10/13	2021/10/14	CAM SOP-00428	SM 23 2540D m
Volatile Organic Compounds in Water	1	N/A	2021/10/13	CAM SOP-00228	EPA 8260C m

**Remarks:**

Bureau Veritas is accredited to ISO/IEC 17025 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Bureau Veritas are based upon recognized Provincial, Federal or US method compendia such as CCME, MELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Bureau Veritas' profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Bureau Veritas in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement Uncertainty has not been accounted for when stating conformity to the referenced standard.

Bureau Veritas liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or



Your P.O. #: ENV-BRM  
Your Project #: BRM-00607375  
Site Location: 230 THE DONWAY  
Your C.O.C. #: 828273-05-01

**Attention: Francois Chartier**

exp Services Inc  
1595 Clark Blvd  
Brampton, ON  
CANADA L6T 4V1

**Report Date: 2021/10/19**  
Report #: R6858754  
Version: 3 - Final

**CERTIFICATE OF ANALYSIS**

**BV LABS JOB #: C1T2443**

**Received: 2021/10/07, 19:16**

implied. Bureau Veritas has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Bureau Veritas, unless otherwise agreed in writing. Bureau Veritas is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by Bureau Veritas, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

\* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) Total PAHs include only those PAHs specified in the sewer use by-by-law.

(2) Note: TPH (Heavy Oil) is equivalent to Mineral / Synthetic Oil & Grease

Encryption Key



**AUTHORIZED REPORT  
RAPPORT AUTORISÉ**

Bureau Veritas

19 Oct 2021 10:24:43

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Patricia Legette, Project Manager

Email: Patricia.Legette@bureauveritas.com

Phone# (905)817-5799

=====  
BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.





BUREAU VERITAS

Bureau Veritas Job #: C1T2443  
Report Date: 2021/10/19

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY  
Your P.O. #: ENV-BRM  
Sampler Initials: TM

### TORONTO SANITARY&STORM SEWER (100-2016)

Bureau Veritas ID				QWN927		
Sampling Date				2021/10/07 11:00		
COC Number				828273-05-01		
	UNITS	Criteria	Criteria-2	BH106	RDL	QC Batch
<b>Calculated Parameters</b>						
Total Animal/Vegetable Oil and Grease	mg/L	150	-	ND	0.50	7624482
<b>Inorganics</b>						
Total BOD	mg/L	300	15	ND	2	7628961
Fluoride (F-)	mg/L	10	-	0.47	0.10	7635150
Total Kjeldahl Nitrogen (TKN)	mg/L	100	-	2.1	0.10	7633933
pH	pH	6.0:11.5	6.0:9.5	8.00		7635165
Phenols-4AAP	mg/L	1.0	0.008	ND	0.0010	7626724
Total Suspended Solids	mg/L	350	15	15	10	7632093
Total Cyanide (CN)	mg/L	2	0.02	ND	0.0050	7633473
<b>Petroleum Hydrocarbons</b>						
Total Oil & Grease	mg/L	-	-	ND	0.50	7641987
Total Oil & Grease Mineral/Synthetic	mg/L	15	-	ND	0.50	7641988
<b>Miscellaneous Parameters</b>						
Nonylphenol Ethoxylate (Total)	mg/L	0.2	0.01	ND	0.005	7626469
Nonylphenol (Total)	mg/L	0.02	0.001	ND	0.001	7626464
<b>Metals</b>						
Chromium (VI)	ug/L	2000	40	ND	0.50	7634115
Mercury (Hg)	mg/L	0.01	0.0004	ND	0.00010	7633746
Total Aluminum (Al)	ug/L	50000	-	1200	4.9	7635958
Total Antimony (Sb)	ug/L	5000	-	0.50	0.50	7635958
Total Arsenic (As)	ug/L	1000	20	3.0	1.0	7635958
Total Cadmium (Cd)	ug/L	700	8	ND	0.090	7635958
Total Chromium (Cr)	ug/L	4000	80	ND	5.0	7635958
Total Cobalt (Co)	ug/L	5000	-	ND	0.50	7635958
Total Copper (Cu)	ug/L	2000	40	2.7	0.90	7635958
Total Lead (Pb)	ug/L	1000	120	ND	0.50	7635958
No Fill	No Exceedance					
Grey	Exceeds 1 criteria policy/level					
Black	Exceeds both criteria/levels					
RDL = Reportable Detection Limit						
QC Batch = Quality Control Batch						
Criteria: Toronto Sanitary and Combined Sewers Discharge Guidelines. Referenced to the Chapter 681.						
Criteria-2: Toronto Storm Sewer Discharge Use By-Law						
ND = Not Detected at a concentration equal or greater than the indicated Detection Limit.						



**TORONTO SANITARY&STORM SEWER (100-2016)**

Bureau Veritas ID				QWN927		
Sampling Date				2021/10/07 11:00		
COC Number				828273-05-01		
	UNITS	Criteria	Criteria-2	BH106	RDL	QC Batch
Total Manganese (Mn)	ug/L	5000	50	65	2.0	7635958
Total Molybdenum (Mo)	ug/L	5000	-	23	0.50	7635958
Total Nickel (Ni)	ug/L	2000	80	1.7	1.0	7635958
Total Phosphorus (P)	ug/L	10000	400	110	100	7635958
Total Selenium (Se)	ug/L	1000	20	ND	2.0	7635958
Total Silver (Ag)	ug/L	5000	120	ND	0.090	7635958
Total Tin (Sn)	ug/L	5000	-	3.5	1.0	7635958
Total Titanium (Ti)	ug/L	5000	-	43	5.0	7635958
Total Zinc (Zn)	ug/L	2000	40	ND	5.0	7635958
<b>Semivolatile Organics</b>						
Di-N-butyl phthalate	ug/L	80	15	ND	2	7631469
Bis(2-ethylhexyl)phthalate	ug/L	12	8.8	ND	2	7631469
3,3'-Dichlorobenzidine	ug/L	2	0.8	ND	0.8	7631469
Pentachlorophenol	ug/L	5	2	ND	1	7631469
Phenanthrene	ug/L	-	-	ND	0.2	7631469
Anthracene	ug/L	-	-	ND	0.2	7631469
Fluoranthene	ug/L	-	-	ND	0.2	7631469
Pyrene	ug/L	-	-	ND	0.2	7631469
Benzo(a)anthracene	ug/L	-	-	ND	0.2	7631469
Chrysene	ug/L	-	-	ND	0.2	7631469
Benzo(b/j)fluoranthene	ug/L	-	-	ND	0.2	7631469
Benzo(k)fluoranthene	ug/L	-	-	ND	0.2	7631469
Benzo(a)pyrene	ug/L	-	-	ND	0.2	7631469
Indeno(1,2,3-cd)pyrene	ug/L	-	-	ND	0.2	7631469
Dibenzo(a,h)anthracene	ug/L	-	-	ND	0.2	7631469
Benzo(g,h,i)perylene	ug/L	-	-	ND	0.2	7631469
Dibenzo(a,i)pyrene	ug/L	-	-	ND	0.2	7631469
No Fill	No Exceedance					
Grey	Exceeds 1 criteria policy/level					
Black	Exceeds both criteria/levels					
RDL = Reportable Detection Limit						
QC Batch = Quality Control Batch						
Criteria: Toronto Sanitary and Combined Sewers Discharge Guidelines. Referenced to the Chapter 681.						
Criteria-2: Toronto Storm Sewer Discharge Use By-Law						
ND = Not Detected at a concentration equal or greater than the indicated Detection Limit.						



BUREAU  
VERITAS

Bureau Veritas Job #: C1T2443  
Report Date: 2021/10/19

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY  
Your P.O. #: ENV-BRM  
Sampler Initials: TM

### TORONTO SANITARY&STORM SEWER (100-2016)

Bureau Veritas ID				QWN927		
Sampling Date				2021/10/07 11:00		
COC Number				828273-05-01		
	UNITS	Criteria	Criteria-2	BH106	RDL	QC Batch
Benzo(e)pyrene	ug/L	-	-	ND	0.2	7631469
Perylene	ug/L	-	-	ND	0.2	7631469
Dibenzo(a,j) acridine	ug/L	-	-	ND	0.4	7631469
7H-Dibenzo(c,g) Carbazole	ug/L	-	-	ND	0.4	7631469
1,6-Dinitropyrene	ug/L	-	-	ND	0.4	7631469
1,3-Dinitropyrene	ug/L	-	-	ND	0.4	7631469
1,8-Dinitropyrene	ug/L	-	-	ND	0.4	7631469
<b>Calculated Parameters</b>						
Total PAHs (18 PAHs)	ug/L	5	2	ND	1	7626029
<b>Volatile Organics</b>						
Benzene	ug/L	10	2	ND	0.20	7626489
Chloroform	ug/L	40	2	1.8	0.20	7626489
1,2-Dichlorobenzene	ug/L	50	5.6	ND	0.40	7626489
1,4-Dichlorobenzene	ug/L	80	6.8	ND	0.40	7626489
cis-1,2-Dichloroethylene	ug/L	4000	5.6	ND	0.50	7626489
trans-1,3-Dichloropropene	ug/L	140	5.6	ND	0.40	7626489
Ethylbenzene	ug/L	160	2	ND	0.20	7626489
Methylene Chloride(Dichloromethane)	ug/L	2000	5.2	ND	2.0	7626489
1,1,2,2-Tetrachloroethane	ug/L	1400	17	ND	0.40	7626489
Tetrachloroethylene	ug/L	1000	4.4	ND	0.20	7626489
Toluene	ug/L	16	2	ND	0.20	7626489
Trichloroethylene	ug/L	400	7.6	ND	0.20	7626489
p+m-Xylene	ug/L	-	-	ND	0.20	7626489
o-Xylene	ug/L	-	-	ND	0.20	7626489
Total Xylenes	ug/L	1400	4.4	ND	0.20	7626489
<b>PCBs</b>						
Total PCB	ug/L	1	0.4	ND	0.05	7627873
No Fill	No Exceedance					
Grey	Exceeds 1 criteria policy/level					
Black	Exceeds both criteria/levels					
RDL = Reportable Detection Limit						
QC Batch = Quality Control Batch						
Criteria: Toronto Sanitary and Combined Sewers Discharge Guidelines. Referenced to the Chapter 681.						
Criteria-2: Toronto Storm Sewer Discharge Use By-Law						
ND = Not Detected at a concentration equal or greater than the indicated Detection Limit.						



BUREAU  
VERITAS

Bureau Veritas Job #: C1T2443  
Report Date: 2021/10/19

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY  
Your P.O. #: ENV-BRM  
Sampler Initials: TM

**TORONTO SANITARY&STORM SEWER (100-2016)**

<b>Bureau Veritas ID</b>				QWN927		
<b>Sampling Date</b>				2021/10/07 11:00		
<b>COC Number</b>				828273-05-01		
	<b>UNITS</b>	<b>Criteria</b>	<b>Criteria-2</b>	<b>BH106</b>	<b>RDL</b>	<b>QC Batch</b>
<b>Microbiological</b>						
Escherichia coli	CFU/100mL	-	200	<10	10	7626013
<b>Surrogate Recovery (%)</b>						
2,4,6-Tribromophenol	%	-	-	78		7631469
2-Fluorobiphenyl	%	-	-	46		7631469
D14-Terphenyl (FS)	%	-	-	77		7631469
D5-Nitrobenzene	%	-	-	66		7631469
D8-Acenaphthylene	%	-	-	57		7631469
Decachlorobiphenyl	%	-	-	98		7627873
4-Bromofluorobenzene	%	-	-	91		7626489
D4-1,2-Dichloroethane	%	-	-	110		7626489
D8-Toluene	%	-	-	90		7626489
No Fill	No Exceedance					
Grey	Exceeds 1 criteria policy/level					
Black	Exceeds both criteria/levels					
RDL = Reportable Detection Limit						
QC Batch = Quality Control Batch						
Criteria: Toronto Sanitary and Combined Sewers Discharge Guidelines. Referenced to the Chapter 681.						
Criteria-2: Toronto Storm Sewer Discharge Use By-Law						



BUREAU  
VERITAS

Bureau Veritas Job #: C1T2443  
Report Date: 2021/10/19

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY  
Your P.O. #: ENV-BRM  
Sampler Initials: TM

### TEST SUMMARY

**Bureau Veritas ID:** QWN927  
**Sample ID:** BH106  
**Matrix:** Water

**Collected:** 2021/10/07  
**Shipped:**  
**Received:** 2021/10/07

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sewer Use By-Law Semivolatile Organics	GC/MS	7631469	2021/10/12	2021/10/13	Adriana Zurita
Biochemical Oxygen Demand (BOD)	DO	7628961	2021/10/09	2021/10/14	Surleen Kaur Romana
Chromium (VI) in Water	IC	7634115	N/A	2021/10/13	Lang Le
Total Cyanide	SKAL/CN	7633473	2021/10/13	2021/10/13	Nimarta Singh
Fluoride	ISE	7635150	2021/10/13	2021/10/14	Surinder Rai
Mercury in Water by CVAA	CV/AA	7633746	2021/10/13	2021/10/13	Gagandeep Rai
Total Metals Analysis by ICPMS	ICP/MS	7635958	N/A	2021/10/18	Arefa Dabhad
E.coli, (CFU/100mL)	PL	7626013	N/A	2021/10/07	Soham Patel
Total Nonylphenol in Liquids by HPLC	LC/FLU	7626464	2021/10/08	2021/10/09	Dennis Boodram
Nonylphenol Ethoxylates in Liquids: HPLC	LC/FLU	7626469	2021/10/08	2021/10/09	Dennis Boodram
Animal and Vegetable Oil and Grease	BAL	7624482	N/A	2021/10/17	Automated Statchk
Total Oil and Grease	BAL	7641987	2021/10/17	2021/10/17	Mitul Patel
Polychlorinated Biphenyl in Water	GC/ECD	7627873	2021/10/08	2021/10/09	Joy Zhang
pH	AT	7635165	2021/10/13	2021/10/14	Surinder Rai
Phenols (4AAP)	TECH/PHEN	7626724	N/A	2021/10/08	Deonarine Ramnarine
Total Kjeldahl Nitrogen in Water	SKAL	7633933	2021/10/13	2021/10/14	Rajni Tyagi
Total PAHs	CALC	7626029	N/A	2021/10/14	Automated Statchk
Mineral/Synthetic O & G (TPH Heavy Oil)	BAL	7641988	2021/10/17	2021/10/17	Mitul Patel
Total Suspended Solids	BAL	7632093	2021/10/13	2021/10/14	Shaneil Hall
Volatile Organic Compounds in Water	GC/MS	7626489	N/A	2021/10/13	Chandni Khawas



BUREAU  
VERITAS

Bureau Veritas Job #: C1T2443  
Report Date: 2021/10/19

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY  
Your P.O. #: ENV-BRM  
Sampler Initials: TM

### GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	10.7°C
-----------	--------

**Results relate only to the items tested.**



**BUREAU**  
**VERITAS**

Bureau Veritas Job #: C1T2443  
Report Date: 2021/10/19

**QUALITY ASSURANCE REPORT**

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY  
Your P.O. #: ENV-BRM  
Sampler Initials: TM

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
7626489	4-Bromofluorobenzene	2021/10/12	102	70 - 130	102	70 - 130	95	%				
7626489	D4-1,2-Dichloroethane	2021/10/12	101	70 - 130	98	70 - 130	102	%				
7626489	D8-Toluene	2021/10/12	104	70 - 130	103	70 - 130	92	%				
7627873	Decachlorobiphenyl	2021/10/09	97	60 - 130	76	60 - 130	85	%				
7631469	2,4,6-Tribromophenol	2021/10/13	95	10 - 130	94	10 - 130	90	%				
7631469	2-Fluorobiphenyl	2021/10/13	82	30 - 130	78	30 - 130	59	%				
7631469	D14-Terphenyl (FS)	2021/10/13	83	30 - 130	81	30 - 130	88	%				
7631469	D5-Nitrobenzene	2021/10/13	87	30 - 130	83	30 - 130	81	%				
7631469	D8-Acenaphthylene	2021/10/13	86	30 - 130	82	30 - 130	72	%				
7626464	Nonylphenol (Total)	2021/10/13	111	50 - 130	111	50 - 130	ND, RDL=0.001	mg/L	1.1		40	
7626469	Nonylphenol Ethoxylate (Total)	2021/10/13	96	50 - 130	96	50 - 130	ND, RDL=0.005	mg/L	NC		40	
7626489	1,1,2,2-Tetrachloroethane	2021/10/12	93	70 - 130	94	70 - 130	ND, RDL=0.40	ug/L	NC		30	
7626489	1,2-Dichlorobenzene	2021/10/12	90	70 - 130	93	70 - 130	ND, RDL=0.40	ug/L	NC		30	
7626489	1,4-Dichlorobenzene	2021/10/12	106	70 - 130	110	70 - 130	ND, RDL=0.40	ug/L	NC		30	
7626489	Benzene	2021/10/12	87	70 - 130	85	70 - 130	ND, RDL=0.20	ug/L	NC		30	
7626489	Chloroform	2021/10/12	92	70 - 130	91	70 - 130	ND, RDL=0.20	ug/L	NC		30	
7626489	cis-1,2-Dichloroethylene	2021/10/12	97	70 - 130	94	70 - 130	ND, RDL=0.50	ug/L	NC		30	
7626489	Ethylbenzene	2021/10/12	85	70 - 130	87	70 - 130	ND, RDL=0.20	ug/L	NC		30	
7626489	Methylene Chloride(Dichloromethane)	2021/10/12	107	70 - 130	103	70 - 130	ND, RDL=2.0	ug/L	NC		30	
7626489	o-Xylene	2021/10/12	83	70 - 130	90	70 - 130	ND, RDL=0.20	ug/L	NC		30	
7626489	p-m-Xylene	2021/10/12	89	70 - 130	92	70 - 130	ND, RDL=0.20	ug/L	NC		30	
7626489	Tetrachloroethylene	2021/10/12	85	70 - 130	85	70 - 130	ND, RDL=0.20	ug/L	NC		30	
7626489	Toluene	2021/10/12	90	70 - 130	90	70 - 130	ND, RDL=0.20	ug/L	3.0		30	
7626489	Total Xylenes	2021/10/12					ND, RDL=0.20	ug/L	NC		30	
7626489	trans-1,3-Dichloropropene	2021/10/12	109	70 - 130	100	70 - 130	ND, RDL=0.40	ug/L	NC		30	
7626489	Trichloroethylene	2021/10/12	95	70 - 130	95	70 - 130	ND, RDL=0.20	ug/L	NC		30	
7626724	Phenols-4AAP	2021/10/08	100	80 - 120	101	80 - 120	ND, RDL=0.0010	mg/L	4.5		20	



BUREAU  
VERITAS

Bureau Veritas Job #: C1T2443  
Report Date: 2021/10/19

### QUALITY ASSURANCE REPORT(CONT'D)

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY  
Your P.O. #: ENV-BRM  
Sampler Initials: TM

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
7627873	Total PCB	2021/10/09	90	60 - 130	94	60 - 130	ND, RDL=0.05	ug/L	NC	40		
7628961	Total BOD	2021/10/14					ND, RDL=2	mg/L	NC	30		80 - 120
7631469	1,3-Dinitropyrene	2021/10/13	80	30 - 130	102	30 - 130	ND, RDL=0.4	ug/L	NC	40		
7631469	1,6-Dinitropyrene	2021/10/13	76	30 - 130	120	30 - 130	ND, RDL=0.4	ug/L	NC	40		
7631469	1,8-Dinitropyrene	2021/10/13	111	30 - 130	130	30 - 130	ND, RDL=0.4	ug/L	NC	40		
7631469	3,3'-Dichlorobenzidine	2021/10/13	77	30 - 130	111	30 - 130	ND, RDL=0.8	ug/L	NC	40		
7631469	7H-Dibenzol(c,g) Carbazole	2021/10/13	103	30 - 130	124	30 - 130	ND, RDL=0.4	ug/L	NC	40		
7631469	Anthracene	2021/10/13	105	30 - 130	104	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Benzo(a)anthracene	2021/10/13	93	30 - 130	91	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Benzo(a)pyrene	2021/10/13	97	30 - 130	101	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Benzo(b)jfluoranthene	2021/10/13	106	30 - 130	107	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Benzo(e)pyrene	2021/10/13	108	30 - 130	112	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Benzo(g,h,i)perylene	2021/10/13	108	30 - 130	121	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Benzo(k)fluoranthene	2021/10/13	101	30 - 130	110	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Bis(2-ethylhexyl)phthalate	2021/10/13	108	30 - 130	110	30 - 130	ND, RDL=2	ug/L	NC	40		
7631469	Chrysene	2021/10/13	107	30 - 130	114	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Dibenzol(a,h)anthracene	2021/10/13	102	30 - 130	113	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Dibenzol(a,i)pyrene	2021/10/13	100	30 - 130	113	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Dibenzol(a,j) acridine	2021/10/13	88	30 - 130	114	30 - 130	ND, RDL=0.4	ug/L	NC	40		
7631469	Di-N-butyl phthalate	2021/10/13	109	30 - 130	104	30 - 130	ND, RDL=2	ug/L	NC	40		
7631469	Fluoranthene	2021/10/13	102	30 - 130	103	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Indeno(1,2,3-cd)pyrene	2021/10/13	101	30 - 130	110	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Pentachlorophenol	2021/10/13	56	30 - 130	65	30 - 130	ND, RDL=1	ug/L	NC	40		
7631469	Perylene	2021/10/13	105	30 - 130	118	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Phenanthrene	2021/10/13	106	30 - 130	105	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7631469	Pyrene	2021/10/13	104	30 - 130	103	30 - 130	ND, RDL=0.2	ug/L	NC	40		
7632093	Total Suspended Solids	2021/10/14					ND, RDL=10	mg/L	2,4	25		85 - 115
7633473	Total Cyanide (CN)	2021/10/13	99	80 - 120	103	80 - 120	ND, RDL=0.0050	mg/L	NC	20		





BUREAU  
VERITAS

Bureau Veritas Job #: C1T2443  
Report Date: 2021/10/19

### QUALITY ASSURANCE REPORT(CONT'D)

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY  
Your P.O. #: ENV-BRM  
Sampler Initials: TM

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
7633746	Mercury (Hg)	2021/10/13	88	75 - 125	91	80 - 120	ND, RDL=0.00010	mg/L	NC		20	
7633933	Total Kjeldahl Nitrogen (TKN)	2021/10/14	95	80 - 120	99	80 - 120	ND, RDL=0.10	mg/L	NC (1)	20	97	80 - 120
7634115	Chromium (VI)	2021/10/13	100	80 - 120	101	80 - 120	ND, RDL=0.50	ug/L	NC	20		
7635150	Fluoride (F-)	2021/10/14	99	80 - 120	99	80 - 120	ND, RDL=0.10	mg/L	4.2	20		
7635165	pH	2021/10/14			101	98 - 103			0.45	N/A		
7635958	Total Aluminium (Al)	2021/10/18	NC	80 - 120	102	80 - 120	ND, RDL=4.9	ug/L				
7635958	Total Antimony (Sb)	2021/10/18	104	80 - 120	95	80 - 120	ND, RDL=0.50	ug/L				
7635958	Total Arsenic (As)	2021/10/18	96	80 - 120	93	80 - 120	ND, RDL=1.0	ug/L				
7635958	Total Cadmium (Cd)	2021/10/18	98	80 - 120	93	80 - 120	ND, RDL=0.090	ug/L				
7635958	Total Chromium (Cr)	2021/10/18	96	80 - 120	93	80 - 120	ND, RDL=5.0	ug/L				
7635958	Total Cobalt (Co)	2021/10/18	102	80 - 120	97	80 - 120	ND, RDL=0.50	ug/L				
7635958	Total Copper (Cu)	2021/10/18	104	80 - 120	98	80 - 120	ND, RDL=0.90	ug/L				
7635958	Total Lead (Pb)	2021/10/18	97	80 - 120	95	80 - 120	ND, RDL=0.50	ug/L	0.89	20		
7635958	Total Manganese (Mn)	2021/10/18	94	80 - 120	94	80 - 120	ND, RDL=2.0	ug/L				
7635958	Total Molybdenum (Mo)	2021/10/18	100	80 - 120	91	80 - 120	ND, RDL=0.50	ug/L				
7635958	Total Nickel (Ni)	2021/10/18	95	80 - 120	94	80 - 120	ND, RDL=1.0	ug/L				
7635958	Total Phosphorus (P)	2021/10/18	93	80 - 120	91	80 - 120	ND, RDL=100	ug/L				
7635958	Total Selenium (Se)	2021/10/18	89	80 - 120	99	80 - 120	ND, RDL=2.0	ug/L				
7635958	Total Silver (Ag)	2021/10/18	97	80 - 120	93	80 - 120	ND, RDL=0.090	ug/L				
7635958	Total Tin (Sn)	2021/10/18	102	80 - 120	93	80 - 120	ND, RDL=1.0	ug/L				
7635958	Total Titanium (Ti)	2021/10/18	99	80 - 120	90	80 - 120	ND, RDL=5.0	ug/L				
7635958	Total Zinc (Zn)	2021/10/18	96	80 - 120	95	80 - 120	ND, RDL=5.0	ug/L				
7641987	Total Oil & Grease	2021/10/17			98	85 - 115	ND, RDL=0.50	mg/L	1.3	25		



**QUALITY ASSURANCE REPORT(CONT'D)**

exp Services Inc  
 Client Project #: BRM-00607375  
 Site Location: 230 THE DONWAY  
 Your P.O. #: ENV-BRM  
 Sampler Initials: TM

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
7641988	Total Oil & Grease Mineral/Synthetic	2021/10/17			95	85 - 115	ND, RDL=0.50	mg/L	1.6		25	

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

Surrogate: A pure or isotopically labeled compound whose behavior mirrors the analytes of interest. Used to evaluate extraction efficiency.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spike amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than the native sample concentration)

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).

(1) Due to a high concentration of NOx, the sample required dilution. The detection limit was adjusted accordingly.



BUREAU  
VERITAS

Bureau Veritas Job #: C1T2443  
Report Date: 2021/10/19

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY  
Your P.O. #: ENV-BRM  
Sampler Initials: TM

### VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by:

---

Anastassia Hamanov, Scientific Specialist

---

Soham Patel, Analyst 2

---

---

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Bureau Veritas Laboratories  
 6172 Campbell Road, Mississauga, Ontario Canada L5N 2L8 Tel: (905) 817-5700 Toll-free 800-563-6266 Fax: (905) 817-5777 www.bvlabs.com

CHAIN OF CUSTODY RECORD

INVOICE TO: **EXP Services Inc** REPORT TO: **EXP Services Inc**

Company Name: **EXP Services Inc** Attention: **Francis Charlier**

Address: **1595 Clark Blvd Brampton ON L6T 4V1** Address: **Thabiso Modise @ exp.com**

Tel: **(905) 793-9800** Fax: **(905) 793-0641** Tel: **(905) 793-9800 Ext. 2523** Fax: **(905) 793-9800**

Email: **AP@exp.com; Karen.Burke@exp.com** Email: **Francis.Charlier@exp.com**

Quotation #: **B91717**

P.O.#: **ENV-6RM**

Project: **BRM-00601375**

Project Name: **230 The Downeaw**

Site #: **Thabiso Modise**

Sampled By: **Thabiso Modise**

BV Labs Job #: **628273**

COC #: **628273**

Project Manager: **Patricia Legette**

**MOE REGULATED DRINKING WATER OR WATER INTENDED FOR HUMAN CONSUMPTION MUST BE SUBMITTED ON THE BV LABS DRINKING WATER CHAIN OF CUSTODY**

Regulation 153 (2011)

Table 1  Res/Park  Medium/Fine  CCME  Sanitary Sewer Bylaw

Table 2  Ind/Comm  Course  Reg 556  MSA  Municipality **TORONTO**

Table 3  Agr/Other  For RSC  PWSO  Reg 405 Table

Other Regulations:  Other

Special Instructions: **Field Filtered (please circle): Metals / Hg / Cr VI**

Include Criteria on Certificate of Analysis (Y/N)?

ANALYSIS REQUESTED (PLEASE BE SPECIFIC): **Toronto Sanitary & Storm Sewer Package**

Turnaround Time (TAT) Required:  Please provide advance notice for rush projects

Regular (Standard) TAT: **19** (not applicable / Rush TAT is not specified)

Standard TAT = 5-7 Working days for most tests.

Please note: Standard TAT for certain tests such as BOD and DBO/Forms are = 5 days - contact your Project Manager for details.

Job Specific Rush TAT (if applies to entire submission): **19**

Date Required: **19**

Rush Confirmation Number: **TAT**

Time Required: **5 DAY**

Sample Barcode Label	Sample Location/Identification	Date Sampled	Time Sampled	Matrix	Field Filtered (please circle): Metals / Hg / Cr VI	Quotation #	P.O.#	Project	Project Name	Site #	Sampled By:	BV Labs Job #:	COC #:	Project Manager:
1	BH 106	7/10/07	11:00	GW	<input checked="" type="checkbox"/>	B91717	ENV-6RM	BRM-00601375	230 The Downeaw	Thabiso Modise	Thabiso Modise	628273	628273	Patricia Legette
2														
3														
4														
5														
6														
7														
8														
9														
10														

\* RELINQUISHED BY: (Signature/Print) **Patricia Legette** RECEIVED BY: (Signature/Print) **Thabiso Modise**

Date: (Y/M/DD) **21/10/07** Date: (Y/M/DD) **19/10/07**

Time: \_\_\_\_\_ Time: \_\_\_\_\_

# of Bottles: **19**

Temperature (°C) on Receipt: **10/12/10**

Laboratory Use Only: **100**

Custody Seal: **100**

Project: **100**

Yes  No

White: BV Labs Yellow: Client

UNLESS OTHERWISE AGREED TO IN WRITING, WORK SUBMITTED ON THIS CHAIN OF CUSTODY IS SUBJECT TO BV LABS' STANDARD TERMS AND CONDITIONS. SIGNING OF THIS CHAIN OF CUSTODY DOCUMENT IS ACKNOWLEDGMENT AND ACCEPTANCE OF OUR TERMS WHICH ARE AVAILABLE FOR VIEWING AT WWW.BVLABS.COM/TERMS-AND-CONDITIONS.

IT IS THE RESPONSIBILITY OF THE RELINQUISHER TO ENSURE THE ACCURACY OF THE CHAIN OF CUSTODY RECORD. AN INCOMPLETE CHAIN OF CUSTODY MAY RESULT IN ANALYTICAL TAT DELAYS.

\*\* SAMPLE CONTAINER, PRESERVATION, HOLD TIME AND PACKAGE INFORMATION CAN BE VIEWED AT WWW.BVLABS.COM/RESOURCES/CHAIN-OF-CUSTODY-FORMS.

Bureau Veritas Canada (2019) Inc.



BUREAU  
VERITAS

Bureau Veritas Job #: C1T2443  
Report Date: 2021/10/19

exp Services Inc  
Client Project #: BRM-00607375  
Site Location: 230 THE DONWAY  
Your P.O. #: ENV-BRM  
Sampler Initials: TM

**Exceedance Summary Table – Toronto Sanitary Sewer**  
**Result Exceedances**

Sample ID	Bureau Veritas ID	Parameter	Criteria	Result	DL	UNITS
-----------	-------------------	-----------	----------	--------	----	-------

No Exceedances

The exceedance summary table is for information purposes only and should not be considered a comprehensive listing or statement of conformance to applicable regulatory guidelines.

**Exceedance Summary Table – Toronto Storm Sewer**  
**Result Exceedances**

Sample ID	Bureau Veritas ID	Parameter	Criteria	Result	DL	UNITS
-----------	-------------------	-----------	----------	--------	----	-------

BH106	QWN927-07	Total Manganese (Mn)	50	65	2.0	ug/L
-------	-----------	----------------------	----	----	-----	------

The exceedance summary table is for information purposes only and should not be considered a comprehensive listing or statement of conformance to applicable regulatory guidelines.



Invoice Information		Report Information (if differs from invoice)		Project Information (where applicable)		Turnaround Time (TAT) Required									
Company Name: <b>EXP</b>		Company Name:		Quotation #:		<input checked="" type="checkbox"/> Regular TAT (5-7 days) Most analyses									
Contact Name: <b>Samuel Lee</b>		Contact Name:		P.O. #/ AFER:		PLEASE PROVIDE ADVANCE NOTICE FOR RUSH PROJECTS									
Address:		Address:		Project #: <b>BHM-00607375-A0</b>		Rush TAT (Surcharges will be applied)									
Phone: Fax:		Phone: Fax:		Site Location: <b>230 The Danway W.</b>		<input type="checkbox"/> 1 Day <input type="checkbox"/> 2 Days <input type="checkbox"/> 3-4 Days									
Email: <b>Samuel.Lee@exp.com</b>		Email: <b>Andrew.Niedzialek@exp.com</b>		Site #:		Date Required:									
MDE REGULATED DRINKING WATER OR WATER INTENDED FOR HUMAN CONSUMPTION MUST BE SUBMITTED ON THE MAXXAM DRINKING WATER CHAIN OF CUSTODY				Site Location Province:		Rush Confirmation #:									
Regulation 153		Other Regulations		Analysis Requested				LABORATORY USE ONLY							
<input type="checkbox"/> Table 1 <input checked="" type="checkbox"/> Res/Park <input type="checkbox"/> Med/ Fine <input checked="" type="checkbox"/> Table 2 <input type="checkbox"/> Ind/Comm <input type="checkbox"/> Coarse <input type="checkbox"/> Table 3 <input type="checkbox"/> Agri/ Other <input type="checkbox"/> Table _____ FOR RSC (PLEASE CIRCLE) <b>Y / N</b>		<input type="checkbox"/> CCME <input type="checkbox"/> Sanitary Sewer Bylaw <input type="checkbox"/> MISA <input type="checkbox"/> Storm Sewer Bylaw <input type="checkbox"/> PWQO Region <input type="checkbox"/> Other (Specify) <input type="checkbox"/> REG 558 (MIN. 3 DAY TAT REQUIRED)		# OF CONTAINERS SUBMITTED FIELD FILTERED (CIRCLE) <b>PHOSPHATE / ZINC</b> BTX/ PHC F1 PHCS F2 - F4 VOCs REG 153 METALS & INORGANICS REG 153 ICPMS METALS + Hg REG 153 METALS (Hg, Cr VI, ICPMS Metals, HWS - B)				CUSTODY SEAL Y / N Present Intact COOLING MEDIA PRESENT: <b>Y / N</b>		COOLER TEMPERATURES <b>10/9/13</b>					
Include Criteria on Certificate of Analysis: <b>O / N</b>								COMMENTS							
SAMPLES MUST BE KEPT COOL (< 10 °C) FROM TIME OF SAMPLING UNTIL DELIVERY TO MAXXAM															
SAMPLE IDENTIFICATION		DATE SAMPLED (YYYY/MM/DD)	TIME SAMPLED (HH:MM)	MATRIX	# OF CONTAINERS SUBMITTED	FIELD FILTERED (CIRCLE)	PHOSPHATE / ZINC	BTX/ PHC F1	PHCS F2 - F4	VOCs	REG 153 METALS & INORGANICS	REG 153 ICPMS METALS + Hg	REG 153 METALS (Hg, Cr VI, ICPMS Metals, HWS - B)	COOLING MEDIA PRESENT: Y / N	COMMENTS
1	MWB	2019/08/09	3:00	GW	7	/	/	/	/	/	/	/	/		
2	MWB6	↓	3:00	1	7	/	/	/	/	/	/	/	/		
3	Trip Blank				3	/	/	/	/	/	/	/	/		
4															
5															
6															
7															
8															
9															
10															
RELINQUISHED BY: (Signature/Print)		DATE: (YYYY/MM/DD)	TIME: (HH:MM)	RECEIVED BY: (Signature/Print)		DATE: (YYYY/MM/DD)	TIME: (HH:MM)								
<b>Andrew Niedzialek</b>		<b>2019/08/09</b>	<b>9:45</b>	<b>A. Niedzialek</b>		<b>2019/08/09</b>	<b>1646</b>								


09-Aug-19 16:46

Christine Gripton  
  
**B9M1129**


KFL ENV-1233

Unless otherwise agreed to in writing, work submitted on this Chain of Custody is subject to Maxxam's standard Terms and Conditions. Signing of this Chain of Custody document is acknowledgment and acceptance of our terms. Sample container, preservation, hold time and packages information can be viewed at <http://maxxam.ca/wp-content/uploads/Ontario-COC.pdf>.

**Petroleum Hydrocarbons F2-F4 in Water Chromatogram**



Reference Spectrum



**TYPICAL PRODUCT CARBON NUMBER RANGES**

Gasoline: C6 - C12  
 Varsol: C8 - C12  
 Kerosene: C8 - C16


Diesel: C10 - C24  
 Fuel Oils: C6 - C32  
 Motor Oils: C16 - C50

Jet Fuels: C6 - C16  
 Creosote: C10 - C26  
 Asphalt: C18 - C50+


**Note: This information is provided for reference purposes only. Should detailed chemist interpretation or fingerprinting be required, please contact the laboratory.**



**Petroleum Hydrocarbons F2-F4 in Water Chromatogram**



Reference Spectrum



**TYPICAL PRODUCT CARBON NUMBER RANGES**


Gasoline: C6 - C12  
 Varsol: C8 - C12  
 Kerosene: C8 - C16

Diesel: C10 - C24  
 Fuel Oils: C6 - C32  
 Motor Oils: C16 - C50


Jet Fuels: C6 - C16  
 Creosote: C10 - C26  
 Asphalt: C18 - C50+

**Note: This information is provided for reference purposes only. Should detailed chemist interpretation or fingerprinting be required, please contact the laboratory.**

**Petroleum Hydrocarbons F2-F4 in Water Chromatogram**



Reference Spectrum



**TYPICAL PRODUCT CARBON NUMBER RANGES**

Gasoline: C6 - C12  
 Varsol: C8 - C12  
 Kerosene: C8 - C16

Diesel: C10 - C24  
 Fuel Oils: C6 - C32  
 Motor Oils: C16 - C50

Jet Fuels: C6 - C16  
 Creosote: C10 - C26  
 Asphalt: C18 - C50+

**Note: This information is provided for reference purposes only. Should detailed chemist interpretation or fingerprinting be required, please contact the laboratory.**



Your Project #: BRM-00607375-A0  
 Site Location: 230 THE DONWAY W.  
 Your C.O.C. #: 132475

**Attention: Samuel Lee**

exp Services Inc  
 1595 Clark Blvd  
 Brampton, ON  
 CANADA L6T 4V1

**Report Date: 2019/08/30**  
 Report #: R5860820  
 Version: 2 - Revision

**CERTIFICATE OF ANALYSIS – REVISED REPORT**

**BV LABS JOB #: B9M1129**

**Received: 2019/08/09, 16:46**

Sample Matrix: Water  
 # Samples Received: 3

Analyses	Quantity	Date	Date	Laboratory Method	Reference
		Extracted	Analyzed		
Chromium (VI) in Water	2	N/A	2019/08/14	CAM SOP-00436	EPA 7199 m
Petroleum Hydro. CCME F1 & BTEX in Water	1	N/A	2019/08/13	CAM SOP-00315	CCME PHC-CWS m
Petroleum Hydro. CCME F1 & BTEX in Water	2	N/A	2019/08/14	CAM SOP-00315	CCME PHC-CWS m
Petroleum Hydrocarbons F2-F4 in Water (1)	3	2019/08/14	2019/08/15	CAM SOP-00316	CCME PHC-CWS m
Mercury	2	2019/08/12	2019/08/12	CAM SOP-00453	EPA 7470A m
Dissolved Metals by ICPMS	2	N/A	2019/08/15	CAM SOP-00447	EPA 6020B m

**Remarks:**

Bureau Veritas Laboratories are accredited to ISO/IEC 17025 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by BV Labs are based upon recognized Provincial, Federal or US method compendia such as CCME, MELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in BV Labs profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and BV Labs in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement Uncertainty has not been accounted for when stating conformity to the referenced standard.

BV Labs liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. BV Labs has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by BV Labs, unless otherwise agreed in writing. BV Labs is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by BV Labs, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

\* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) All CCME PHC results met required criteria unless otherwise stated in the report. The CWS PHC methods employed by Bureau Veritas Laboratories conform to all prescribed elements of the reference method and performance based elements have been validated. All modifications have been validated and proven equivalent following "Alberta Environment's Interpretation of the Reference Method for the Canada-Wide Standard for Petroleum Hydrocarbons in Soil Validation of Performance-Based Alternative Methods September 2003". Documentation is available upon request. Modifications from Reference Method for the Canada-wide Standard for Petroleum Hydrocarbons in Soil-Tier 1 Method: F2/F3/F4 data reported using validated cold solvent extraction instead of Soxhlet extraction.



Your Project #: BRM-00607375-A0  
Site Location: 230 THE DONWAY W.  
Your C.O.C. #: 132475

**Attention: Samuel Lee**

exp Services Inc  
1595 Clark Blvd  
Brampton, ON  
CANADA L6T 4V1

**Report Date: 2019/08/30**  
Report #: R5860820  
Version: 2 - Revision

**CERTIFICATE OF ANALYSIS – REVISED REPORT**

**BV LABS JOB #: B9M1129**

**Received: 2019/08/09, 16:46**

Encryption Key

Christine Gripton  
Senior Project Manager  
30 Aug 2019 12:04:50

Please direct all questions regarding this Certificate of Analysis to your Project Manager.  
Christine Gripton, Senior Project Manager  
Email: Christine.Gripton@bvlabs.com  
Phone# (519)652-9444

=====  
BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



BUREAU  
VERITAS

BV Labs Job #: B9M1129  
Report Date: 2019/08/30

exp Services Inc  
Client Project #: BRM-00607375-A0  
Site Location: 230 THE DONWAY W.  
Sampler Initials: AN

**O.REG 153 METALS PACKAGE (WATER)**

BV Labs ID				KMF592			KMF592			KMF593		
Sampling Date				2019/08/09 15:00			2019/08/09 15:00			2019/08/09 15:00		
COC Number				132475			132475			132475		
	<b>UNITS</b>	<b>San</b>	<b>Stm</b>	<b>MW6</b>	<b>RDL</b>	<b>QC Batch</b>	<b>MW6 Lab-Dup</b>	<b>RDL</b>	<b>QC Batch</b>	<b>MW66</b>	<b>RDL</b>	<b>QC Batch</b>

<b>Metals</b>												
Chromium (VI)	ug/L	2000	40	<0.50	0.50	6274845				<0.50	0.50	6274845
Mercury (Hg)	ug/L	10	0.4	<0.1	0.1	6274323	<0.1	0.1	6274323	<0.1	0.1	6274323
Dissolved Antimony (Sb)	ug/L	5000	-	<0.50	0.50	6274547				<0.50	0.50	6274547
Dissolved Arsenic (As)	ug/L	1000	20	<1.0	1.0	6274547				<1.0	1.0	6274547
Dissolved Barium (Ba)	ug/L	-	-	290	2.0	6274547				290	2.0	6274547
Dissolved Beryllium (Be)	ug/L	-	-	<0.50	0.50	6274547				<0.50	0.50	6274547
Dissolved Boron (B)	ug/L	-	-	130	10	6274547				130	10	6274547
Dissolved Cadmium (Cd)	ug/L	700	8	<0.10	0.10	6274547				<0.10	0.10	6274547
Dissolved Chromium (Cr)	ug/L	4000	80	<5.0	5.0	6274547				<5.0	5.0	6274547
Dissolved Cobalt (Co)	ug/L	5000	-	<0.50	0.50	6274547				<0.50	0.50	6274547
Dissolved Copper (Cu)	ug/L	2000	40	3.1	1.0	6274547				1.2	1.0	6274547
Dissolved Lead (Pb)	ug/L	1000	120	<0.50	0.50	6274547				<0.50	0.50	6274547
Dissolved Molybdenum (Mo)	ug/L	5000	-	2.2	0.50	6274547				2.1	0.50	6274547
Dissolved Nickel (Ni)	ug/L	2000	80	<1.0	1.0	6274547				<1.0	1.0	6274547
Dissolved Selenium (Se)	ug/L	1000	20	<2.0	2.0	6274547				<2.0	2.0	6274547
Dissolved Silver (Ag)	ug/L	5000	120	<0.10	0.10	6274547				<0.10	0.10	6274547
Dissolved Thallium (Tl)	ug/L	-	-	<0.050	0.050	6274547				<0.050	0.050	6274547
Dissolved Uranium (U)	ug/L	-	-	0.72	0.10	6274547				0.65	0.10	6274547
Dissolved Vanadium (V)	ug/L	-	-	1.2	0.50	6274547				1.2	0.50	6274547
Dissolved Zinc (Zn)	ug/L	2000	40	5.3	5.0	6274547				<5.0	5.0	6274547

No Fill	No Exceedance
Grey	Exceeds 1 criteria policy/level
Black	Exceeds both criteria/levels
RDL = Reportable Detection Limit	
QC Batch = Quality Control Batch	
Lab-Dup = Laboratory Initiated Duplicate	
San,Stm: Toronto Sanitary and Storm Sewer Use By Law Guidelines, respectively. Referenced to Chapter 681	



BUREAU  
VERITAS

BV Labs Job #: B9M1129  
Report Date: 2019/08/30

exp Services Inc  
Client Project #: BRM-00607375-A0  
Site Location: 230 THE DONWAY W.  
Sampler Initials: AN

**O.REG 153 PHCS, BTEX/F1-F4 (WATER)**

BV Labs ID				KMF592	KMF593	KMF594		
Sampling Date				2019/08/09 15:00	2019/08/09 15:00			
COC Number				132475	132475	132475		
	<b>UNITS</b>	<b>San</b>	<b>Stm</b>	<b>MW6</b>	<b>MW66</b>	<b>TRIP BLANK</b>	<b>RDL</b>	<b>QC Batch</b>
<b>BTEX &amp; F1 Hydrocarbons</b>								
Benzene	ug/L	10	2	1.4	1.3	<0.20	0.20	6276929
Toluene	ug/L	16	2	<0.20	<0.20	<0.20	0.20	6276929
Ethylbenzene	ug/L	160	2	1.4	1.5	<0.20	0.20	6276929
o-Xylene	ug/L	1400	4.4	<0.20	<0.20	<0.20	0.20	6276929
p+m-Xylene	ug/L	1400	4.4	<0.40	<0.40	<0.40	0.40	6276929
Total Xylenes	ug/L	1400	4.4	<0.40	<0.40	<0.40	0.40	6276929
F1 (C6-C10)	ug/L	-	-	<25	<25	<25	25	6276929
F1 (C6-C10) - BTEX	ug/L	-	-	<25	<25	<25	25	6276929
<b>F2-F4 Hydrocarbons</b>								
F2 (C10-C16 Hydrocarbons)	ug/L	-	-	<100	<100	<100	100	6279824
F3 (C16-C34 Hydrocarbons)	ug/L	-	-	<200	<200	<200	200	6279824
F4 (C34-C50 Hydrocarbons)	ug/L	-	-	<200	<200	<200	200	6279824
Reached Baseline at C50	ug/L	-	-	Yes	Yes	Yes		6279824
<b>Surrogate Recovery (%)</b>								
1,4-Difluorobenzene	%	-	-	101	100	102		6276929
4-Bromofluorobenzene	%	-	-	97	99	98		6276929
D10-Ethylbenzene	%	-	-	99	100	99		6276929
D4-1,2-Dichloroethane	%	-	-	99	99	99		6276929
o-Terphenyl	%	-	-	111	112	112		6279824
No Fill	No Exceedance							
Grey	Exceeds 1 criteria policy/level							
Black	Exceeds both criteria/levels							
RDL = Reportable Detection Limit								
QC Batch = Quality Control Batch								
San,Stm: Toronto Sanitary and Storm Sewer Use By Law Guidelines, respectively. Referenced to Chapter 681								



BV Labs Job #: B9M1129  
 Report Date: 2019/08/30

exp Services Inc  
 Client Project #: BRM-00607375-A0  
 Site Location: 230 THE DONWAY W.  
 Sampler Initials: AN

**TEST SUMMARY**

**BV Labs ID:** KMF592  
**Sample ID:** MW6  
**Matrix:** Water

**Collected:** 2019/08/09  
**Shipped:**  
**Received:** 2019/08/09

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chromium (VI) in Water	IC	6274845	N/A	2019/08/14	Lang Le
Petroleum Hydro. CCME F1 & BTEX in Water	HSGC/MSFD	6276929	N/A	2019/08/13	Haibin Wu
Petroleum Hydrocarbons F2-F4 in Water	GC/FID	6279824	2019/08/14	2019/08/15	Prabhjot Gulati
Mercury	CV/AA	6274323	2019/08/12	2019/08/12	Ron Morrison
Dissolved Metals by ICPMS	ICP/MS	6274547	N/A	2019/08/15	Matthew Ritenburg

**BV Labs ID:** KMF592 Dup  
**Sample ID:** MW6  
**Matrix:** Water

**Collected:** 2019/08/09  
**Shipped:**  
**Received:** 2019/08/09

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Mercury	CV/AA	6274323	2019/08/12	2019/08/12	Ron Morrison

**BV Labs ID:** KMF593  
**Sample ID:** MW66  
**Matrix:** Water

**Collected:** 2019/08/09  
**Shipped:**  
**Received:** 2019/08/09

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chromium (VI) in Water	IC	6274845	N/A	2019/08/14	Lang Le
Petroleum Hydro. CCME F1 & BTEX in Water	HSGC/MSFD	6276929	N/A	2019/08/14	Haibin Wu
Petroleum Hydrocarbons F2-F4 in Water	GC/FID	6279824	2019/08/14	2019/08/15	Prabhjot Gulati
Mercury	CV/AA	6274323	2019/08/12	2019/08/12	Ron Morrison
Dissolved Metals by ICPMS	ICP/MS	6274547	N/A	2019/08/15	Matthew Ritenburg

**BV Labs ID:** KMF594  
**Sample ID:** TRIP BLANK  
**Matrix:** Water

**Collected:**  
**Shipped:**  
**Received:** 2019/08/09

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Petroleum Hydro. CCME F1 & BTEX in Water	HSGC/MSFD	6276929	N/A	2019/08/14	Haibin Wu
Petroleum Hydrocarbons F2-F4 in Water	GC/FID	6279824	2019/08/14	2019/08/15	Prabhjot Gulati



BUREAU  
VERITAS

BV Labs Job #: B9M1129  
Report Date: 2019/08/30

exp Services Inc  
Client Project #: BRM-00607375-A0  
Site Location: 230 THE DONWAY W.  
Sampler Initials: AN

### GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	9.7°C
-----------	-------

Revised report [2019/08/30]: Includes Toronto Sewer Use bylaw criteria.

**Results relate only to the items tested.**





BUREAU  
VERITAS

BV Labs Job #: B9M1129  
Report Date: 2019/08/30

### QUALITY ASSURANCE REPORT

exp Services Inc  
Client Project #: BRM-00607375-A0  
Site Location: 230 THE DONWAY W.  
Sampler Initials: AN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits
6276929	1,4-Difluorobenzene	2019/08/13	98	70 - 130	100	70 - 130	101	%		
6276929	4-Bromofluorobenzene	2019/08/13	100	70 - 130	99	70 - 130	97	%		
6276929	D10-Ethylbenzene	2019/08/13	100	70 - 130	103	70 - 130	102	%		
6276929	D4-1,2-Dichloroethane	2019/08/13	100	70 - 130	101	70 - 130	101	%		
6279824	o-Terphenyl	2019/08/15	109	60 - 130	107	60 - 130	110	%		
6274323	Mercury (Hg)	2019/08/12	96	75 - 125	105	80 - 120	<0.1	ug/L	NC	20
6274547	Dissolved Antimony (Sb)	2019/08/15	106	80 - 120	101	80 - 120	<0.50	ug/L	NC	20
6274547	Dissolved Arsenic (As)	2019/08/15	102	80 - 120	99	80 - 120	<1.0	ug/L	NC	20
6274547	Dissolved Barium (Ba)	2019/08/15	104	80 - 120	103	80 - 120	<2.0	ug/L	0.49	20
6274547	Dissolved Beryllium (Be)	2019/08/15	103	80 - 120	100	80 - 120	<0.50	ug/L	NC	20
6274547	Dissolved Boron (B)	2019/08/15	107	80 - 120	107	80 - 120	<10	ug/L	4.7	20
6274547	Dissolved Cadmium (Cd)	2019/08/15	103	80 - 120	99	80 - 120	<0.10	ug/L	NC	20
6274547	Dissolved Chromium (Cr)	2019/08/15	101	80 - 120	100	80 - 120	<5.0	ug/L	NC	20
6274547	Dissolved Cobalt (Co)	2019/08/15	99	80 - 120	98	80 - 120	<0.50	ug/L	NC	20
6274547	Dissolved Copper (Cu)	2019/08/15	104	80 - 120	103	80 - 120	<1.0	ug/L	NC	20
6274547	Dissolved Lead (Pb)	2019/08/15	95	80 - 120	95	80 - 120	<0.50	ug/L	NC	20
6274547	Dissolved Molybdenum (Mo)	2019/08/15	109	80 - 120	102	80 - 120	<0.50	ug/L	3.8	20
6274547	Dissolved Nickel (Ni)	2019/08/15	98	80 - 120	98	80 - 120	<1.0	ug/L	4.2	20
6274547	Dissolved Selenium (Se)	2019/08/15	101	80 - 120	100	80 - 120	<2.0	ug/L	NC	20
6274547	Dissolved Silver (Ag)	2019/08/15	97	80 - 120	98	80 - 120	<0.10	ug/L	NC	20
6274547	Dissolved Thallium (Tl)	2019/08/15	95	80 - 120	94	80 - 120	<0.050	ug/L	NC	20
6274547	Dissolved Uranium (U)	2019/08/15	91	80 - 120	90	80 - 120	<0.10	ug/L	8.2	20
6274547	Dissolved Vanadium (V)	2019/08/15	104	80 - 120	102	80 - 120	<0.50	ug/L	NC	20
6274547	Dissolved Zinc (Zn)	2019/08/15	100	80 - 120	99	80 - 120	<5.0	ug/L	NC	20
6274845	Chromium (VI)	2019/08/14	103	80 - 120	105	80 - 120	<0.50	ug/L	NC	20
6276929	Benzene	2019/08/13	95	70 - 130	102	70 - 130	<0.20	ug/L	NC	30
6276929	Ethylbenzene	2019/08/13	92	70 - 130	97	70 - 130	<0.20	ug/L	NC	30
6276929	F1 (C6-C10) - BTEX	2019/08/13					<25	ug/L	NC	30
6276929	F1 (C6-C10)	2019/08/13	85	70 - 130	98	70 - 130	<25	ug/L	NC	30
6276929	o-Xylene	2019/08/13	89	70 - 130	94	70 - 130	<0.20	ug/L	NC	30
6276929	p+m-Xylene	2019/08/13	92	70 - 130	97	70 - 130	<0.40	ug/L	NC	30



BUREAU  
VERITAS

BV Labs Job #: B9M1129  
Report Date: 2019/08/30

### QUALITY ASSURANCE REPORT(CONT'D)

exp Services Inc  
Client Project #: BRM-00607375-A0  
Site Location: 230 THE DONWAY W.  
Sampler Initials: AN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits
6276929	Toluene	2019/08/13	91	70 - 130	96	70 - 130	<0.20	ug/L	NC	30
6276929	Total Xylenes	2019/08/13					<0.40	ug/L	NC	30
6279824	F2 (C10-C16 Hydrocarbons)	2019/08/15	97	50 - 130	93	60 - 130	<100	ug/L	NC	30
6279824	F3 (C16-C34 Hydrocarbons)	2019/08/15	101	50 - 130	99	60 - 130	<200	ug/L	NC	30
6279824	F4 (C34-C50 Hydrocarbons)	2019/08/15	112	50 - 130	108	60 - 130	<200	ug/L	NC	30

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

Surrogate: A pure or isotopically labeled compound whose behavior mirrors the analytes of interest. Used to evaluate extraction efficiency.

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).



BUREAU  
VERITAS

BV Labs Job #: B9M1129  
Report Date: 2019/08/30

exp Services Inc  
Client Project #: BRM-00607375-A0  
Site Location: 230 THE DONWAY W.  
Sampler Initials: AN

### VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

---

Anastassia Hamanov, Scientific Specialist

---

Brad Newman, Scientific Service Specialist

---

---

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



BUREAU  
VERITAS

BV Labs Job #: B9M1129  
Report Date: 2019/08/30

exp Services Inc  
Client Project #: BRM-00607375-A0  
Site Location: 230 THE DONWAY W.  
Sampler Initials: AN

**Exceedence Summary Table – Toronto San/Stm Sewer  
Result Exceedences**

Sample ID	BV Labs ID	Parameter	Criteria	Result	DL	Units
No Exceedences						
The exceedence summary table is for information purposes only and should not be considered a comprehensive listing or statement of conformance to applicable regulatory guidelines.						

EXP Services Inc.

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

## Appendix E – Construction (Short-Term) and Post-Construction (Long-Term) Flow Rate Calculations

## APPENDIX E: Short-Term and Long-Term Flow Rates

230 The Donway West, Toronto, ON  
BRM-00607375-A0

Table E-1: Flow from Open Excavation and Under-Slab Drain System

P3

P3

Parameters	Symbols	Unit	Short-Term	Long-Term
Geological Formation	-	-	Glacial Deposit	Glacial Deposit
Ground Elevation	-	mASL	142.85	142.85
Highest Groundwater Elevation	-	mASL	142.01	142.01
Lowest Slab Elevation	-	mASL	133.30	133.30
Lowest Footing Elevation	-	mASL	131.80	136.00
Base of the Water-Bearing Zone	-	mASL	128.00	128.00
Height of Static Water Table Above the Base of the Water-Bearing Zone	<b>H</b>	m	14.01	14.01
Dewatering Target Elevation	-	mASL	130.80	132.80
Height of Target Water Level Above the Base of Water-Bearing Zone	<b>h<sub>w</sub></b>	m	2.80	4.80
Dupuit Criteria	<b>Hw/H</b>	%	20%	34%
Hydraulic Conductivity	<b>K</b>	m/s	1.5E-07	1.5E-07
Length of Excavation	-	m	156	156
Width of Excavation	-	m	65	65
Equivalent Radius (equivalent perimeter)	<b>r<sub>e</sub></b>	m	70	70
Method to Calculate Radius of Influence	-	-	<b>Cooper-Jacob</b>	<b>Cooper-Jacob</b>
Time (30 days for Short-Term and 3 years for Long-Term)	<b>t</b>	s	2592000	126144000
Specific Yield	<b>Sy</b>	-	0.20	0.05
Cooper-Jacob's Radius of Influence from Sides of Excavation	<b>R<sub>cj</sub></b>	m	8	109
Radius of Influence	<b>R<sub>o</sub></b>	m	78	180
Dewatering Flow Rate (unconfined radial flow component)	<b>Q</b>	m <sup>3</sup> /day	73	8
Factor of Safety	<b>fs</b>	-	2.00	1.50
Dewatering Flow Rate (multiplied by factor of safety)	<b>Q.fs</b>	m <sup>3</sup> /day	145	11
Precipitation Event	-	mm/day	15	-
Volume from Precipitation	-	m <sup>3</sup> /day	152	-
Dewatering Flow Rate <b>Without Safety Factor</b> (including stormwater collection)	-	m <sup>3</sup> /day	225	-
Dewatering Flow Rate <b>With Safety Factor</b> (including stormwater collection)	-	m <sup>3</sup> /day	298	-

### Notes:

mASL - meters above sea level

### Analytical Solution for Estimating Radial Flow from an Unconfined Aquifer to a Fully-Penetrating Excavation

$$Q_w = \frac{\pi K(H^2 - h^2)}{\ln \left[ \frac{R_o}{r_e} \right]} \quad \text{(Based on the Dupuit-Forcheimer Equation)}$$

$$r_e = \frac{a+b}{\pi} \quad R_o = R_{cj} + r_e \quad R_{cj} = \sqrt{2.25KDt/S}$$

Where:

Q<sub>w</sub> = Flow rate per unit length of excavation (m<sup>3</sup>/s)

K = Hydraulic conductivity (m/s)

H = Height of static water table above base of water-bearing zone (m)

h<sub>w</sub> = Height of target water level above the base of water-bearing zone (m)

R<sub>cj</sub> = Cooper Jacob Radius of Influence (m)

R<sub>o</sub> = Radius of influence (m)

r<sub>e</sub> = Equivalent perimeter (m)

S = Storativity

EXP Services Inc.

*Project Number: BRM- 00607375-A0*

*Date: September 23, 2019*

*Revision 1: May 28, 2021*

*Revision 2: October 20, 2021*

*Revision 3: January 13, 2022*

*Revision 4: October 31, 2023*

## Appendix F – Architectural Drawings



# 230 AND 240 THE DONWAY WEST

OFFICIAL PLAN AMENDMENT AND REZONING APPLICATION  
OCTOBER 24TH, 2023

A100	CONTEXT PLAN & STATISTICS
A101	SITE PLAN
A201	P3 PARKING PLAN
A202	P2 PARKING PLAN
A203	WALKOUT UNITS & P1 PARKING PLAN
A301	GROUND FLOOR PLAN
A302	2ND FLOOR PLAN
A303	3RD FLOOR PLAN
A304	4TH FLOOR PLAN
A305	5TH FLOOR PLAN
A306	6TH FLOOR PLAN
A401	NORTH & WEST ELEVATION
A402	SOUTH & EAST ELEVATION
A502	BUILDING SECTION
A503	BUILDING SECTION

**CLIENT:**  
DONWAY CO-OPERATIVE  
DEVELOPMENT CORPORATION AND  
THE DONWAY COVENANT UNITED  
CHURCH  
  
468 QUEEN ST. E.,  
TORONTO, ON,  
M5A 1T7  
  
TEL.: 416 340 8100

**ARCHITECT:**  
ARCHITECTURE UNFOLDED  
  
368 DUFFERIN ST.  
TORONTO, ONTARIO  
M6K 1Z8  
  
TEL: 416.601.5416


**HERITAGE ARCHITECT:**  
ERA ARCHITECTS INC.  
  
625 CHURCH ST.,  
SUITE 600, TORONTO  
ON, M5A 3S5  
  
TEL.: 416 340 8100

**PLANNING:**  
BOUSFIELDS INC  
  
3 CHURCH ST.,  
TORONTO, ON,  
M5E 1M2  
  
TEL.: 416 947 9744

**LANDSCAPE ARCHITECT:**  
O2 DESIGN (FORMERLY NAK DESIGN  
GROUP)  
  
400 RICHMOND ST E.,  
TORONTO, ON,  
M5A 3S5  
  
TEL.: 416 340 8100


**SITE SERVICES:**  
EXP  
  
220 COMMERCE VALLEY  
DRIVE WEST - SUITE 110  
MARKHAM, ON, L3T 0A8  
  
TEL.: 905 695 3217





### LEGEND

	DB	CATCH BASIN
	H.P.	HYDRO POLE
	MH	MANHOLE
	F.H.	FIRE HYDRANT
	B.B.	BOLLARD LIGHT REFER TO ELEC. DWGS



### SURVEY DATA

PLAN OF SURVEY AND TOPOGRAPHY OF BLOCK B, REGISTERED PLAN 4332, CITY OF TORONTO (FORMERLY CITY OF NORTH YORK), BEING ALL OF PIN 10117-0318

PREPARED BY: J D BARNES LTD., 140 RENFREW DRIVE, SUITE 100, MARKHAM, ON L3R 6B3 (905) 477-3882 JULY 15, 2019

### 230 AND 240 THE DONWAY WEST

#### 1. ZONING

1. ZONING	10,268.00 m <sup>2</sup>	110,523.73 ft <sup>2</sup>	2.54	ACRES
-----------	--------------------------	----------------------------	------	-------

#### 2. SITE AREA

PARK DEDICATION	513.42 m <sup>2</sup>	5,526.18 ft <sup>2</sup>		
0.4M ROAD ALLOWANCE	47.00 m <sup>2</sup>	505.90 ft <sup>2</sup>		
NET SITE AREA (INCLUDES 187 m <sup>2</sup> HYDRO EASEMENT)	9,707.58 m <sup>2</sup>	104,491.42 ft <sup>2</sup>	2.40	ACRES
<b>TOTAL SITE AREA</b>	<b>10,268.00 m<sup>2</sup></b>	<b>110,523.73 ft<sup>2</sup></b>	<b>2.54</b>	<b>ACRES</b>

#### 3. ESTABLISHED GRADE

141.69 m (AVERAGE GRADE AS PER BY-LAW)

#### 4. PROPOSED BUILDING:

AREA	22,390.8 m <sup>2</sup>	241,011.8 ft <sup>2</sup>
BUILDING AREA	3,850.25 m <sup>2</sup>	41,443.71 ft <sup>2</sup>
DENSITY	2.18 FSI (GFA / SA)	
UNITS	308	

#### 5. FLOOR AREA:

LEVEL	TOTAL FL. AREA (TFA)	DEDUCTIONS (AS PER BY-LAW)	GROSS FL. AREA (GFA)
U/G			
P3	1,093.0 m <sup>2</sup>	1,081.0 m <sup>2</sup>	12.0 m <sup>2</sup>
P2	5,162.0 m <sup>2</sup>	5,208.0 m <sup>2</sup>	35.2 m <sup>2</sup>
P1	4,778.0 m <sup>2</sup>	5,142.9 m <sup>2</sup>	0.00 m <sup>2</sup>
MECH. P.H.	484.0 m <sup>2</sup>	290.0 m <sup>2</sup>	144.0 m <sup>2</sup>
SUB TOTAL	11,467.0 m <sup>2</sup>	13,278.0 m <sup>2</sup>	198.2 m <sup>2</sup>
U/G RES.			
P1	2,089.0 m <sup>2</sup>	91.0 m <sup>2</sup>	1,998.0 m <sup>2</sup>
LEVEL	TOTAL FL. AREA (TFA)	DEDUCTIONS (AS PER BY-LAW)	GROSS FL. AREA (GFA)
GF.	3,107.0 m <sup>2</sup>	10,677.8 m <sup>2</sup>	2,115.0 m <sup>2</sup>
2ND	4,020.0 m <sup>2</sup>	2,012.8 m <sup>2</sup>	41,258.0 m <sup>2</sup>
SUB TOTAL	7,127.0 m <sup>2</sup>	12,690.6 m <sup>2</sup>	5,948.0 m <sup>2</sup>
U/G CHURCH			
GF.	743.3 m <sup>2</sup>	9.00 m <sup>2</sup>	734.3 m <sup>2</sup>
SUB TOTAL	743.3 m <sup>2</sup>	9.00 m <sup>2</sup>	734.3 m <sup>2</sup>
U/G TYP.			
3RD	3,695.0 m <sup>2</sup>	80.0 m <sup>2</sup>	3,615.0 m <sup>2</sup>
4TH	3,098.0 m <sup>2</sup>	80.0 m <sup>2</sup>	3,018.0 m <sup>2</sup>
5TH	3,415.0 m <sup>2</sup>	80.0 m <sup>2</sup>	3,335.0 m <sup>2</sup>
6TH	3,029.0 m <sup>2</sup>	80.0 m <sup>2</sup>	2,949.0 m <sup>2</sup>
TOTAL	13,241.5 m <sup>2</sup>	320.0 m <sup>2</sup>	12,921.5 m <sup>2</sup>
RES. TOTAL	23,057.5 m <sup>2</sup>	1,590.0 m <sup>2</sup>	21,656.5 m <sup>2</sup>
GRAND TOTAL	35,267.8 m <sup>2</sup>	12,877.0 m <sup>2</sup>	22,390.8 m <sup>2</sup>

#### 6. UNIT SUMMARY

FLOOR	BACK	1B	1B+D	2B	2B+D	3B	Podium Towns	TOTAL
P1	2	2	2	7	4	8	0	25
GF.	1	2	10	7	2	6	4	27
2ND	1	9	21	12	5	6	0	54
3RD	0	12	21	6	12	4	0	55
4TH	0	12	21	9	8	5	0	55
5TH	4	11	9	11	10	2	0	47
6TH	4	9	8	13	10	1	0	45
TOTAL	11	57	92	65	51	32	-	308
CLIENT TARGET	3.0%	18.5%	29.9%	21.1%	16.6%	10.4%	-	100.0%
	5.0%	20.0%	25.0%	25.0%	15.0%	10.0%	-	100.0%

#### 7. ACCESSIBLE UNITS

FLOOR	BACK	1B	1B+D	2B	2B+D	3B	TOTAL
P1	0	0	0	0	0	0	0
GF.	0	1	2	1	1	1	6
2ND	0	1	4	1	1	1	8
3RD	0	1	3	3	2	1	10
4TH	0	1	2	3	1	1	8
5TH	0	1	2	1	1	1	6
6TH	0	1	2	1	1	1	6
TOTAL (15% for the building)	0	6	15	10	9	6	46

#### 8. EFFICIENCY (NSA/GFA)

PERMITTED:	TBA	PROPOSED:	6.51% (21.31m)
------------	-----	-----------	----------------

#### 9. HEIGHT

MECH. P.H. (EXCL.)	Max. 8.00 m FOR 40% OF ROOF AREA	MECH. P.H. (EXCL.)	= 376 m <sup>2</sup> (14% OF ROOF AREA)
	+ Max. 10.00 m FOR 25% OF ROOF AREA		

#### 10. PARKING

REQUIRED (MAX)	0.8 PER UNIT	11	=	9
1B	0.9 PER UNIT	149	=	134
2B	1 PER UNIT	116	=	116
3B+	1.2 PER UNIT	32	=	38
CHURCH	MAX. 6 PER 100 m <sup>2</sup> OF WORKSPACE (143M <sup>2</sup> )		=	44
TOTAL			=	341
VS. (MIN)	0.05 PER UNIT "I"	308	=	17

#### 11. ELECTRICAL VEHICLE

REQUIRED	(LEV 2 EVEL) 100% OF RES & 25% OF VIS = All remaining to have EV ROUGH-INS	338	PROPOSED:	(LEV 1 EVEL) 100% OF RES & 25% OF VIS = All remaining to have EV ROUGH-INS	228	Provided
----------	--	-----	-----------	--	-----	----------

#### 12. ACCESSIBLE PARKING

REQUIRED:	11 Spaces	PROPOSED:	RES. 9
			VIS. 1
			CHURCH 1
			TOTAL 11

#### 13. LOCKERS

REQUIRED:	11 Spaces	PROPOSED: (72%)	A/G 0
			U/G 222
			TOTAL 222

#### 14. BICYCLE

REQUIRED:	11 Spaces	PROPOSED:	RESIDENTIAL 22
			(120 Ground Floor + 90 P1) 210
			TOTAL 232

#### 15. INDOOR AMENITY

REQUIRED:	RES. 2 m <sup>2</sup> / UNIT ( 308 ) = (m <sup>2</sup> ) 616	PROPOSED:	1.55 m <sup>2</sup> / U
			477.40 m <sup>2</sup>
			5,138.69 ft <sup>2</sup>

#### 16. BREAKDOWN

P1	76.00 m <sup>2</sup>	818.06 ft <sup>2</sup>
GROUND FL.	383.40 m <sup>2</sup>	4,126.88 ft <sup>2</sup>
2ND FL.	18.00 m <sup>2</sup>	193.75 ft <sup>2</sup>
TOTAL	477.40 m <sup>2</sup>	5,138.69 ft <sup>2</sup>

#### 17. PART OF GFA

AMENITY INCL. IN GFA	477.40 m <sup>2</sup>	5,138.69 ft <sup>2</sup>
----------------------	-----------------------	--------------------------

#### 18. OUTDOOR AMENITY

REQUIRED:	RES. 2 m <sup>2</sup> / UNIT ( 308 ) = (m <sup>2</sup> ) 616	PROPOSED:	1.50 m <sup>2</sup> / U
			462.00 m <sup>2</sup>
			4,972.92 ft <sup>2</sup>

#### 19. BREAKDOWN

OUTDOOR AMENITY	383.00 m <sup>2</sup>	4,122.57 ft <sup>2</sup>
KIDS SPACE	99.00 m <sup>2</sup>	1,065.63 ft <sup>2</sup>
OUTDOOR WORKOUT	67.00 m <sup>2</sup>	721.38 ft <sup>2</sup>
TOTAL	549.00 m <sup>2</sup>	5,909.58 ft <sup>2</sup>

#### 20. LANDSCAPED OPEN SPACE

REQUIRED:	SITE AREA 10,268.00 m <sup>2</sup>	PROVIDED:	SITE AREA 10,268.00 m <sup>2</sup>
	REQUIRED OPEN SPACE ON SITE 45.8%		45.8%
	TOTAL 3,080.00 m <sup>2</sup>		4,680.3 m <sup>2</sup>

#### 21. SOFTSCAPE

REQUIRED:	SOFTSCAPE N/A m <sup>2</sup>	PROVIDED:	SOFTSCAPE 2,660.69 m <sup>2</sup>
	HARDSCAPE N/A m <sup>2</sup>		HARDSCAPE 1,786.69 m <sup>2</sup>
	TOTAL N/A m <sup>2</sup>		4,388.0 m <sup>2</sup>

#### 22. REFUSE

REQUIRED:	GARBAGE ROOM AREA 46 m <sup>2</sup>	PROVIDED:	GARBAGE ROOM AREA ( P1 LEVEL) 76 m <sup>2</sup>
	BULK AREA 10 m <sup>2</sup>		BULK AREA 54 m <sup>2</sup>
	BIN STAGING AREA 31 m <sup>2</sup>		BIN STAGING AREA 58 m <sup>2</sup>

#### 23. LOADING SPACES

REQUIRED:	TYPE G (13m L X 4m W X 6.1m H)	PROVIDED:	TYPE G (13m L X 4m W X 6.1m H)
-----------	--------------------------------	-----------	--------------------------------

The drawings are the property of Architecture unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplementary information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the consistency of the represented by them, of contractor or subcontractors must satisfy themselves when bidding and of all times that they can properly construct the work represented by these plans.

revisions:

- 12 ISSUED FOR REZONING 2023.10.24
- 11 ISSUED FOR REZONING 2022.03.09
- 10 DRAFT REZONING SUBMISSION 2022.01.18
- 9 DRAFT REZONING SUBMISSION 2021.05.21
- 8 SUBMISSION FOR CONSULTANTS COORDINATION 2021.04.20
- 7 SUBMISSION FOR CONSULTANTS COORDINATION 2021.01.21
- 6 SUBMISSION FOR CONSULTANTS COORDINATION 2020.12.23
- 5 ISSUED FOR CLIENT REVIEW 2020.11.27
- 4 PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING 2019.11.08
- 3 ISSUED FOR CLIENT 2019.10.20
- 2 ISSUED FOR CLIENT REVIEW 2019.09.30
- 1 FEASIBILITY SUBMISSION 2018.03.20

revisions: dd-mm-yy

architectural team:

Eduardo Ortiz

interior design:

planning: BOUSFIELDS INC

structural:

electrical:

mechanical:

landscape: O2 DESIGN (FORMELY NAK DESIGN GROUP)

site services: EXP

owner: DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project: 230 THE DONWAY WEST  
230 The Donway W., North York, ON

CONTEXT PLAN & STATISTICS

2023.10.24 date:  
1 : 500 scale:  
18-16 project:  
Author drawn by:  
drawing number: A100

NOTE: BE ADVISED THAT SHOULD ANY PARTY, INCLUDING THE OWNER OR ANY SUBSEQUENT OWNER, APPLY FOR MORE THAN ONE CONDOMINIUM CORPORATION ENCOMPASSING ANY OR ALL OF THIS DEVELOPMENT OR MAKE AN APPLICATION THAT RESULTS IN A LAND DIVISION, STAFF MAY REQUIRE LEGAL ASSURANCES, INCLUDING BUT NOT LIMITED TO EASEMENTS, WITH RESPECT TO THE APPROVED SERVICES. SUCH ASSURANCES WILL BE DETERMINED AT THE TIME OF APPLICATION FOR CONDOMINIUM APPROVAL.

The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplement information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.


Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the constructability of the represented work. All contractors or subcontractors must satisfy themselves when bidding and at all times that they can properly construct the work represented by these plans.

notes:



12	ISSUED FOR REZONING	2023.10.24
11	ISSUED FOR REZONING	2022.03.09
10	DRAFT REZONING SUBMISSION	2022.01.18
9	DRAFT REZONING SUBMISSION	2021.05.21
8	SUBMISSION FOR CONSULTANTS COORDINATION	2021.04.20
7	SUBMISSION FOR CONSULTANTS COORDINATION	2021.01.21
6	SUBMISSION FOR CONSULTANTS COORDINATION	2020.12.23
5	ISSUED FOR CLIENT REVIEW	2020.11.27
4	PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING	2019.11.08
3	ISSUED FOR CLIENT	2019.10.20
2	ISSUED FOR CLIENT REVIEW	2019.09.30
1	FEASIBILITY SUBMISSION	2018.03.20

revisions: dd-mm-yy


architectural team :  
 Eduardo Ortiz

interior design:  
 BOUSFIELDS INC  
 structural:  
 electrical:  
 mechanical:  
 landscape:  
 O2 DESIGN (FORMERLY NAK DESIGN GROUP)  
 site services:  
 EXP  
 owner:  
 DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project:  
 230 THE DONWAY WEST  
 230 The Donway W., North York, ON

SITE PLAN

2023.10.24 date:  
 1 : 200 scale:  
 18-16 project:  
 Author drawing number:



A101

The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplement information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conference only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the constructability of the represented by them. All contractors or subcontractors must satisfy themselves when bidding and/or at all times that they can properly construct the work represented by these plans.

- notes:**
- All residential parking spaces provided for dwelling units located in an apartment building, mixed use building, multiple dwelling unit building, excluding visitor parking spaces, will include an energized outlet capable of providing Level 2 charging or higher to the parking space. Specify which strategy is used: a dedicated electrical outlet, receptacle, or EVSE supplied by a separate branch circuit or using Electric Vehicle Energy Management Systems (EVEMS) load sharing technologies.
  - Level 2 Charging means a Level 2 electric vehicle charging level as defined by SAE International's J1772 standard, as amended (208V to 240V single-phase power, with maximum current of 80A).
  - 25% of all visitor residential spaces and non-residential parking spaces in a building must include an energized outlet capable of providing Level 2 charging or higher.
  - Energized Outlet means a connected point in an electrical wiring installation at which current is taken to supply utilization equipment for electric vehicle charging.

12	ISSUED FOR REZONING	2023.10.24
11	ISSUED FOR REZONING	2022.03.09
10	DRAFT REZONING SUBMISSION	2022.01.18
9	DRAFT REZONING SUBMISSION	2021.05.21
8	SUBMISSION FOR CONSULTANTS COORDINATION	2021.04.20
7	SUBMISSION FOR CONSULTANTS COORDINATION	2021.01.21
6	SUBMISSION FOR CONSULTANTS COORDINATION	2020.12.23
5	ISSUED FOR CLIENT REVIEW	2020.11.27
4	PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING	2019.11.08
3	ISSUED FOR CLIENT	2019.10.20
2	ISSUED FOR CLIENT REVIEW	2019.09.30
1	FEASIBILITY SUBMISSION	2018.03.20

revisions: dd-mm-yy

architectural team :

Eduardo Ortiz

interior design:

planning:  
BOUSFIELDS INC

structural:

electrical:

mechanical:

landscape:

O2 DESIGN (FORMERLY NAK DESIGN GROUP)

site services:  
EXP

owner:  
DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project:  
230 THE DONWAY WEST  
230 The Donway W., North York, ON

**P3 PARKING PLAN**

2023.10.24

1 : 200

18-16

Author

due north

project north

drawing number:  
**A201**



The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplement information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conference only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the constructability of the represented by them, all contractor or subcontractors must satisfy themselves when bidding and/or at all times that they can properly construct the work represented by these plans.

**notes:**

- All residential parking spaces provided for dwelling units located in an apartment building, mixed use building, multiple dwelling unit building, excluding visitor parking spaces, will include an energized outlet capable of providing Level 2 charging or higher to the parking space. Specify which strategy is used: a dedicated electrical outlet, receptacle, or EVSE supplied by a separate branch circuit or using Electric Vehicle Energy Management Systems (EVEMS) load sharing technologies.
- Level 2 Charging means a Level 2 electric vehicle charging level as defined by SAE International's J1772 standard, as amended (208V to 240V single-phase power, with maximum current of 80A).
- 25% of all visitor residential spaces and non-residential parking spaces in a building must include an energized outlet capable of providing Level 2 charging or higher.
- Energized Outlet means a connected point in an electrical wiring installation at which current is taken to supply utilization equipment for electric vehicle charging.

11	ISSUED FOR REZONING	2022.03.09
10	DRAFT REZONING SUBMISSION	2022.01.18
9	DRAFT REZONING SUBMISSION	2021.05.21
8	SUBMISSION FOR CONSULTANTS COORDINATION	2021.04.20
7	SUBMISSION FOR CONSULTANTS COORDINATION	2021.01.21
6	SUBMISSION FOR CONSULTANTS COORDINATION	2020.12.23
5	ISSUED FOR CLIENT REVIEW	2020.11.27
4	PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING	2019.11.08
3	ISSUED FOR CLIENT	2019.10.20
2	ISSUED FOR CLIENT REVIEW	2019.09.30
1	FEASIBILITY SUBMISSION	2018.03.20

revisions: dd-mm-yy

architectural team :

Eduardo Ortiz

interior design:

planning: BOUSFIELDS INC

structural:

electrical:

mechanical:

landscape: O2 DESIGN (FORMERLY NAK DESIGN GROUP)


site services: EXP

owner: DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project: 230 THE DONWAY WEST  
230 The Donway W., North York, ON

**P2 PARKING PLAN**

2023.10.24 date:  
1 : 200 scale:  
18-16 project:  
Author drawn by:  
drawing number:  
**A202**



P1 Total Parking	97
P1 Total Bicycle parking	90

The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written clarification or supplement information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conference only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the constructability of the represented by them. All contractors or subcontractors must satisfy themselves when bidding and/or at all times that they can properly construct the work represented by these plans.

**notes:**

- All residential parking spaces provided for dwelling units located in an apartment building, mixed use building, multiple dwelling unit building, excluding visitor parking spaces, will include an energized outlet capable of providing Level 2 charging or higher to the parking space. Specify which strategy is used: a dedicated electrical outlet, receptacle, or EVSE supplied by a separate branch circuit or using Electric Vehicle Energy Management Systems (EVEMS) load sharing technologies.
- Level 2 Charging means a Level 2 electric vehicle charging level as defined by SAE International's J1772 standard, as amended (208V to 240V single-phase power, with maximum current of 80A).
- 25% of all visitor residential spaces and non-residential parking spaces in a building must include an energized outlet capable of providing Level 2 charging or higher.
- Energized Outlet means a connected point in an electrical wiring installation at which current is taken to supply utilization equipment for electric vehicle charging.

11 ISSUED FOR REZONING	2022.03.09
10 DRAFT REZONING SUBMISSION	2022.01.18
9 DRAFT REZONING SUBMISSION	2021.05.21
8 SUBMISSION FOR CONSULTANTS COORDINATION	2021.04.20
7 SUBMISSION FOR CONSULTANTS COORDINATION	2021.01.21
6 SUBMISSION FOR CONSULTANTS COORDINATION	2020.12.23
5 ISSUED FOR CLIENT REVIEW	2020.11.27
4 PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING	2019.11.08
3 ISSUED FOR CLIENT REVIEW	2019.10.20
2 ISSUED FOR CLIENT REVIEW	2019.09.30
1 FEASIBILITY SUBMISSION	2018.03.20

revisions: dd-mm-yy

**architectural team :**

Eduardo Ortiz

interior design:

planning: BOUSFIELDS INC

structural:

electrical:

mechanical:

landscape: O2 DESIGN (FORMERLY NAK DESIGN GROUP)

site services: EXP

owner: DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH


project: 230 THE DONWAY WEST  
230 The Donway W., North York, ON

**WALKOUT UNITS & P1 PARKING PLAN**

2023.10.24 date:  
1 : 200 scale:  
18-16 project:  
Author drawn by:

due north project north

drawing number: **A203**



The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplementary information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.


These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the constructability of the represented by them. All contractor or subcontractors must satisfy themselves when bidding and at all times that they can properly construct the work represented by these plans.

notes:

P1 Total Bicycle parking  
120



12	ISSUED FOR REZONING	2023.10.24
11	ISSUED FOR REZONING	2022.03.09
10	DRAFT REZONING SUBMISSION	2022.01.18
9	DRAFT REZONING SUBMISSION	2021.05.21
8	SUBMISSION FOR CONSULTANTS COORDINATION	2021.04.20
7	SUBMISSION FOR CONSULTANTS COORDINATION	2021.01.21
6	SUBMISSION FOR CONSULTANTS COORDINATION	2020.12.23
5	ISSUED FOR CLIENT REVIEW	2020.11.27
4	PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING	2019.11.08
3	ISSUED FOR CLIENT REVIEW	2019.10.20
2	ISSUED FOR CLIENT REVIEW	2019.09.30
1	FEASIBILITY SUBMISSION	2018.03.20

revisions: dd-mm-yy

architectural team :  
Eduardo Ortiz


interior design:  
planning: BOUSFIELDS INC  
structural:  
electrical:  
mechanical:  
landscape: O2 DESIGN (FORMELY NAK DESIGN GROUP)  
site services: EXP  
owner: DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project:  
230 THE DONWAY WEST  
230 The Donway W., North York, ON

GROUND FLOOR PLAN

2023.10.24 date:  
1 : 200 scale:  
18-16 project:  
Author drawn by:

drawing number:  
A301



The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplementary information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the constructability of the represented by them. All contractor or subcontractors must satisfy themselves when bidding and/or at all times that they can properly construct the work represented by these plans.

notes:

- |    |  |            |
|----|--|------------|
| 12 | ISSUED FOR REZONING                                  | 2023.10.24 |
| 11 | ISSUED FOR REZONING                                  | 2022.03.09 |
| 10 | DRAFT REZONING SUBMISSION                            | 2022.01.18 |
| 9  | DRAFT REZONING SUBMISSION                            | 2021.05.21 |
| 8  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2021.04.20 |
| 7  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2021.01.21 |
| 6  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2020.12.23 |
| 5  | ISSUED FOR CLIENT REVIEW                             | 2020.11.27 |
| 4  | PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING | 2019.11.08 |
| 3  | ISSUED FOR CLIENT                                    | 2019.10.20 |
| 2  | ISSUED FOR CLIENT REVIEW                             | 2019.09.30 |
| 1  | FEASIBILITY SUBMISSION                               | 2018.03.20 |
- revisions: dd-mm-yy

architectural team :

Eduardo Ortiz

interior design:

planning: BOUSFIELDS INC

structural:

electrical:

mechanical:

landscape: O2 DESIGN (FORMERLY NAK DESIGN GROUP)

site services:

EXP

owner: DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project: 230 THE DONWAY WEST  
230 The Donway W., North York, ON

2ND FLOOR PLAN


2023.10.24

1 : 200


18-16

Author

date:  
scale:  
project:  
drawing number:



A302



The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic certification or supplementary information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the availability of the represented by them, or contractor or subcontractors must satisfy themselves when bidding and/or at all times that they can properly construct the work represented by these plans.

**notes:**

- |    |  |            |
|----|--|------------|
| 12 | ISSUED FOR REZONING                                  | 2023.10.24 |
| 11 | ISSUED FOR REZONING                                  | 2022.03.09 |
| 10 | DRAFT REZONING SUBMISSION                            | 2022.01.18 |
| 9  | DRAFT REZONING SUBMISSION                            | 2021.05.21 |
| 8  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2021.04.20 |
| 7  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2021.01.21 |
| 6  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2020.12.23 |
| 5  | ISSUED FOR CLIENT REVIEW                             | 2020.11.27 |
| 4  | PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING | 2019.11.08 |
| 3  | ISSUED FOR CLIENT REVIEW                             | 2019.10.20 |
| 2  | ISSUED FOR CLIENT REVIEW                             | 2019.09.30 |
| 1  | FEASIBILITY SUBMISSION                               | 2018.03.20 |
- revisions: dd-mm-yy

**architectural team :**


- Eduardo Ortiz
- interior design:
- planning: BOUSFIELDS INC
- structural:
- electrical:
- mechanical:
- landscape: O2 DESIGN (FORMERLY NAK DESIGN GROUP)
- site services: EXP
- owner: DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project:  
230 THE DONWAY WEST  
230 The Donway W., North York, ON


**3RD FLOOR PLAN**

2023.10.24  
1 : 200  
18-16  
Author

date:  
scale:  
project:  
drawn by:



drawing number:  
**A303**





The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic certification or supplementary information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the consistency of the represented by them, or contractor or subcontractors must satisfy themselves when bidding and/or at all times that they can properly construct the work represented by these plans.

notes:



12	ISSUED FOR REZONING	2023.10.24
11	ISSUED FOR REZONING	2022.03.09
10	DRAFT REZONING SUBMISSION	2022.01.18
9	DRAFT REZONING SUBMISSION	2021.05.21
8	SUBMISSION FOR CONSULTANTS COORDINATION	2021.04.20
7	SUBMISSION FOR CONSULTANTS COORDINATION	2021.01.21
6	SUBMISSION FOR CONSULTANTS COORDINATION	2020.12.23
5	ISSUED FOR CLIENT REVIEW	2020.11.27
4	PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING	2019.11.08
3	ISSUED FOR CLIENT	2019.10.20
2	ISSUED FOR CLIENT REVIEW	2019.09.30
1	FEASIBILITY SUBMISSION	2018.03.20

revisions: dd-mm-yy

architectural team :  
Eduardo Ortiz




interior design:  
BOUSFIELDS INC  
structural:  
electrical:  
mechanical:  
landscape:  
O2 DESIGN (FORMERLY NAK DESIGN GROUP)  
site services:  
EXP  
owner:  
DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project:  
230 THE DONWAY WEST  
230 The Donway W., North York, ON

4TH FLOOR PLAN

2023.10.24 date:  
1 : 200 scale:  
18-16 project:  
Author drawn by:



The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplementary information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the availability of the represented by them, all contractors or subcontractors must satisfy themselves when bidding and/or at all times that they can properly construct the work represented by these plans.

notes:

- |    |  |            |
|----|--|------------|
| 12 | ISSUED FOR REZONING                                  | 2023.10.24 |
| 11 | ISSUED FOR REZONING                                  | 2022.03.09 |
| 10 | DRAFT REZONING SUBMISSION                            | 2022.01.18 |
| 9  | DRAFT REZONING SUBMISSION                            | 2021.05.21 |
| 8  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2021.04.20 |
| 7  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2021.01.21 |
| 6  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2020.12.23 |
| 5  | ISSUED FOR CLIENT REVIEW                             | 2020.11.27 |
| 4  | PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING | 2019.11.08 |
| 3  | ISSUED FOR CLIENT                                    | 2019.10.20 |
| 2  | ISSUED FOR CLIENT REVIEW                             | 2019.09.30 |
| 1  | FEASIBILITY SUBMISSION                               | 2018.03.20 |
- revisions: dd-mm-yy

architectural team :

Eduardo Ortiz

interior design:

planning: BOUSFIELDS INC

structural:

electrical:

mechanical:

landscape: O2 DESIGN (FORMERLY NAK DESIGN GROUP)

site services: EXP

owner: DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project: 230 THE DONWAY WEST  
230 The Donway W., North York, ON


5TH FLOOR PLAN

2023.10.24


1 : 200

Author

date:  
scale:  
project:  
drawing number:



A305



The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplementary information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the constructability of the represented by them. All contractor or subcontractors must satisfy themselves when bidding and/or at all times that they can properly construct the work represented by these plans.

notes:

12	ISSUED FOR REZONING	2023.10.24
11	ISSUED FOR REZONING	2022.03.09
10	DRAFT REZONING SUBMISSION	2022.01.18
9	DRAFT REZONING SUBMISSION	2021.05.21
8	SUBMISSION FOR CONSULTANTS COORDINATION	2021.04.20
7	SUBMISSION FOR CONSULTANTS COORDINATION	2021.01.21
6	SUBMISSION FOR CONSULTANTS COORDINATION	2020.12.23
5	ISSUED FOR CLIENT REVIEW	2020.11.27
4	PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING	2019.11.08
3	ISSUED FOR CLIENT REVIEW	2019.10.20
2	ISSUED FOR CLIENT REVIEW	2019.09.30
1	FEASIBILITY SUBMISSION	2018.03.20
revisions:		dd-mm-yy

architectural team :

Eduardo Ortiz

interior design:  
 BOUSFIELDS INC  
 structural:  
 electrical:  
 mechanical:  
 landscape:  
 O2 DESIGN (FORMERLY NAK DESIGN GROUP)  
 site services:  
 EXP  
 owner:  
 DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project:  
 230 THE DONWAY WEST  
 230 The Donway W., North York, ON

6TH FLOOR PLAN

2023.10.24 date:  
 1 : 200 scale:  
 18-16 project:  
 Author drawn by:

due north project north  
 drawing number:  
**A306**



The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplementary information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly indicated will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the consistency of the represented by them, all contractor or subcontractors must satisfy themselves when bidding and at all times that they can properly construct the work represented by these plans.

**notes:**

12	ISSUED FOR REZONING	2023.10.24
11	ISSUED FOR REZONING	2022.03.09
10	DRAFT REZONING SUBMISSION	2022.01.18
9	DRAFT REZONING SUBMISSION	2021.05.21
8	SUBMISSION FOR CONSULTANTS COORDINATION	2021.04.20
7	SUBMISSION FOR CONSULTANTS COORDINATION	2021.01.21
6	SUBMISSION FOR CONSULTANTS COORDINATION	2020.12.23
5	ISSUED FOR CLIENT REVIEW	2020.11.27
4	PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING	2019.11.08
3	ISSUED FOR CLIENT	2019.10.20
2	ISSUED FOR CLIENT REVIEW	2019.09.30
1	FEASIBILITY SUBMISSION	2018.03.20

revisions: dd-mm-yy

**architectural team :**

Eduardo Ortiz

interior design:

planning:  
BOUSFIELDS INC

structural:

electrical:

mechanical:

landscape:  
O2 DESIGN (FORMERLY NAK DESIGN GROUP)

site services:  
EXP

owner:  
DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project:  
230 THE DONWAY WEST  
230 The Donway W., North York, ON

**ROOF FLOOR PLAN**

2023.10.24


1 : 200

18-16


Author

due north

project north



drawing number:  
**A308**



The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplementary information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the Mechanical and Electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the constructability of the represented by them, all contractor or subcontractors must satisfy themselves when bidding and/or at all times that they can properly construct the work represented by these plans.

**notes:**

12	ISSUED FOR REZONING	2023.10.24
11	ISSUED FOR REZONING	2022.03.09
10	DRAFT REZONING SUBMISSION	2022.01.18
9	DRAFT REZONING SUBMISSION	2021.05.21
8	SUBMISSION FOR CONSULTANTS COORDINATION	2021.04.20
7	SUBMISSION FOR CONSULTANTS COORDINATION	2021.01.21
6	SUBMISSION FOR CONSULTANTS COORDINATION	2020.12.23
5	ISSUED FOR CLIENT REVIEW	2020.11.27
4	PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING	2019.11.08
3	ISSUED FOR CLIENT	2019.10.20
2	ISSUED FOR CLIENT REVIEW	2019.09.30
1	FEASIBILITY SUBMISSION	2018.03.20

revisions: dd-mm-yy

**architectural team :**

Eduardo Ortiz

interior design:

planning:  
BOUSFIELDS INC

structural:

electrical:

mechanical:

landscape:  
O2 DESIGN (FORMERLY NAK DESIGN GROUP)

site services:  
EXP

owner:  
DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project:  
230 THE DONWAY WEST  
230 The Donway W., North York, ON

**NORTH & WEST ELEVATION**

2023.10.24

1 : 250

18-16


Author

date:


scale:

project:


drawn by:



drawing number:  
**A401**



**3 WEST**  
A401 1 : 250



**1 NORTH**  
A401 1 : 250

The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplementary information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the constructability of the represented by them. All contractors or subcontractors must satisfy themselves when bidding and/or at all times that they can properly construct the work represented by these plans.

**notes:**

- |    |  |            |
|----|--|------------|
| 12 | ISSUED FOR REZONING                                  | 2023.10.24 |
| 11 | ISSUED FOR REZONING                                  | 2022.03.09 |
| 10 | DRAFT REZONING SUBMISSION                            | 2022.01.18 |
| 9  | DRAFT REZONING SUBMISSION                            | 2021.05.21 |
| 8  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2021.04.20 |
| 7  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2021.01.21 |
| 6  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2020.12.23 |
| 5  | ISSUED FOR CLIENT REVIEW                             | 2020.11.27 |
| 4  | PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING | 2019.11.08 |
| 3  | ISSUED FOR CLIENT                                    | 2019.10.20 |
| 2  | ISSUED FOR CLIENT REVIEW                             | 2019.09.30 |
| 1  | FEASIBILITY SUBMISSION                               | 2018.03.20 |
- revisions: dd-mm-yy

**architectural team :**

Eduardo Ortiz



interior design:

planning:  
BOUSFIELDS INC  
structural:

electrical:

mechanical:

landscape:  
O2 DESIGN (FORMELY NAK DESIGN GROUP)

site services:  
EXP

owner:  
DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project:  
230 THE DONWAY WEST  
230 The Donway W., North York, ON

**SOUTH & EAST ELEVATION**


2023.10.24

1 : 250


18-16

Author


date:  
scale:  
project:  
drawn by:





drawing number:  
**A402**




**2 EAST**  
A402 1 : 250



**1 SOUTH**  
A402 1 : 250



1 SECTION 1  
A502 1:200



2 SECTION 2  
A502 1:200

The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplementary information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the Mechanical and Electrical drawings. Those items not clearly indicated will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the constructability of the represented by them. All contractors or subcontractors must satisfy themselves when bidding and/or at all times that they can properly construct the work represented by these plans.

Notes:

- 12 ISSUED FOR REZONING 2023.10.24
- 11 ISSUED FOR REZONING 2022.03.09
- 10 DRAFT REZONING SUBMISSION 2022.01.18
- 9 DRAFT REZONING SUBMISSION 2021.05.21
- 8 SUBMISSION FOR CONSULTANTS COORDINATION 2021.04.20
- 7 SUBMISSION FOR CONSULTANTS COORDINATION 2021.01.21
- 6 SUBMISSION FOR CONSULTANTS COORDINATION 2020.12.23
- 5 ISSUED FOR CLIENT REVIEW 2020.11.27
- 4 PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING 2019.11.08
- 3 ISSUED FOR CLIENT 2019.10.20
- 2 ISSUED FOR CLIENT REVIEW 2019.09.30
- 1 FEASIBILITY SUBMISSION 2018.03.20

revisions: dd-mm-yy

architectural team:

Eduardo Ortiz

interior design:

planning: BOUSFIELDS INC  
structural:

electrical:  
mechanical:

landscape: O2 DESIGN (FORMERLY NAK DESIGN GROUP)

site services: EXP

owner: DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project: 230 THE DONWAY WEST  
230 The Donway W., North York, ON

BUILDING SECTION

2023.10.24 date:


1:200 scale:

18-16 project:

Author drawn by:

due north project north drawing number:

A502



1 SECTION 3  
A503 1 : 200

The drawings are the property of Architecture Unfolded. The drawing and all associated documents are an instrument of service by the Designer. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the designer.

These Contract Documents are the property of the architect. The architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application the architect will provide written graphic clarification or supplementary information regarding the intent of the Contract Documents. The architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the architect before commencing work.

Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the mechanical and electrical drawings. Those items not clearly located will be located as directed by the architect.

These drawings are not to be used for construction unless noted below as "Issued for Construction".

All work to be carried out in conformance with the Code and bylaws of the authorities having jurisdiction.

The Designer of these plans and specifications gives no warranty or representation to any party about the constructability of the represented by them, all contractor or subcontractors must satisfy themselves when bidding and/or at all times that they can properly construct the work represented by these plans.

notes:

- |    |  |            |
|----|--|------------|
| 12 | ISSUED FOR REZONING                                  | 2023.10.24 |
| 11 | ISSUED FOR REZONING                                  | 2022.03.09 |
| 10 | DRAFT REZONING SUBMISSION                            | 2022.01.18 |
| 9  | DRAFT REZONING SUBMISSION                            | 2021.05.21 |
| 8  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2021.04.20 |
| 7  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2021.01.21 |
| 6  | SUBMISSION FOR CONSULTANTS COORDINATION              | 2020.12.23 |
| 5  | ISSUED FOR CLIENT REVIEW                             | 2020.11.27 |
| 4  | PRE-APPLICATION CONSULTATION WITH COMMUNITY PLANNING | 2019.11.08 |
| 3  | ISSUED FOR CLIENT                                    | 2019.10.20 |
| 2  | ISSUED FOR CLIENT REVIEW                             | 2019.09.30 |
| 1  | FEASIBILITY SUBMISSION                               | 2018.03.20 |
- revisions: dd-mm-yy

architectural team :

Eduardo Ortiz

interior design:

planning:  
BOUSFIELDS INC

structural:

electrical:

mechanical:

landscape:  
O2 DESIGN (FORMELY NAK DESIGN GROUP)

site services:  
EXP

owner:  
DONWAY CO-OPERATIVE DEVELOPMENT CORPORATION AND THE DONWAY COVENANT UNITED CHURCH

project:  
230 THE DONWAY WEST  
230 The Donway W., North York, ON

BUILDING SECTION


2023.10.24

1 : 200

18-16

Author

due north



date:

scale:

project:

drawn by:

drawing number:

A503